



Infrastructure, environment, facilities.

FILE

Imagine the result



SDMS DocID


2095155


Facility Vapor Intrusion Evaluation Summary


Former Bally Engineered Structures Facility
Bally Borough, Berks County, Pennsylvania

December 2006

ARCADIS


Christopher T. Sharpe
Project Scientist


Diane D. Wisbeck
Senior Scientist


Frank C. Natitus, P.E.
Senior Engineer

**Facility Vapor Intrusion
Evaluation Summary**

Former Bally Engineered
Structures Facility

Prepared for:
Sunbeam, Inc.

Prepared by:
ARCADIS G&M, Inc.
6 Terry Drive
Suite 300
Newtown
Pennsylvania 18940
Tel 267 685 1800
Fax 267 685 1801

Our Ref :
NP000597.0006

Date
December 2006

*This document is intended only for the use
of the individual or entity for which it was
prepared and may contain information that
is privileged, confidential, and exempt from
disclosure under applicable law. Any
dissemination, distribution, or copying of
this document is strictly prohibited.*

AR100763

1. Introduction	1
1.1 Project Scope and Objectives	1
1.2 Report Organization	2
2. Background	2
2.1 Site Investigation History	2
2.2 Physical Setting	3
2.2.1 AREA 1: Large Warehouse Area	4
2.2.2 AREA 2: Older Warehouse Area	4
2.2.3 AREA 3: Former Plant Area	5
2.2.4 AREA 4: Back Building (Northwest Warehouse Building)	5
2.2.5 AREA 5: Office Building	6
3. Previous Vapor Intrusion Investigations	6
3.1 2004 Soil Vapor Sampling	6
3.2 2005 Tracer Gas Investigation	7
4. 2006 Supplemental Soil Vapor / Indoor Air Sampling	7
4.1 Sampling Location and Rationale	8
4.2 Sample Collection Methodology	10
4.2.1 IAQ Collection Methodology	10
4.2.2 SV Collection Methodology	11
4.3 Analysis and Results	12
4.3.1 Analysis Method	12
4.3.2 Results	13
4.3.2.1 Area 1: Impress Industries	13
4.3.2.2 Area 1: L&Z Public Storage	14
4.3.2.3 Area 1: Hunsinger Plastics	15
4.3.2.4 Area 2: Stauffer Manufacturing Company, Inc.	15

4.3.2.5	Area 3: Gregory's Woodworking	16
4.3.2.6	Area 4: Back Building (Northwest Warehouse Building)	16
4.3.2.7	Area 5: Office Building	17
4.4	Data Validation Summary	17
5.	Screening Level Human Health Risk Assessment	18
5.1	Exposure Factors	18
5.2	Toxicity Values	19
5.3	Risk Characterization	20
5.3.1	Area 1: Hunsinger Plastics	20
5.3.2	Area 2: Stauffer Manufacturing Company, Inc.	20
5.3.3	Area 3: Gregory's Woodworking	21
5.3.4	Area 4: Back Building	21
5.3.4.1	T.G Packaging	21
5.3.4.2	S&W Metals	21
5.3.5	Area 5: Office Building	21
6.	Summary and Conclusions	21
7.	References	22

Tables

1	Summary of Site Specific COPCs
2	Summary of Facility Subslab Soil Vapor and Indoor Air Results

Figures

1	Site Location
2	Site Plan
3	Subslab Sample Results 2004 and 2005
4	Subslab Vapor and Indoor Sampling Results 2006

Appendices

- A Standard Operating Procedures
- B Sample Logs
- C Laboratory Data Packages
- D Data Validation Reports

1. Introduction

On behalf of Sunbeam, Inc. (Sunbeam), ARCADIS G&M, Inc. (ARCADIS) prepared this report to summarize the results of the supplemental facility soil vapor and indoor air investigation conducted at the former Bally Engineered Structures (BES) facility (the facility) between February and October of 2006. The investigation was conducted following the procedures and protocols identified in the Revised Facility Vapor Intrusion Investigation Supplemental Workplan for the Bally Groundwater Contamination Superfund Site dated 25 January 2006. The investigation activities were conducted to supplement on-going facility investigations of potential vapor intrusion associated with residual impacts to soil and groundwater from historical operations.

1.1 Project Scope and Objectives

The supplemental facility investigation was aimed at further evaluation of the former BES facility to identify any possible human health risks associated with potential vapor intrusion of site-related Constituents of Potential Concern (COPCs) present in groundwater beneath the buildings. The following samples were collected in support of the supplemental facility investigations completed in 2006:

- A total of 15 indoor air quality (IAQ) samples were collected within the facility:
 - Eight samples were collected in February 2006 which are representative of the time of year when the vapor intrusion rate would be higher;
 - Five samples were collected in August 2006 which are representative of the time of year when the vapor intrusion rate would be lower; and
 - Two samples were collected in October 2006 which are confirmatory samples;
- A total of 15 subslab soil vapor (SV) samples were collected within the facility.
- A total of four ambient air samples (two samples each in March and August of 2006) were collected outside the facility.

This report presents a comparison of the IAQ sample analytical results to the USEPA Region 3 Risk-based Concentrations (RBCs) for ambient air and Pennsylvania

Department of Environment (PADEP) Act 2 Medium-Specific Concentration for Indoor Air Quality (MSC_{IAQ}) under a non-residential land use.

1.2 Report Organization

In addition to this introduction, this report consists of the following six sections:

- Section 2 presents background information and a summary of historical facility investigations;
- Section 3 presents a summary of the 2004 and 2005 soil vapor intrusion investigations;
- Section 4 presents details of the supplemental soil vapor and indoor air sampling performed in 2006 and a discussion of the laboratory analytical results including data validation;
- Section 5 presents a screening-level human health risk assessment;
- Section 6 presents the summary and conclusions, including recommendations for future activities;
- Section 7 provides the references that were used to develop this report.

2. Background

The former BES facility is located on the southwestern edge of the Borough of Bally, Berks County, Pennsylvania. **Figure 1** presents the site location. The following subsections describe historical site investigations and present a description of the site as it currently exists.

2.1 Site Investigation History

The site was formerly a manufacturing facility for the production of insulated freezer cases. Historic operations included the use of chlorinated compounds to clean and degrease molds, nozzles and small parts used in the manufacturing process. **Figure 2** depicts the facility layout.

Several phases of soil investigations have occurred at the facility. The first occurred as a series of mobilizations between 1987 and 1989. Soil sampling during this period was conducted using direct push technology at approximately 30 locations. A photoionization detection device (PID) was used to check soil sample headspace for volatile organic compounds (VOCs).

An additional phase of soil sampling was conducted in November 1994, again using direct push technology. This 1994 investigation evaluated approximately 30 additional locations by collecting soil, water, and vapor samples. Soil samples were collected from 3 to 5 different depth intervals in each boring. Water samples were collected at eleven locations and soil gas was only successfully collected at one location. Concentrations of trichloroethene (TCE), 1,1,1-trichloroethane (TCA) and 1,1-dichloroethene (DCE) in the single soil vapor sample were below the detection limits.

In 2003, the USEPA requested further site characterization activities with respect to the risks posed by the potential for vapor intrusion. In October 2003, Sunbeam submitted a workplan to the USEPA to conduct subslab vapor sampling at the facility. This work plan was approved by the USEPA and the subslab vapor sampling was completed in March 2004 under the supervision of USEPA personnel (as for all subsequent events). The results of this investigation were submitted to the USEPA in May 2004, and are reviewed in Section 3 of this report. The USEPA provided comments on the results and a workplan for additional investigation was submitted to the USEPA in March 2005. The March 2005 work plan was approved and the additional investigation was completed in March 2005. The results of this investigation were submitted to the USEPA in June 2005 and are also summarized in Section 3 of this report. On August 9, 2005, Sunbeam, ARCADIS and the USEPA met to discuss the next phase of investigation for the facility. The January 25, 2006 revised facility vapor intrusion supplemental workplan was submitted to the USEPA as a result of the August 2005 meeting. This workplan was approved by the USEPA in a letter dated January 30, 2006. This report addresses the activities conducted in accordance with the revised supplemental workplan.

2.2 Physical Setting

The facility was expanded in several stages, such that the building itself is composed of a number of segments varying in age and construction. Presently the facility is used for several different commercial and industrial purposes, ranging from fabrication and light manufacturing to office space. Some areas have been reconditioned and modified according to the needs of the present tenants. These modifications have not

been extensively documented but included the installation of raised flooring and electrical/plumbing modifications. For the purpose of this investigation, the facility has been divided into five "work spaces" or building types as described below.

2.2.1 AREA 1: Large Warehouse Area

Based upon previous reports, the southwest portion of this area was formerly used as a lagoon/surface water impoundment. Presently the large warehouse area is occupied by the following operating companies:

- Impress Industries;
- L&Z Public Storage (note: for consistency this area is still referred to as L&Z, however since the last report/investigation, the tenant changed and is currently Luciano and Sons); and
- Hunsinger Plastics (a.k.a. HPE).

The Impress Industries portion of the facility was constructed in stages from approximately 1949-1973. Impress Industries currently uses this building for warehousing and/or storage. The L&Z portion of the facility was constructed in approximately 1969. Note that as of approximately late July 2006 a new tenant occupies the space previously occupied by L&Z Public Storage. The new tenant, Luciano and Sons, produces molded sinks and bathtubs. In order to accommodate the new tenant, a portion of the wall between Impress Industries and the former L&Z Public Storage area was removed and later replaced with drywall. However, significant gaps remain where overhead pipes penetrate the wall. During the August 2006 sampling event, strong odors were noted emanating from this portion of the facility. The odors were apparently strongest in the space occupied by the new tenant (Luciano and Sons). The construction date of the Hunsinger Plastics portion of the facility is approximately 1947.

2.2.2 AREA 2: Older Warehouse Area

The occupied portion of this area of the facility is presently used for storage of safety supplies. The occupants of this portion of the facility include:

- Stauffer Manufacturing Company, Inc.; and

- Ram Motors (listed as occupant, the space remains unoccupied).

Ram Motors is a separate building of similar construction and age as Stauffer Manufacturing. The construction date of the Stauffer portion of the facility is approximately 1947.

2.2.3 AREA 3: Former Plant Area

Based on previous reports, the former degreasing area of the original Bally Engineered Structures facility was located in this area. The two businesses operating in this portion of the facility at this time are:

- Great American Weaving Corporation (GAWC); and
- Gregory Woodworking.

GAWC and Gregory Woodworking are separated by a wall, with a man door connecting the two areas. The construction date of this portion of the former BES facility is approximately 1934.

2.2.4 AREA 4: Back Building (Northwest Warehouse Building)

Based on previous reports, historic source areas have not been identified in the northwest warehouse building. The businesses currently operating in this area are:

- T&G Packaging; and
- Cutting Edge (wood products, formerly S&W Metals).

The Northwest building was constructed after 1977 and is presently used for light manufacturing. It is separated into three segments by large bay doors that are typically left open. Additionally, large bay doors to the outside of the building are often left open, allowing free exchange of indoor and outdoor air. This building is pre-fabricated metal over an asphalt/concrete slab.

2.2.5 AREA 5: Office Building

Based upon previous reports, the basement of the office building overlies an area where lagoons or pits formerly existed. The businesses currently operating in this area are:

- Conduct and Co. (office);
- Hunsinger Plastics (office); and
- Curves (workout center).

This building was constructed in approximately 1970. The office areas consist of improved areas that have carpeted/tiled floors, finished wall systems, and drop ceilings. Heating and air conditioning are provided by a central forced air system and/or direct vent window/wall units. Ceiling heights are approximately 8 to 10 feet. Basement underlies about one-third of the building footprint; this is the only basement present on the site. The basement has a competent concrete floor and contains two sealed sumps that collect water and pump it to grade level.

The manufacturing and storage areas, including Areas 1, 2, 3 and 4, contain competent concrete floors, have ceiling heights ranging from approximately 15 to 25 feet, generally are not insulated, and are heated using direct vent natural gas-fired units. Ventilating fans were also noted in several areas of the building. Large bay doors are located in each of these areas to provide ready access to the building.

3. Previous Vapor Intrusion Investigations

This section presents the results of the previous vapor intrusion investigations that were conducted in 2004 and 2005 at the request of the USEPA. The results of these investigations were used to identify the location and number of samples collected in the 2006 investigation.

3.1 2004 Soil Vapor Sampling

Four subslab vapor samples (SV-1 through SV-4) were collected from locations within the former BES facility in March and April of 2004. The sample locations are shown on **Figure 3**. **Table 1** presents the COPCs analyzed as part of the investigation and the shallow soil gas screening levels, based on a 1×10^{-6} risk level, identified in USEPA

guidance (2002). TCE is the primary COPC at the BES facility. A summary of the results which were provided to the USEPA in a May 5, 2004 summary letter are provided below:

- Samples SV-1 and SV-2 had TCE concentrations of 130 and 140 ug/m3, respectively.
- Samples SV-3 and SV-4 had TCE concentrations of 13,000 and 6,100 ug/m3, respectively.
- The other COPCs, with the exception of vinyl chloride (VC), were detected in the samples but were at concentrations below the shallow soil gas screening levels (USEPA, 2002).
- VC was not detected in any samples.

3.2 2005 Tracer Gas Investigation

In March 2005, five additional subslab vapor samples, TG-1 through TG-5, were collected and analyzed for the COPCs. The results are presented on **Table 2**. A duplicate sample was collected at location TG-5. The sample locations are shown on **Figure 3**. A summary of the results which were provided to the USEPA in a June 30, 2005 summary letter are provided below:

- TCE was detected in all of the samples at concentrations ranging from 2 ug/m3 (TG-4, collected from the suspected former location of the dip tank) to 39,000 ug/m3 (TG-5, collected from T&G Packaging).
- 1,1,1-TCA and 1,1-DCE were also detected in several samples. 1,1-DCE was the only other COPC detected above the USEPA shallow soil-gas screening level, at 79,000 ug/m3 at TG-5. The March 2005 results were reported in a June 30, 2005 summary letter to the USEPA.

4. 2006 Supplemental Soil Vapor / Indoor Air Sampling

The 2006 supplemental sampling events include three separate events in which subslab vapor and/or indoor air samples were collected.

Nine subslab vapor samples, eight indoor air samples, two ambient air samples, and four quality assurance duplicate samples were collected in February 2006 and analyzed for the site-specific COPCs listed in **Table 1**, to evaluate the potential for vapor intrusion.

In August 2006, six subslab vapor samples, five indoor air samples, two ambient air samples, and one quality assurance duplicate sample were collected and analyzed for the site-specific COPCs listed in **Table 1**, to evaluate the potential for vapor intrusion.

Finally, in October 2006 two additional indoor air samples were collected in Area 1.

The following subsections present the sample collection methodology and the laboratory analytical results.

4.1 Sampling Location and Rationale

The following points describe the samples collected during each of the three 2006 sampling events and the basis for selecting each location. The sample locations and results are shown on **Figure 4**.

- **AREA 1 - Large Warehouse Area**

February 2006

Samples collected: IAQ-1/SV-4B, IAQ-4/SV-5, SV-9 and SV-10.

TCE was previously detected in subslab samples collected beneath Area 1 at concentrations of 6,100 ug/m³ (SV-4 in 2004) and 17,000 ug/m³ (TG-1 in 2005) in the southwestern portion of the Impress Industries space. The middle and eastern portions of the Area 1 were not assessed in either 2004 or 2005. Therefore, the locations of SV-9 and SV-10 were selected for investigation because of their proximity to the former northern lagoon area and former small parts degreasing area, respectively.

August 2006

Samples collected: IA-A-1/SS-A-1, IA-A-2/SS-A-2, and SS-A-3.

Three SV samples were collected to further characterize subslab COPC concentrations which were detected in the warehouse area during the February 2006 event. Corresponding IAQ samples were collected at two of the SV sample locations to characterize indoor air concentrations of COPCs and to evaluate the

potential for vapor intrusion. A corresponding IAQ sample was not collected at SS-A-3 because the room had open 5 gallon buckets, 30 gallon and 55 gallon drums as well as smaller containers possibly containing volatile liquids, which would have impacted results if a sample was collected. It is noted that strong odors, which were most prominent in the Luciana and Sons area, were noticed during this event.

October 2006

Samples collected: IA-A-1-101206, and IA-A-3-101206.

Two additional indoor air samples were collected. IA-A-1-101206 was collected to confirm the TCE concentration detected in indoor air at Impress Industries in August 2006. IA-A-3-101206 was collected within Impress Industries to further characterize indoor air concentrations in the vicinity in which the open containers were present during the August 2006 sampling event in the Luciano and Sons area.

- AREA 2 - Older Warehouse Area

February 2006

Samples collected: IAQ-2/SV-3B.

An IAQ/SV sampling pair was collected in this area to further evaluate TCE detections of 290 and 13,000 ug/m³ in previously collected subslab vapor samples in the Stauffer portion of the facility.

- AREA 3 - Former Plant Area

February 2006

Samples collected: IAQ-7/SV-11.

The portion of the building occupied by Gregory Woodworking had not been previously assessed.

August 2006

Samples collected: IA-A-4/SS-A-4.

An IAQ/SV sampling pair was collected in this area to further evaluate the potential for TCE vapor intrusion based on a subslab vapor sample (SV-11) collected in February 2006 in which 110,000 ug/m³ TCE was detected.

- AREA 4 - Back Building (IAQ-5/SV-7 and IAQ-6/SV-6) .

February 2006

Samples collected: IAQ-5/SV-7 and IAQ-6/SV-6.

Although historic source areas have not been identified in the northwest warehouse building, subslab concentrations of COPCs above the screening levels were detected here in March of 2005. As a result, additional sampling was conducted.

August 2006

Samples collected: IA-A-5/SS-A-5, and IA-A-6/SS-A-6.

These paired samples were collected in the vicinity where TCE was detected in two subslab vapor samples (TG-5 and SV-7) at a maximum concentration of 48,000 ug/m³, but was not detected in a nearby subslab sample (SV-6).

- AREA 5 - Office Building

February 2006

Samples collected: IAQ-3A/IAQ-3B and SV-8.

A subslab vapor sample collected from the basement in March 2005 had 9.6 ug/m³ TCE. As a result, additional subslab vapor samples were collected. Indoor air samples from both the ground floor and the basement were collected in order to investigate air quality throughout the building.

4.2 Sample Collection Methodology

Samples were collected in accordance with the SOPs included in **Appendix A**. Portions of the procedures, such as checking initial and final vacuums, are dictated by laboratory procedure. In all cases the IAQ samples were collected prior to collecting the SV samples. A summary of the sample collection methods for IAQ samples and SV samples is presented below.

4.2.1 IAQ Collection Methodology

Before the initiation of the IAQ sampling, the sample location, date, time, weather, atmospheric pressure, Summa™ canister number and flow controller number were recorded on the IAQ sampling log. Initial canister vacuum was verified and noted prior to collecting samples.

To sample over an eight hour period, a flow restrictor was connected to the top of a 6-L Summa™ canister. Samples were collected at an elevation within the normal breathing zone of building occupants. This was accomplished by either setting the canister on a shelf, or attaching tubing to the flow controller and securing the opposite end several feet above the ground surface. After the eight hour collection period, the final vacuum was verified and recorded on the IAQ sampling log and canister tag. Sample logs are provided in **Appendix B**.

Following completion of sampling activities, the 6-L Summa™ canisters were appropriately packaged, sealed, and sent back to Air Toxics for analysis. Chain of custody forms were completed and included in each shipment.

4.2.2 SV Collection Methodology

The sample apparatus was assembled prior to drilling holes in the building slab. Sampling equipment included a stainless steel probe, Tedlar bag, flow controller, 6-L Summa™ canister, inert flexible tubing and associated inert unions, clamps, valves and other necessary components. Initial canister vacuum measurements were recorded prior to collecting samples.

A hammer drill was used to drill a 3/8-inch diameter hole in the slab at each location. After breaking through the slab, the drill bit was advanced approximately three inches further into the subsurface material. Cuttings produced during drilling were periodically swept away from the top of the hole. Drill cuttings were removed from the surface around the hole with a clean, damp sponge, prior to inserting the probe. The probe was allowed to "float" within the slab, sealed and secured using an inert clay material. The clay material provided an air-tight seal to the ground surface around the boring and the probe, and was also used to ensure an air-tight seal between the probe and the tubing.

After each sampling apparatus was assembled, the sampling connections were checked before purging air. Approximately 2 liters of subslab air were purged from each sample location using a sampling pump. The purge volume was selected based upon the approximate volume of the sample apparatus. The purged air was collected in Tedlar bags and evacuated outside of the facility. The purge rate was approximately 200 cubic centimeters per minute (cm^3/min). The purge time and amount were recorded for each sample.

Following purging, the connection to the pump was clamped off to prevent cross-contamination during the sample collection. Subslab vapor samples were then collected in certified clean 6-L Summa™ canisters equipped with flow regulators to limit the intake rate to approximately 200 cm³/min. Canisters were monitored during the 30 minute period required for sample collection. Final vacuums were recorded on the sample log sheet at the end of the sampling period. Sample locations, canisters and times were recorded on sample log sheets.

Following completion of sampling activities at each location, the sampling equipment was disassembled, and clay material was removed from the concrete surface. The 6-L Summa™ canisters were appropriately packaged, sealed, and sent back to Air Toxics for analysis. Chain of custody forms were completed and included in each shipment. The boring holes were sealed using a concrete patching compound. The filler material was packed into the holes using a wooden dowel rod, to restore the hole to the original concrete slab surface grade. Photographs of the sampling locations were taken to document restoration of the concrete slab.

4.3 Analysis and Results

The results of the February, August, and October 2006 sampling events are presented in detail in this section. Results of previous sampling rounds are discussed and compared to the most recent data. Indoor air results are also compared to the ambient air RBC value, as an initial screening mechanism. More detailed risk calculations, in the subsequent section, build on these results.

4.3.1 Analysis Method

The indoor air, ambient air, and subslab vapor samples collected from the facility were submitted to Air Toxics Limited for gas chromatography/mass spectroscopy (GC/MS) analysis by modified TO-15 for the COPCs listed in **Table 1**.

Subslab vapor samples were analyzed by the low-level TO-15 method and indoor/ambient air samples were analyzed by the SIM TO-15 method, with reporting limits as noted in **Table 1**. All results were reported according to the laboratory Reporting Limit (RL). Concentrations presented in parts per billion volume (ppbv) were converted to micrograms per cubic meter using the following equation:

$$\text{ug/m}^3 = (\text{ppbv} \times \text{molecular weight})/24.45$$

where 24.45 is the molar volume of air, in liters, at 25°C and 760 torr.

4.3.2 Results

The IAQ and SV results are provided in **Table 2**. For the purpose of evaluating indoor air sample analytical results, observed concentrations were compared to:

- USEPA (2006) Region 3 Risk-based Concentrations (RBC) for ambient air under a residential land-use; and
- PADEP (2004) Act 2 Medium-Specific Concentration for Indoor Air Quality (MSC_{IAQ}) under a non-residential land use;

There are known uncertainties associated with the screening levels associated with assumptions used to calculate them. These uncertainties include:

- USEPA Region 3 RBCs for ambient air are based on residential exposures.
- The RBC for TCE was calculated using the most conservative cancer slope factor of the available range established by NCEA (2001). This is further discussed in Section 5.2 below.
- PADEP TCE MSCIAQ is based on a withdrawn toxicity value and 1E-5 cancer risk.

4.3.2.1 Area 1: Impress Industries

Four rounds of soil vapor samples (SV-4, TG-1, SV-4B, SS-A-1) and three rounds of indoor air samples (IAQ-1, IA-A-1, IA-A-1-101206) have been collected over a two year period from the southern portion of the building currently occupied by Impress Industries. Two of the indoor air samples and subslab samples were co-located (IAQ-1/SV4B and IA-A-1/SS-A-1), and all of the samples were collected in the same general location (i.e., above the former Southern Lagoon area). Soil vapor samples were also collected from the center of the building in 2006 (SV-9) and from the northern portion of the building (SV-1) in 2004.

During the soil vapor sampling, the flooring was observed to be approximately 14-inch-thick competent concrete. TCE was detected in all of the subslab soil vapor samples collected in this building; however, concentrations observed in the samples collected from the center (SV-9 at 11 ug/m³) and northern portion of the building (SV-1 at 130

ug/m³) were not high enough to result in unacceptable indoor air concentrations based on the attenuation factors predicted using the results of the March 2005 investigation.

In the southern portion of the building, in the vicinity of what was previously the southern lagoon, TCE was detected in all four subslab soil vapor samples at concentrations ranging from 6,100 ug/m³ to 210,000 ug/m³. TCE was also detected in all three IAQ samples at concentrations ranging from 40 ug/m³ to 280 ug/m³. These concentrations are greater than the ambient air RBC for TCE (0.016 ug/m³). In addition, TCE concentrations in two of the three IAQ samples (180 ug/m³ at IA-A-1 and 280 ug/m³ in IA-A-1-101206) were greater than the PADEP non-residential MSC_{IAQ} for TCE (48 ug/m³). 1,1,1-TCA, 1,1-DCE, and cis-1,1-dichloroethene were also detected in at least one indoor air sample, but the concentrations were less than their respective ambient air RBCs and non-residential MSC_{IAQs}.

An additional indoor air sample (IA-A-3-101206) was collected in the northeastern portion of Impress Industries near the wall shared with the former L&Z Public Storage area (currently occupied by Luciano and Sons). This sample was collected to characterize indoor air concentrations near which the open containers were present during the August 2006 sampling event. As noted above, significant gaps in the drywall separating Impress Industries and the L&Z Storage area are present where overhead pipes penetrate the wall. In addition, odors emanating from the L&Z Storage area were apparent in this portion of Impress Industries. Therefore, the indoor air sample collected at this location is representative of indoor air within the former L&Z Storage area, and results are discussed below.

The concentration of TCE in indoor air has steadily increased in the southern portion of Impress Industries during each of the three sampling events in this area: from 40 ug/m³ in February to 180 ug/m³ in August to 280 ug/m³ in October. This area is connected with the other portions of the building and the increase in TCE concentrations observed may be associated with new operations in the area of the building that was formerly occupied by L&Z Public Storage as discussed below.

4.3.2.2 Area 1: L&Z Public Storage

Two subslab soil vapor samples (SV-5, SS-A-3) and one indoor air sample (IAQ-4) was collected from this portion of the main building in February 2006. Indoor air sample IAQ-4 was co-located with the subslab soil vapor sample SV-5 in the central portion of the space. During the subslab soil vapor sampling, the flooring was observed to be approximately 14-inch-thick competent concrete.

TCE was detected in both of the subslab soil vapor samples at concentrations of 2,600 ug/m^3 in SV-5 and 3,000 ug/m^3 at SS-A-3. The concentration of TCE at IAQ-4 (48 ug/m^3) is greater than the ambient air RBC (0.016 ug/m^3); however, it is equal to the non-residential MSCIAQ (48 ug/m^3). 1,1,1-TCA and 1,1-DCE were also detected in the indoor air sample, but the concentrations were below their respective ambient air RBCs and non-residential MSC_{IAQS}.

As noted above, IA-A-3-101206 was collected within the Impress Industries area, but results are representative of indoor area within L&Z Public Storage. The TCE concentration at IA-A-3-101206 (490 ug/m^3) is greater than both the ambient air RBC (0.016 ug/m^3) and the non-residential MSCIAQ (48 ug/m^3). 1,1,1-TCA and 1,1-DCE were also detected in the indoor air sample, but the concentrations were below their respective ambient air RBCs and non-residential MSC_{IAQS}.

There has been a 10-fold increase of TCE concentrations in indoor air between February 2006 (48 ug/m^3) and October 2006 (490 ug/m^3). As noted in Section 2.2.1 above, L&Z Public Storage no longer occupies this area. Luciano and Sons began occupying this space in August 2006. The appearance of the strong odor and the increase in the indoor air concentrations of TCE coincides with the change of tenants and operational use of the area.

4.3.2.3 Area 1: Hunsinger Plastics

Two subslab soil vapor samples (SV-10 and SS-A-2) and one indoor air sample (IA-A-2) was collected in 2006. Indoor air sample IA-A-2 was co-located with the subslab soil vapor sample SS-A-2 in the central portion of the space. The concentration of TCE in SV-10 and SS-A-2 was 490 ug/m^3 and 350 ug/m^3 , respectively. The concentration of TCE at IA-A-2 (3.8 ug/m^3) is greater than the ambient air RBC (0.016 ug/m^3); however, it is less than the non-residential MSCIAQ (48 ug/m^3). 1,1,1-TCA and 1,1-DCE were also detected in the indoor air sample, but the concentrations were less than their respective ambient air RBCs and non-residential MSC_{IAQS}.

4.3.2.4 Area 2: Stauffer Manufacturing Company, Inc.

Three subslab vapor samples (TG-2, SV-3, SV-3B) and one indoor air sample (IAQ-2) have been collected in this portion of the main building. During the soil vapor sampling, the flooring was observed to be approximately 8-inch-thick competent concrete with wood slats overlying the concrete in some portions of the building.

The TCE concentrations observed in subslab soil vapor have oscillated over time, from 13,000 ug/m³ in 2004, to 290 ug/m³ in 2005, to 4,200 ug/m³ in 2006. TCE was detected at 2.5 ug/m³ in the indoor air sample (IAQ-2) which is greater than the ambient air RBC (0.016 ug/m³), but less than non-residential MSC_{IAQ} (48 ug/m³). 1,1,1-TCA and 1,1-DCE were detected in the indoor air sample, but the concentrations were less than their respective ambient air RBCs and non-residential MSC_{IAQ}s.

4.3.2.5 Area 3: Gregory's Woodworking

Two subslab soil vapor/indoor air sample pairs (SV-11/IAQ-7 and SS-A-4/IA-A-4) were collected in 2006. During the subslab soil vapor sampling, the flooring was observed to be approximately 3-inch-thick competent concrete.

The TCE concentration observed in the subslab soil vapor collected in February 2006 was 110,000 ug/m³, but the TCE concentration in the co-located indoor air sample (average of IAQ-7 and IAQ-7DUP) was only 0.44 ug/m³. The subslab soil vapor concentration in SS-A-4, which was collected in October 2006 and in close proximity to SV-11, was 4.6 ug/m³. TCE in the co-located indoor air sample (IA-A-4) was 0.35 ug/m³. Although the TCE concentrations observed in both indoor air samples are greater than the ambient air RBC (0.016 ug/m³), they are less than the non-residential MSC_{IAQ} (48 ug/m³). 1,1,1-TCA and 1,1-DCE were detected in IA-A-4 (they were not detected in IAQ-7 or its duplicate), but the concentrations were less than their respective ambient air RBCs and non-residential MSC_{IAQ}s.

4.3.2.6 Area 4: Back Building (Northwest Warehouse Building)

Five subslab soil vapor samples (TG-5, SV-6, SV-7, SS-A-5, and SS-A-6) and four indoor air samples (IAQ-5, IAQ-6, IA-A-5, and IA-A-6) have been collected from the building located northwest of the main facility. TCE was detected in four of the five subslab soil vapor samples at concentrations ranging from 3.8 ug/m³ (SS-A-6) to 48,000 ug/m³ (SV-7). TCE was not detected in SV-6. During the subslab soil vapor sampling, the flooring was observed to be approximately 12-inch-thick competent concrete and/or asphalt.

TCE was detected in all four indoor air samples at concentrations ranging from 1 ug/m³ (IA-A-6) to 7.7 ug/m³ (IAQ-5), which are greater than the ambient air RBC (0.016 ug/m³). However, the observed concentrations of TCE were less than the non-residential MSC_{IAQ} (48 ug/m³). 1,1,1-TCA and 1,1-DCE were also detected all four

indoor air samples, but the concentrations were less than their respective ambient air RBCs and non-residential MSC_{IAQS} .

4.3.2.7 Area 5: Office Building

Two subslab soil vapor samples (TG-3 and SV-8) and two indoor air samples (IAQ-3A and IAQ-3B) have been collected from the office building. Indoor air sample IAQ-3A and subslab soil vapor sample SV-8 were co-located in the building basement. Indoor air sample IAQ-3B and its duplicate (IAQ-3B Dup) were collected on the ground floor, above the basement sample location. During the subslab soil vapor sampling, the flooring was observed to be approximately 2-inch-thick competent concrete.

TCE concentrations in the subslab soil vapor samples were 9.6 ug/m^3 in TG-3 (collected in March 2005) and 9.1 ug/m^3 in SV-8 (collected in February 2006). TCE was detected in indoor air samples at concentrations of 1.4 ug/m^3 (IAQ-3B) and 2.9 ug/m^3 (IAQ-3A). The observed TCE concentration in indoor air is greater than the ambient air RBC (0.016 ug/m^3), but less than the non-residential MSC_{IAQ} (48 ug/m^3). 1,1,1-TCA and 1,1-DCE were also detected in at least on indoor air sample; however, the concentrations were less than their respective ambient air RBCs and non-residential MSC_{IAQS} .

4.4 Data Validation Summary

The purpose of the data validation is to determine the reliability of the chemical analyses and the accuracy and precision of data generated by the laboratory for the recent data collected. The quality of laboratory data was evaluated by comparison to a set of quality control criteria, including precision, accuracy, and completeness.

Six analytical data packages were generated by the laboratory for the February samples, three were generated for the August samples, and one was generated for the October samples. The laboratory reports were reviewed for completeness and compliance with the deliverable requirements. Level 4 data packages were complete upon receipt and are provided electronically as **Appendix C**. Method blanks were prepared and analyzed in conjunction with the field samples to monitor potential contamination impacts during analysis. No target compounds were detected in any of the method blanks. Laboratory controls samples (LCSs) were included with each analytical batch to establish method control within the laboratory environment. All LCSs associated with project samples were acceptable. Field duplicates were collected to evaluate precision of sample collection as well as analytical method

performance. The relative percent differences of chemical concentrations observed in the primary and duplicate samples were within control limits.

Based on the data validation, the data gathered under this investigation meet the project and analytical data quality objectives. One hundred percent of the samples were analyzed as collected and as requested on the chains of custody or corrected through communication with the project chemist. The data are considered to be of known and documented quality. One hundred percent of the data generated are usable for the intended purpose as qualified during the review and verification assessment. Data validation reports are provided in **Appendix D**.

5. Screening Level Human Health Risk Assessment

This screening level human health risk assessment (HHRA) characterizes potential risks in a manner consistent with the risk assessment principles and practices established by the U.S. Environmental Protection Agency (USEPA) Risk Assessment Guidance for Superfund (RAGS) (USEPA, 1989), and subsequent USEPA guidance (USEPA, 1991; 1997; 2002; and 2003).

Potential risks and hazards were calculated using the constituent concentrations observed in indoor air samples as presented in the previous section.

5.1 Exposure Factors

With the exception of the Stauffer Manufacturing Company area, the main building is regularly frequented by site workers throughout the day storing and retrieving items. Therefore, the following site-specific exposure factors were selected:

- Inhalation rate of 1.6 m³/hour based on moderate activity level (USEPA, 1997);
- Exposure time of 8 hours per day (professional judgment);
- Exposure frequency of 250 days per year (USEPA, 1991);
- Exposure duration of 25 years (USEPA, 1991);
- Body weight of 70 kg (USEPA, 1989); and

- Averaging time for cancer effects of 25,550 days based on a 70-year average lifespan (USEPA, 1989);
- Averaging time for non-cancer effects of 9,125 days based on a 25-year exposure duration (USEPA, 1989).

5.2 Toxicity Values

Human health risk assessment is based on two general categories of toxic effects—non-carcinogenic and carcinogenic. Constituent-specific toxicity values are used to calculate potential risks for these two types of effects. Following USEPA (2003) guidance, the constituent-specific toxicity values used to evaluate potential non-carcinogenic and carcinogenic effects were compiled following the recommended toxicity value hierarchy as follows:

- Tier 1: USEPA's Integrated Risk Information System (IRIS) (IRIS, 2006);
- Tier 2: USEPA's Provisional Peer Reviewed Toxicity Values (PPRTVs); and
- Tier 3: Other toxicity values including USEPA and non-USEPA sources of toxicity information.

Based on the above criteria, the following toxicity values were used in this screening level HHRA.

Chemical	Inhalation Cancer Slope Factor (mg/kg/day) ⁻¹	Inhalation Reference Dose (mg/kg/day)
Trichloroethene	0.02 - 0.4	0.01
1,1,-Dichloroethene	NA	0.06
1,1-Dichloroethane	NA	0.14
cis-1,2-Dichloroethene	NA	NA
1,1,1-Trichloroethane	NA	0.63
Vinyl chloride	0.015	0.028

NA – Not available

For 1,1,1-TCA, potential non-cancer hazards were calculated using a provisional reference concentration available through NCEA, which expired in August 2005 and retired from the PPRTV in October 2005 (STSC, 2003). For TCE, potential risks were calculated using both the upper and lower end of the range of cancer slope factors for the inhalation pathway of 0.02 to 0.4 per mg/kg/day (NCEA, 2001).

5.3 Risk Characterization

The following subsections summarize the potential risks and hazards calculated for each area of the facility using the information presented above. Samples were collected in the winter, when vapor intrusion would be expected to be higher, and in the summer, when vapor intrusion would be expected to be lower. Thus, averaging samples collected during these two seasons will provide a more realistic exposure point concentration. Therefore, in areas where more than one indoor air sample was collected, the average indoor air concentration was used to calculate potential risks and hazards. Note that potential risks and hazards were not calculated for exposure to VOCs in indoor air at the Impress Industries and L&Z Public Storage areas. As discussed above, the concentration of TCE in indoor air increased significantly during 2006 and the increase appears to be related to the current operational use of the former L&Z Public Storage area.

5.3.1 Area 1: Hunsinger Plastics

Using the average constituent concentrations detected in the indoor air samples, the potential incremental cancer risk ranges from $3\text{E-}6$ to $7\text{E-}5$, which is within the target risk range established by USEPA (1991) of $1\text{E-}6$ to $1\text{E-}4$. TCE is the only chemical contributing to the potential incremental cancer risk. The non-cancer hazard index is less than one ($\text{HI}=0.05$), indicating that adverse non-cancer effects are unlikely.

5.3.2 Area 2: Stauffer Manufacturing Company, Inc.

Using the average chemical concentrations detected in the indoor air samples, the potential incremental cancer risk ranges from $2\text{E-}6$ to $4\text{E-}5$, which is within the target risk range established by USEPA (1991) of $1\text{E-}6$ to $1\text{E-}4$. TCE is the only chemical contributing to the potential incremental cancer risk. The non-cancer hazard index is less than one ($\text{HI}=0.03$), indicating that adverse non-cancer effects are unlikely.

5.3.3 Area 3: Gregory's Woodworking

Using the average chemical concentrations detected in the indoor air samples, the potential incremental cancer risk ranges from $4\text{E-}7$ to $7\text{E-}6$, which ranges from less than to within the target risk range established by USEPA (1991) of $1\text{E-}6$ to $1\text{E-}4$. TCE is the only chemical contributing to the potential incremental cancer risk. The non-cancer hazard index is less than one ($\text{HI}=0.005$), indicating that adverse non-cancer effects are unlikely.

5.3.4 Area 4: Back Building

5.3.4.1 T.G Packaging

Using the average chemical concentrations detected in the indoor air samples, the potential incremental cancer risk ranges from $7\text{E-}6$ to $1\text{E-}4$, which is within the target risk range established by USEPA (1991) of $1\text{E-}6$ to $1\text{E-}4$. TCE is the only chemical contributing to the potential incremental cancer risk. The non-cancer hazard index is less than one ($\text{HI}=0.2$), indicating that adverse non-cancer effects are unlikely.

5.3.4.2 S&W Metals

Using the average chemical concentrations detected in the indoor air samples, the potential incremental cancer risk ranges from $3\text{E-}6$ to $6\text{E-}5$, which is within the target risk range established by USEPA (1991) of $1\text{E-}6$ to $1\text{E-}4$. TCE is the only chemical contributing to the potential incremental cancer risk. The non-cancer hazard index is less than one ($\text{HI}=0.1$), indicating that adverse non-cancer effects are unlikely.

5.3.5 Area 5: Office Building

Using the commercial/industrial exposure factors identified above, the potential incremental cancer risk ranges from $2\text{E-}6$ to $4\text{E-}5$, which is within the target risk range established by USEPA (1991) of $1\text{E-}6$ to $1\text{E-}4$. TCE is the only chemical contributing to the potential incremental cancer risk. The non-cancer hazard index is less than one ($\text{HI}=0.03$), indicating that adverse non-cancer effects are unlikely.

6. Summary and Conclusions

The supplemental investigation performed by ARCADIS in 2006 evaluated the potential impacts to indoor air quality from vapor intrusion. A total of 15 subslab soil

vapor and indoor air quality samples were collected between February and October 2006. TCE and several other COPCs, were identified the indoor air samples in all areas of the facility. During the August and October sampling events, strong odors were being emitted from the former L&Z Storage area and could be identified in the Impress industries area. The indoor air samples collected in August and October 2006 reflected an increase in the TCE concentrations. The suspected source of the increase in TCE is the current operations at the former L&Z Storage area. The assessment of potential risks associated with the increase TCE concentrations associated with the current operations of the new tenant is beyond the scope of this investigation.

The potential cancer risk and non-cancer hazard associated with exposure via inhalation of volatile COPCs in the subsurface migrating to indoor air at all areas of the facility, except Impress Industries and the former L&Z Storage area, were calculated. Results indicate that concentrations of COPCs present in the subsurface do not pose an unacceptable risk to site workers via inhalation of indoor air.

7. References

Pennsylvania Department of Health and Environment (PADEP). July 2004. Final Draft Guidance on Vapor Intrusion into Buildings from Groundwater and Soil under the Act 2 Statewide Health Standard. Publication 253-0300-100.

National Center for Environmental Assessment (NCEA). 2001. Trichloroethylene Health Risk Assessment: Synthesis and Characterization (External Review Draft). U.S. Environmental Protection Agency, Office of Research and Development, National Center for Environmental Assessment, Washington Office, Washington, DC, EPA/600/P-01/002A, 2001.

Superfund Health Risk Technical Support Center (STSC). 2003. PPRTV Derivation Support Document for 1,1,1-Trichloroethane (CASRN. 71-55-6). 98-025/8-03). August.

U.S. Environmental Protection Agency (USEPA). 1989. Risk Assessment Guidance for Superfund (RAGS): Volume I Human Health Evaluation Manual (Part A). EPA/540/1 89/002. December.

U.S. Environmental Protection Agency (USEPA). 1991. Risk Assessment Guidance for Superfund, Human Health Evaluation Manual: Standard Default Exposure Factors. OSWER Directive 9285.6 03.

U.S. Environmental Protection Agency (USEPA). 1997. Exposure Factors Handbook: I, II, and III. EPA/600/P 95 002Ba, Bb, and Bc. Science Advisory Board Review Draft. August.

U.S. Environmental Protection Agency (USEPA). 2002. User's Guide For Evaluating Subsurface Vapor Intrusion Into Buildings. U.S. Environmental Protection Agency, Office of Emergency and Remedial Response, Washington, DC. June 19.

U.S. Environmental Protection Agency (USEPA). 2003. Human Health Toxicity Values in Superfund Risk Assessments. OSWER Directive 9285.7-53.

U.S. Environmental Protection Agency (USEPA). 2006. Region 3 Risk-based Concentration Table. October.

ARCADIS

Table 1. Summary of Site Specific COPCs
Former BES Facility Bally, Pennsylvania

Air Toxics Reporting Limits

Constituent of Potential Concern (COPC)	CAS No.	Low-Level Analysis (ug/m ³)	SIM analysis (ug/m ³)	Shallow Soil Gas Screening Level (USEPA, 2002) (ug/m ³)
1,1-Dichloroethane	75-01-4	0.1	0.02	5000
1,1-Dichloroethene	75-34-3	0.1	0.01	2000
cis-1,2-Dichloroethene	75-35-4	0.1	0.02	350
1,1,1-Trichloroethane	156-59-2	0.1	0.02	22,000
Trichloroethene	71-55-6	0.1	0.02	0.22
Vinyl Chloride	79-01-6	0.1	0.01	2.8

Notes:

Laboratory reporting limits may not be achievable under all conditions.

ARCADIS

Table 2. Summary of Facility Subslab Soil Vapor and Indoor Air Results
Former BES Facility Bally, Pennsylvania

Location	Sample ID	Sample Date	Medium	Trichloroethene	1,1,-Dichloroethene	1,1-Dichloroethane	cis-1,2-Dichloroethene	1,1,1-Trichloroethane	Vinyl chloride
Screening Levels	USEPA Region 3 Ambient Air RBC Residential PADEP Indoor Air MSC _{IAQ} Nonresidential			0.016 48	220 580	510 510	37 100	1000 6,100	0.072 9.5
Area 1: Impress Industries	SV-1	4/7/2004	SV	130	500	1.1	0.89	260	<0.23
	SV-4	4/7/2004	SV	6,100	<22	<70	<22	<67	<14
	TG-1	3/23/2005	SV	17,000	34 J	<35	<35	<48	<22
	SV-4B	2/4/2006	SV	210,000	<590	<600	<590	<810	<380
	IAQ-1	2/4/2006	IA	40	3.6	<0.13	<0.13	5.4	<0.041
	SV-9	2/28/2006	SV	11	<0.55	<0.56	<0.55	0.78	<0.36
	SS-A-1	8/30/2006	SV	14000	<34	<35	49	69	<22
	SS-A-1 (dup)	8/30/2006	SV	9300	<26	<27	29	54	<17
	IA-A-1	8/28/2006	IA	180	62	<0.18	0.18	100	<0.056
	IA-A-1-101206	10/12/2006	IA	280	43	<0.65	<0.64	44	<0.41
	IA-A-3-101206	10/12/2006	IA	490	150	<1.2	<1.2	170	<0.75
Area 1: Hunsinger Plastics	SV-10	2/28/2006	SV	490	<4.1	9.0	740	370	<2.6
	SS-A-2	8/30/2006	SV	350	6.0	2.5	200	100	<0.70
	IA-A-2	8/28/2006	IA	3.8	1.3	<0.13	<0.12	1.6	<0.040
Area 1: L&Z Public Storage	SV-5	2/28/2006	SV	2,600	580	<6.5	<6.3	22	<4.0
	SV-5Dup	2/28/2006	SV	2,600	590	<6.2	<6.0	23	<3.9
	IAQ-4	2/24/2006	IA	48	7.4	<0.13	<0.13	8.4	<0.041
	SS-A-3	8/30/2006	SV	3000	240	<11	<11	21	<7.0
Area 4: T.G. Packaging	TG-5	3/23/2005	SV	39,000	79,000	<120	<35	<48	<22
	SV-7	2/27/2006	SV	48,000	100,000	<300	<300	51,000	<190
	IAQ-5	2/24/2006	IA	7.7	37	<0.18	<0.18	13	<0.057
	SS-A-5	8/29/2006	SV	47,000	79000	<230	<220	52000	<140
	IA-A-5	8/28/2006	IA	7.4	19	<0.12	<0.12	9.6	<0.038
Area 4: S&W Metals	SV-6	2/27/2006	SV	<0.76	<0.56	<0.57	<0.56	<0.77	<0.36
	IAQ-6	2/24/2006	IA	5.1	53	<0.14	<0.14	19	<0.046
	IAQ-6Dup	2/24/2006	IA	5.2	52	<0.14	<0.14	20	<0.46
	SS-A-6	8/29/2006	SV	3.8	0.84	<0.56	<0.55	5.1	<0.36
	IA-A-6	8/28/2006	IA	1	3.3	<0.13	<0.13	2.3	<0.041
Area 5: Office Area	TG-3	3/24/2005	SV	9.6	<0.063	<0.13	<0.14	0.95	<0.04
	SV-8	2/28/2006	SV	9.1	<0.58	<0.59	<0.58	<0.80	<0.37
	IAQ-3A	2/24/2006	IA (Basement)	2.9	0.065	<0.13	<0.12	0.38	<0.043
	IAQ-3B	2/24/2006	IA (1st Floor)	1.4	<0.067	<0.14	<0.13	0.38	<0.043
	IAQ-3B Dup	2/24/2006	IA (1st Floor)	1.4	0.07	<0.14	<0.13	0.4	<0.043
Former Test Coolers	SV-2	4/7/2004	SV	140	180	2.1	3.6	560	<0.14

ARCADIS

Table 2. Summary of Facility Subslab Soil Vapor and Indoor Air Results
Former BES Facility Bally, Pennsylvania

Location	Sample ID	Sample Date	Medium	Trichloroethene	1,1,-Dichloroethene	1,1-Dichloroethane	cis-1,2-Dichloroethene	1,1,1-Trichloroethane	Vinyl chloride
Screening Levels	USEPA Region 3 Ambient Air RBC Residential			0.016	220	510	37	1000	0.072
	PADEP Indoor Air MSC _{IAQ} Nonresidential			48	580	510	100	6,100	9.5
Area 2: Stauffer Mfg. Co	SV-3	4/7/2004	SV	13,000	<53	<54	<53	<73	<34
	TG-2	3/22/2005	SV	290	<0.72	<0.74	<0.72	<1.0	<0.47
	SV-3B	2/28/2006	SV	4,200	<9.5	<9.7	<9.5	<13	<6.1
	IAQ-2	2/24/2006	IA	2.5	0.3	<0.14	<0.13	0.43	<0.043
Area 3: Gregory's Woodworking	SV-11	3/1/2006	SV	110,000	38,000	<300	<290	27,000	<190
	IAQ-7	2/24/2006	IA	0.43	<0.082	<0.17	<0.16	<0.22	<0.053
	IAQ-7DUP	2/24/2006	IA	0.45	<0.082	<0.17	<0.16	<0.22	<0.053
	SS-A-4	8/29/2006	SV	4.6	<0.56	<0.57	<0.56	<0.77	<0.36
	IA-A-4	8/28/2006	IA	0.35	0.07	<0.13	<0.12	0.3	<0.040
Area 3: Great American Weaving Corporation	TG-4	3/22/2005	SV	2.0	<0.071	<0.14	<0.14	0.29	<0.046
Ambient Air Samples	Upwind	2/24/2006	AA	<0.16	<0.06	<0.12	<0.12	<0.16	<0.039
	Downwind	2/24/2006	AA	<0.17	<0.064	<0.13	<0.13	<0.18	<0.041
	AA-East	8/28/2006	AA	0.27	0.12	<0.13	<0.13	0.33	<0.042
	AA-West	8/28/2006	AA	0.19	0.075	<0.13	<0.13	0.27	<0.041

Notes

All results are presented in ug/m³


J - Results are estimated.

SV - Subslab soil vapor

IA - Indoor air


AA - Ambient air

NA - Not available




UTM GRID AND 198
MAGNETIC NORTH

SOURCE: USGS 7.5 MIN. TOPOGRAPHICAL QUADRANGLES EAST GREENVILLE, PENNSYLVANIA 1967, PHOTOREVISED 1985.

© 2006 ARCADIS GAM, Inc.	Area Manager A. ROBINSON	 6 Terry Drive Suite 300 Newtown, Pa 18940 Tel: 267/685-1800 Fax: 267/685-1801 www.arcadis-us.com	SUNBEAM PRODUCTS INC. FORMER BALLY ENGINEERED STRUCTURES <h1>SITE LOCATION MAP</h1> BALLY, PA	Project Number NP000597.002
	Project Director M. WOLFERT			Drawing Date 6 FEBRUARY, 2006
	Task Manager C. SHARPE			Figure 1
	Technical Review S. POTTER			AR100793

G:\PROJECT\AH Bally Vapour Intrusion\2006_Facility Sampling\Indoor Air & Subslab Sampling\Reports\2006.1204 Bally V\FIG-2 FORMER BES FACILITY SITE PLANDWG 12/21/2006 - 1:41:36 PM Layout: New SUBS



copyright © 20 04

LEGEND:

V

STREAM

V

VENT OR VENT FAN

H

OVERHEAD HEATING UNIT

S

SPRINKLER LINE THROUGH FLOOR

W

WATER LINE

|||||

WOOD FLOOR UNDERLAIN BY CONCRETE

|||||

STORM DRAIN

S

SUMP

SUNBEAM PRODUCTS, INC.
BALLY GROUNDWATER SITEBALLY BOROUGH
BERKS COUNTY, PENNSYLVANIAFORMER BES FACILITY
SITE PLAN
ARCADIS6 Terry Drive
Suite 300, Newtown, Pa 18940
Tel: 287/885-1800 Fax: 287/885-1801

0120

SCALE: 1"=120'



SV-2 4/7/2004	
Trichloroethene	140
1,1-Dichloroethene	180
1,1-Dichloroethane	2.1
cis-1,2-Dichloroethene	3.6
1,1,1-Trichloroethane	560
Vinyl Chloride	< 0.14

SV-1 4/7/2004	
Trichloroethene	130
1,1-Dichloroethene	500
1,1-Dichloroethane	1.1
cis-1,2-Dichloroethene	0.89
1,1,1-Trichloroethane	260
Vinyl Chloride	< 0.23

TG-5 3/23/05	
Trichloroethene	39,000
1,1-Dichloroethene	79,000
1,1-Dichloroethane	<120
cis-1,2-Dichloroethene	<35
1,1,1-Trichloroethane	<48
Vinyl Chloride	<22

TG-3 3/24/05	
Trichloroethene	9.6
1,1-Dichloroethene	<0.063
1,1-Dichloroethane	<0.13
cis-1,2-Dichloroethene	<0.14
1,1,1-Trichloroethane	0.95
Vinyl Chloride	<0.04


TG-1 3/23/05	
Trichloroethene	17,000
1,1-Dichloroethene	34 J
1,1-Dichloroethane	<35
cis-1,2-Dichloroethene	<35
1,1,1-Trichloroethane	<48
Vinyl Chloride	<22

SV-4 4/7/2004	
Trichloroethene	6,100
1,1-Dichloroethene	< 22
1,1-Dichloroethane	< 70
cis-1,2-Dichloroethene	< 22
1,1,1-Trichloroethane	< 67
Vinyl Chloride	< 14

TG-4 3/22/05	
Trichloroethene	2
1,1-Dichloroethene	<0.071
1,1-Dichloroethane	<0.14
cis-1,2-Dichloroethene	<0.14
1,1,1-Trichloroethane	0.29
Vinyl Chloride	<0.046

SV-3 4/7/2004	
Trichloroethene	13,000
1,1-Dichloroethene	< 53
1,1-Dichloroethane	< 54
cis-1,2-Dichloroethene	< 53
1,1,1-Trichloroethane	< 73
Vinyl Chloride	< 34

TG-2 3/22/05	
Trichloroethene	290
1,1-Dichloroethene	<0.72
1,1-Dichloroethane	<0.74
cis-1,2-Dichloroethene	<0.72
1,1,1-Trichloroethane	<1.0
Vinyl Chloride	<0.47



copyright © 20 04

LEGEND:	
TG-3	PROPOSED TRACER GAS SAMPLE LOCATION
SV-1	SUBSLAB VAPOR SAMPLE LOCATION (MARCH/APRIL 2004)
V	STREAM VENT OR VENT FAN
H	OVERHEAD HEATING UNIT
S	SPRINKLER LINE THROUGH FLOOR
W	WATER LINE
W	WOOD FLOOR UNDERLAIN BY CONCRETE
SD	STORM DRAIN
S	SUMP

NOTE:
ALL CONCENTRATIONS IN ug/m³

NO.	DATE	REVISION DESCRIPTION	BY
CKD			

SUNBEAM PRODUCTS, INC.
BALLY GROUNDWATER SITE
BALLY BOROUGH
BERKS COUNTY, PENNSYLVANIA


FORMER BES FACILITY
SUBSLAB SAMPLE RESULTS
2004 AND 2005



6 Terry Drive
Suite 300, Newtown, Pa 18940
Tel: 287/885-1800 Fax: 287/885-1801

0 120
SCALE: 1"=120'

PROJECT MANAGER M. BEDARD	DEPARTMENT MANAGER M. BEDARD
LEAD DESIGN PROF. F. NATTUS	CHECKED F. NATTUS
DRAWN M. WASILEWSKI	DATE 9
PROJECT NUMBER NP000597.006	DRAWING NUMBER 00795 3




SUNBEAM PRODUCTS, INC.
BALLY GROUNDWATER SITE
BALLY BOROUGH
BERKS COUNTY, PENNSYLVANIA

FORMER BES FACILITY
SUBSLAB VAPOR AND INDOOR
SAMPLING RESULTS
(2006)

ARCADIS

6 Terry Drive
Suite 300, Newtown, Pa 18940
Tel: 287/685-1800 Fax: 287/685-1801



PROJECT MANAGER M. BEDARD	DEPARTMENT MANAGER M. BEDARD
LEAD DESIGN PROF. F. NATTUS	CHECKED C. SHARPE
DRAWN M. WASILEWSKI	DATE 12/1/06
PROJECT NUMBER NP000597.006	DRAWING NUMBER 00796 4

ARCADIS

Appendix A

Standard Operating Procedures

STANDARD OPERATING PROCEDURE NO. 1

Chain-of-Custody Procedures

Scope: This procedure describes the Chain-of-Custody used to establish the necessary documentation to track sample possession from time of collection to analysis.

Purpose: The purpose of this procedure is to develop and maintain good quality control in field operations and uniformity between field personnel involved in the documentation of samples for shipment.

Equipment: Chain-of-Custody Record and Chain-of-Custody Seals

Procedure:

Prior to leaving the sampling site and/or prior to sealing sample cartons or coolers for shipment, the Chain-of-Custody Record must be completed.

Information to be provided on this form includes:

1. Project number and Location
2. Laboratory Identification
3. Sampling Party
4. Sample Identification (sample number)
5. Sample Bottle/Container Description
6. Date of Sampling
7. Signature of Persons including Chain-of-Custody and Dates and Times of Possession
8. Delivery Method (attach shipping bill)

Once the container is ready for shipment, Chain-of-Custody Seals shall be applied to the cooler in such a manner as to monitor tampering.

Upon change of possession, the record is to be signed and dated by both parties. The white (original) copy accompanies the shipment, the field sampler retains the yellow copy.

STANDARD OPERATING PROCEDURE NO. 2

Air/Vapor Sample Packaging and Shipment

- Scope: This procedure describes acceptable methodology for packaging and shipping air/vapor samples to an analytical laboratory for chemical analyses.
- Purpose: The purpose of this procedure is to provide a uniform and documented means of securely transporting environmental samples to the laboratory so as to preserve the integrity and quality of the sample(s).
- Equipment: Packaging tape, mailing labels, chain-of-custody forms, chain-of-custody seals, and shipping forms.

Procedures:

1. Assemble all sample containers from the completed sampling event.
2. Locate, identify and record type of canister for each sample identification number on a chain-of-custody form.
3. Determine the total container count and cross check sample count.
4. Check to make sure canisters were labeled properly.
5. Place some shock absorbing material in the bottom of the package to prevent direct contact of the container with the bottom of the package.
6. Arrange canister to prevent movement.
7. Place the top copy of the chain-of-custody in package.
8. Close lid and place custody seals over the joint and cover with clear tape.
9. Properly complete and address a shipping form and affix to the lid of the package. Samples should be delivered to the laboratory by the next morning.
10. Deliver to an appropriate overnight courier or the laboratory.
11. File a copy of the chain-of-custody form and the shipping form in the project file.
12. Call laboratory the next morning to confirm arrival of samples.

STANDARD OPERATING PROCEDURE NO. 3

Subslab Soil Vapor Sampling

Scope: This procedure describes the methodology to be used for the collection of subslab soil vapor samples.

Purpose: The purpose of this procedure is to ensure good quality control in field operations, uniformity between different field personnel and to allow traceability of possible cause of errors in analytical results.

Equipment: Hammer Drill; 3/8 in. bit; tedlar bags; peristaltic pump; 1/4 inch ID Masterflex tubing; concrete sealant; 6-L Summa™ canister; regulator; barometer

Procedure:

Probe Installation

1. Prior to subslab vapor probe installation, identify and mark utilities coming into the building from the outside (e.g., gas, water, sewer, refrigerant, and electrical lines) and utilities beneath (inside) the building.
2. Core hole through cement slab.
3. Drill an approximately 3/8 inch boring approximately 3 inches into subslab soil.
4. Remove the drill and cover the hole with inert material until the probe is ready to be inserted.
5. Install sampling apparatus (i.e., commercially available soil vapor point and tubing) so that it "floats" in the slab avoiding obstruction with subslab material.
6. Seal boring by creating an air-tight seal around sample tubing at ground surface using an inert material.
7. Check sampling apparatus connections. Note that barbed union fittings should be used for tubing connections. If there is a problem with obtaining fittings, the connections may be sealed using an inert material.

Soil Vapor Collection

8. Record location, date, time, weather, atmospheric pressure, approximate depth of subslab vapor samples, on Soil Vapor Sample Log.

9. Connect Tygon sample tubing to ¼ inch ID Masterflex tubing and a peristaltic pump and 1-L Tedlar bag. Use of a peristaltic pump will ensure that sampled air does not circulate through a pump causing potential cross contamination and leakage.
10. Purge vapor probe by filling two Tedlar bags or routing purge air to the exterior of the building with tubing. A purge volume of 2 L was chosen based on the assumption of a 2-inch sampling interval and an affected sample diameter of 0.61 m (2 ft). Purge rate should be approximately 200 cubic centimeters per minute (i.e., 5 minutes per Tedlar bag).
11. Record purge date and time on Soil Vapor Sample Log
12. Collect subslab vapor samples in evacuated 100 percent sim-certified 6-L Summa™ polished canisters equipped with regulators to control intake rate. Sampling rate should be approximately 200 cubic centimeters per minute. Check vacuum in canisters prior to sampling. At least 4-L of air will be collected in the canister for analysis (i.e. 20 minute collection time at 200 cubic centimeters per minute). Following sample collection, check and record final vacuum in canister. Submit canisters to a commercial laboratory for analysis. Record Sample ID, Date, Time and analysis requested on the Sample Label.
13. Record sample time on Soil Vapor Sample Log.
14. Remove sampling apparatus and seal the borehole annulus with an appropriate sealant to the original surface grade (*note duplicate sample collection method below*).

Duplicate Soil Vapor Sample Collection

1. Note duplicate sample location on Soil Vapor Sample Log.
2. Duplicate samples will be collected using duplicate tees and flow restrictors per laboratory guidance. Check vacuum in canisters prior to sampling. At least 4-L of air will be collected in the canister for analysis (i.e. 20 minute collection time at 200 cubic centimeters per minute). Following sample collection, check and record final vacuum in canister. Record Duplicate Sample ID, Date, Time and analysis requested on the Sample Label.
3. Submit canisters to a commercial laboratory for analysis.

STANDARD OPERATING PROCEDURE NO. 5

Indoor Air Quality Sampling

Scope: This procedure describes the methodology to be used for the collection of Indoor Air Quality (IAQ) samples.

Purpose: The purpose of this procedure is to ensure good quality control in field operations, uniformity between different field personnel and to allow traceability of possible cause of errors in analytical results.

Equipment: ¼ inch ID Masterflex tubing; 6-L Summa™ canister; regulator/pressure gauge; barometer, IAQ Sample Log, ARCADIS Form IAQ – 01

Procedure:

Indoor Air Quality Sample Collection

Before Sampling

1. Record location, date, time, weather, atmospheric pressure, canister number, flow controller number, on IAQ Sample Log.
2. Verify gauge operation. Gauge on flow controller should read “zero” before use.
3. Verify initial vacuum of canister per laboratory guidance.
 - a. Make sure canister valve is closed.
 - b. Remove brass cap from top of canister.
 - c. Attach gauge/flow controller to canister.
 - d. Attach brass cap to influent side of gauge/flow controller tee fitting.
 - e. Open and close valve quickly.
 - f. Read vacuum on gauge (Initial vacuum of the canister should be greater than 25 in. of Hg. If it is not call AirToxics client services at 1-800-985-5955 and arrange for replacement). Record gauge reading on “Initial Vacuum” section on chain of custody, IAQ Sample log, and on canister tag.

During Sampling

4. Install flow controller, supplied by AirToxics, to top of pressure gauge.

5. Install approximately 3 – 5 ft. tubing to end of flow controller to assure sample is collected at breathing level.
6. Open valve ½ turn.
7. Record time of sample collection start in IAQ Sample log.
8. Check and record gauge pressure in IAQ Sample log after 4 hours of sampling time have elapsed. The sample will be an integrated 8 hour sample. (Note that the flow controllers are set by the laboratory such that some vacuum will remain following the set collection period.)

After Sampling

9. Verify and record final vacuum on IAQ sampling log and on canister tag.
10. Close valve on canister by hand tightening knob.
11. Disassemble pressure gauge and flow controller. Replace brass cap on canister.
12. Complete canister sample tag.
13. Return canisters and sampling apparatus in boxes provided by laboratory.
14. Fill out chain of custody (COC) and place lab. copy of COC in box.
15. Seal box and affix custody seal.
16. Record canister to lab via appropriate shipping method, taking into account canister holding times (14 – 30 days).

Duplicate Indoor Air Quality Sample Collection

1. If a duplicate sample has been collected, note duplicate sample location on IAQ Sample Log.
2. Duplicate samples will be collected using duplicate tees and flow restrictors per laboratory guidance. Check vacuum in canisters prior to sampling. At least 4-L of air will be collected in the canister for analysis. Following sample collection, check and record final vacuum in canister. Record Duplicate Sample ID, Date, Time and analysis requested on the Sample Label.
3. Submit canisters to a commercial laboratory for analysis as described above.

STANDARD OPERATING PROCEDURE NO. 5

Indoor Air Quality Sampling

Scope: This procedure describes the methodology to be used for the collection of Indoor Air Quality (IAQ) samples.

Purpose: The purpose of this procedure is to ensure good quality control in field operations, uniformity between different field personnel and to allow traceability of possible cause of errors in analytical results.

Equipment: ¼ inch ID Masterflex tubing; 6-L Summa™ canister; regulator/pressure gauge; barometer, IAQ Sample Log, ARCADIS Form IAQ - 01

Procedure:

Indoor Air Quality Sample Collection

Before Sampling

1. Record location, date, time, weather, atmospheric pressure, canister number, flow controller number, on IAQ Sample Log.
2. Verify gauge operation. Gauge on flow controller should read “zero” before use.
3. Verify initial vacuum of canister per laboratory guidance.
 - a. Make sure canister valve is closed.
 - b. Remove brass cap from top of canister.
 - c. Attach gauge/flow controller to canister.
 - d. Attach brass cap to influent side of gauge/flow controller tee fitting.
 - e. Open and close valve quickly.
 - f. Read vacuum on gauge (Initial vacuum of the canister should be greater than 25 in. of Hg. If it is not call AirToxics client services at 1-800-985-5955 and arrange for replacement). Record gauge reading on “Initial Vacuum” section on chain of custody, IAQ Sample log, and on canister tag.

During Sampling

4. Install flow controller, supplied by AirToxics, to top of pressure gauge.

5. Install approximately 3 – 5 ft. tubing to end of flow controller to assure sample is collected at breathing level.
6. Open valve ½ turn.
7. Record time of sample collection start in IAQ Sample log.
8. Return to collect the sample 8 hours after deploying canister. The sample will be an integrated 8 hour sample. (Note that the flow controllers are set by the laboratory such that some vacuum will remain following the set collection period.)

After Sampling

9. Verify and record final vacuum on IAQ sampling log and on canister tag.
10. Close valve on canister by hand tightening knob.
11. Disassemble pressure gauge and flow controller. Replace brass cap on canister.
12. Complete canister sample tag.
13. Return canisters and sampling apparatus in boxes provided by laboratory.
14. Fill out chain of custody (COC) and place lab. copy of COC in box.
15. Seal box and affix custody seal.
16. Record canister to lab via appropriate shipping method, taking into account canister holding times (14 – 30 days).

Duplicate Indoor Air Quality Sample Collection

1. If a duplicate sample has been collected, note duplicate sample location on IAQ Sample Log.
2. Duplicate samples will be collected using duplicate tees and flow restrictors per laboratory guidance. Check vacuum in canisters prior to sampling. At least 4-L of air will be collected in the canister for analysis. Following sample collection, check and record final vacuum in canister. Record Duplicate Sample ID, Date, Time and analysis requested on the Sample Label.
3. Submit canisters to a commercial laboratory for analysis as described above.

ARCADIS

Appendix B

Sample Logs



ARCADIS G&M.

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BAL-IAQ-01-822406
Date 2/24/06
Time 1030
Weather Partly cloudy, wind gusts
up to 40 mph, 9.5°C

Project/No. NP000597.0006.00007

Sampling Personnel DBK

Duplicate ID —

Barometric Pressure 29.56 in Hg

Corresponding Subslab ID

DESCRIPTION OF SAMPLE LOCATION:

Location	Alt Bally Facility
Facility	Former BES
Floor Type	Concrete
Cracks?	
Room Dimensions	
Tie Meas. 1	
Tie Meas. 2	
Tie Meas. 3	
Intake Height	

Cannister Type	511mmg
Cannister No.	11882
Flow Regulator No.	11882
Pre Sample Vacuum	-31 in Hg
Begin Sample Time	1030
Mid Sample Time	1310
Mid Sample Vacuum	-19.5
End Sample Time	7:28
End Sample Vacuum	-6.0 "Hg

FIELD PARAMETERS:

Sample Method Ambient air - 60L Summa canister

Sample Description _____

PID 1


FID 1

CONTAINER DESCRIPTION:

	<u>Container</u> <u>6L Summa</u>	<u>Analysis</u> <u>TO-15</u>
Total		

Total

Location Diagram (Show Ties)





ARCADIS G&M

See backside for resampling

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BAL-IAQ-02-022406

Project/No.

NP000597.0006.00007

Date

2/24/2006

Sampling Personnel

D.K.

Time

850

Duplicate ID

—

Weather

Sunny, Windy - gusts @ 40 mph

Barometric Pressure

29.47 in. Hg

Corresponding Subslab ID

DESCRIPTION OF SAMPLE LOCATION:

Location

Shutter Glow

Cannister Type

SUMMA

Facility

Former BES

Cannister No.

35242

Floor Type

Concrete

Flow Regulator No.

35242

Cracks?

Concrete Y.

Pre Sample Vacuum

-30

Room Dimensions

Begin Sample Time

8:50 AM

Tie Meas. 1

Mid Sample Time

1150

Tie Meas. 2

Mid Sample Vacuum

-28.5

Tie Meas. 3

End Sample Time

705 PM

Intake Height

End Sample Vacuum

-12:0 "Hg

FIELD PARAMETERS:

Sample Method

Indoor Air per WP

Sample Description

PID


FID

CONTAINER DESCRIPTION:

Container
6L SummaAnalysis
TO-15

Total

Location Diagram (Show Ties)



Note: The pressure reading bounced back -25 quickly. Then ~~the~~ it was tightened up to secure the Sealing. The reading moved to -15 slowly

G:\PROJECT\AH Bally, PA\Vapor Intrusion\2006_Facility Sampling\Indoor Air & Subslab Sampling\workplan 1005\2006_revision\Attachment 2 - indoor air survey and log\Indoor Air Quality SampleForm.xls

Starting 8:30 AM. @ 9:10 AM. The reading is -4 in. Hg. @ 9:50

AR100808



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BAL-IAQ-3A-022406
 Date 2/24/06
 Time 9:21
 Weather Sunny, gusts \leq 40 mph

Project/No. NP000597.0006.00007
 Sampling Personnel DBK
 Duplicate ID —
 Barometric Pressure 29.47 in Hg
 Corresponding Subslab ID —

DESCRIPTION OF SAMPLE LOCATION:

Location —
 Facility Former BES
 Floor Type Linoleum
 Cracks? —
 Room Dimensions —
 Tie Meas. 1 See diagram
 Tie Meas. 2 —
 Tie Meas. 3 —
 Intake Height —

Cannister Type SUNMA
 Cannister No. ~~2407~~ 2407
 Flow Regulator No. 24007
 Pre Sample Vacuum -20
 Begin Sample Time 9:21
 Mid Sample Time 12:40
 Mid Sample Vacuum -19.5 in Hg
 End Sample Time 6:20
 End Sample Vacuum -6.0" Hg

FIELD PARAMETERS:

Sample Method Indoor air per W.P.
 Sample Description —

PID —
 FID —


CONTAINER DESCRIPTION:

Container
 6L Summa

Analysis
 TO-15

Total

Location Diagram (Show Ties)





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID IAQ-38-DUP ²⁰²²⁴⁰⁶ Project/No. NP000597.0006.00007
 Date 2/24/06 Sampling Personnel DBK
 Time 923 Duplicate ID _____
 Weather Sunny, windy - gusts ≤ 40 mph Barometric Pressure 29.65 in Hg
 Corresponding Subslab ID _____

DESCRIPTION OF SAMPLE LOCATION:

Location _____	Cannister Type <u>Summa</u>
Facility <u>Former BES</u>	Cannister No. <u>11006</u>
Floor Type <u>Concrete</u>	Flow Regulator No. <u>11006</u>
Cracks? _____	Pre Sample Vacuum <u>-30.0 in Hg</u>
Room Dimensions _____	Begin Sample Time <u>923</u>
Tie Meas. 1 <u>See diagram</u>	Mid Sample Time <u>1251</u>
Tie Meas. 2 _____	Mid Sample Vacuum <u>-20.0 in Hg</u>
Tie Meas. 3 _____	End Sample Time <u>18.0</u>
Intake Height _____	End Sample Vacuum <u>630 PM</u>

FIELD PARAMETERS:

Sample Method Indoor Air per WP.
 Sample Description _____

 PID _____
 FID _____


CONTAINER DESCRIPTION:

Container
6L Summa

 Total _____

Analysis
TO-15

Location Diagram (Show Ties)





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BAL IAQ -03B-DUP-022406 Project/No. NP000597.0006.00007
 Date 2/24/2006 Sampling Personnel DBK
 Time 953 Duplicate ID BAL-IAQ-03B-DUP-022406
 Weather Sunny, Windy - gusts ≤ 40 mph Barometric Pressure 29.65 in Hg
 Corresponding Subslab ID _____

DESCRIPTION OF SAMPLE LOCATION:

Location	_____	Cannister Type	<u>Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>34423</u>
Floor Type	<u>linoleum Concrete</u>	Flow Regulator No.	<u>140086 34423</u>
Cracks?	_____	Pre Sample Vacuum	<u>-27.5 inHg</u>
Room Dimensions	_____	Begin Sample Time	<u>9:53</u>
Tie Meas. 1	<u>See diagram</u>	Mid Sample Time	<u>12:51</u>
Tie Meas. 2	_____	Mid Sample Vacuum	<u>-17.0</u>
Tie Meas. 3	_____	End Sample Time	<u>6:30 PM</u>
Intake Height	_____	End Sample Vacuum	<u>-9.5</u>

FIELD PARAMETERS:

Sample Method Indoor air per W.P.
 Sample Description _____

PID _____
 FID _____

Location Diagram (Show Ties)

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
Total	_____

See IAQ - 3B-DUP



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BA1-IAQ-04-022406
Date 2/24/2006
Time 910
Weather Sunny, windy up to 40mph

Project/No. NP000597.0006.00007

Sampling Personnel K.M

Duplicate ID _____

Barometric Pressure 29.47 in. Hg

Corresponding Subslab ID _____

DESCRIPTION OF SAMPLE LOCATION:

Location Alt Bally, Bally PA
Facility Former BES
Floor Type Concrete
Cracks? _____
Room Dimensions _____
Tie Meas. 1 See diagram
Tie Meas. 2 _____
Tie Meas. 3 _____
Intake Height _____

Cannister Type	Summa
Cannister No.	11885
Flow Regulator No.	11885
Pre Sample Vacuum	-30
Begin Sample Time	910
Mid Sample Time	1210
Mid Sample Vacuum	-17.0
End Sample Time	506 521
End Sample Vacuum	-6.0

FIELD PARAMETERS:


Sample Method	Per WP
Sample Description	Indoor Air

PID _____
FID _____

CONTAINER DESCRIPTION:

	Container 6L Summary
Total	

Analysis
TO-15

Total



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BAL-IAQ05-022406 Project/No. NP000597.0006.00007
 Date 2/24/06 Sampling Personnel _____
 Time 935 Duplicate ID _____
 Weather Sunny, Windy - gusts ~ 40 mph Barometric Pressure 29.47 in. Hg
 Corresponding Subslab ID _____

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>S&W Metal Product back</u>	Cannister Type	<u>SUMMA</u>
Facility	<u>Former BES</u>	Cannister No.	<u>13846</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>13846</u>
Cracks?	_____	Pre Sample Vacuum	<u>-36</u>
Room Dimensions	_____	Begin Sample Time	<u>9:35 AM</u>
Tie Meas. 1	_____	Mid Sample Time	<u>1330</u>
Tie Meas. 2	_____	Mid Sample Vacuum	<u>-23.5</u>
Tie Meas. 3	_____	End Sample Time	<u>734</u>
Intake Height	_____	End Sample Vacuum	<u>-13.5</u>

FIELD PARAMETERS:


Sample Method Indoor Air per WP.
 Sample Description _____

PID _____
 FID _____

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
Total	_____

Location Diagram (Show Ties)



Influent tubing ~ 6.0' above ground.



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID	BAZ-IAQ-6-022406	Project/No.	NP000597.0006.00007
Date	2/24/06	Sampling Personnel	DBK
Time	925	Duplicate ID	
Weather	Sunny, Windy - gusts ≤ 40 mph	Barometric Pressure	29.47 in. Hg
		Corresponding Subslab ID	

DESCRIPTION OF SAMPLE LOCATION:

Location	SX W Metal Product	Cannister Type	SUMMA
Facility	Former BES	Cannister No.	34364 34364
Floor Type	Concrete	Flow Regulator No.	34364 34364
Cracks?		Pre Sample Vacuum	-30
Room Dimensions		Begin Sample Time	9:25AM
Tie Meas. 1	See diagram	Mid Sample Time	1325
Tie Meas. 2		Mid Sample Vacuum	-18.5
Tie Meas. 3		End Sample Time	1801
Intake Height		End Sample Vacuum	-8.5

FIELD PARAMETERS:

Sample Method Indoor Air per WP

Sample Description


PID _____
FID _____

CONTAINER DESCRIPTION:

	<u>Container</u> <u>6L Summa</u>	<u>Analysis</u> <u>TO-15</u>
	<u> </u>	<u> </u>
	<u> </u>	<u> </u>
	<u> </u>	<u> </u>
	<u> </u>	<u> </u>
	<u> </u>	<u> </u>
	<u> </u>	<u> </u>
Total	<u> </u>	<u> </u>

Total

Location Diagram (Show Ties)



Influent port ~ 4.0' above ground.
(No tubing)



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

BAL-
 Sample ID IAQ-07-022406
 Date 2/24/2006
 Time 1010
 Weather Sunny, Windy, gusts \leq 40 mph
 Project/No. NP000597.0006.00007
 Sampling Personnel K.M
 Duplicate ID _____
 Barometric Pressure 29.47 in. Hg
 Corresponding Subslab ID _____

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Gregory wood working</u>	Cannister Type	<u>SUMMA</u>
Facility	<u>Former BES</u>	Cannister No.	<u>4866</u>
Floor Type	<u>Linoeum</u>	Flow Regulator No.	<u>14866</u>
Cracks?	_____	Pre Sample Vacuum	<u>-30</u>
Room Dimensions	_____	Begin Sample Time	<u>1010</u>
Tie Meas. 1	<u>See diagram</u>	Mid Sample Time	<u>1220</u>
Tie Meas. 2	_____	Mid Sample Vacuum	<u>-25.0</u>
Tie Meas. 3	_____	End Sample Time	<u>6:50</u>
Intake Height	_____	End Sample Vacuum	<u>-11.5</u>

FIELD PARAMETERS:

Sample Method Indoor air per W.P.
 Sample Description _____


 PID _____
 FID _____

CONTAINER DESCRIPTION:

Container
6L Summa

 Total _____

Analysis
TO-15





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID	BAL - IAG - UW - 022906	Project/No.	NP000597.0006.00007
Date	2/24/06	Sampling Personnel	DBK
Time	955	Duplicate ID	
Weather	Mostly sunny, 35°F, gusty winds up to 45 mph	Barometric Pressure	29.62 in Hg
		Corresponding Subslab ID	

DESCRIPTION OF SAMPLE LOCATION:

Location	Outside facility - upwind	Cannister Type	SUMMA
Facility	Former BES	Cannister No.	94304
Floor Type	—	Flow Regulator No.	94304
Cracks?		Pre Sample Vacuum	-30 inHg
Room Dimensions		Begin Sample Time	09:55
Tie Meas. 1	Corner of Facility	Mid Sample Time	1352
Tie Meas. 2		Mid Sample Vacuum	-17.5
Tie Meas. 3		End Sample Time	7:00 PM
Intake Height		End Sample Vacuum	-7.0

FIELD PARAMETERS:


Sample Method	Per WP
Sample Description	Upwind

PID _____

FID _____

CONTAINER DESCRIPTION:[illegible]**Total**

Location Diagram (Show Ties)



No tubing. Influent port ~ 2.0' above ground.



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID BAL - IAQ-DW-022406
 Date 2/24/06
 Time 10:05
 Weather Sunny, 35°F, gusty winds

Project/No. NP000597.0006.00007
 Sampling Personnel DBK
 Duplicate ID —
 Barometric Pressure 29.65" Hg
 Corresponding Subslab ID —

DESCRIPTION OF SAMPLE LOCATION:

Location —
 Facility Former BES
 Floor Type Grass
 Cracks? —
 Room Dimensions —
 Tie Meas. 1 See diagram
 Tie Meas. 2 —
 Tie Meas. 3 —
 Intake Height —

Cannister Type SUMMA
 Cannister No. 34749
 Flow Regulator No. 34749
 Pre Sample Vacuum -30 in Hg
 Begin Sample Time 10:05
 Mid Sample Time 1343
 Mid Sample Vacuum -18.0
 End Sample Time 644 PM
 End Sample Vacuum -7.9

FIELD PARAMETERS:


Sample Method —
 Sample Description —

PID —
 FID —

CONTAINER DESCRIPTION:

Container	Analysis
6L Summa	TO-15
Total	

Location Diagram (Show Ties)



No tubing, Influent port ~ 2.0' above ground.



ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>BAL-SV-009-030106</u>	Project/No.	<u>NP000597.0006</u>
Date	<u>3.1.06</u>	Sampling Personnel	<u>DOM + DOK</u>
Time	<u>0931</u>	Duplicate ID	<u>n/a</u>
Weather	<u>clear, low 30s</u>	Barometric Pressure	<u>29.29" Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>S+G</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>23882</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>23882</u>
Cracks?		Pre Sample Vacuum	<u>-28.6" Hg</u>
Room Dimensions		Sample Depth (ft)	<u>7"</u>
Tie Meas. 1	<u>42' to I-beam w/ OH tank</u>	Purge Time	<u>0917-0929</u>
Tie Meas. 2	<u>115' to E wall</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>252' to N wall</u>	Purge Volume	<u>2.5 L</u>
		Begin Sample Time	<u>0931</u>
		End Sample Time	<u>1011</u>
		End Sample Vacuum	<u>-4.0" Hg</u>

FIELD PARAMETERS:


Sample Method	<u>Purge 2.5 L through scrubber cell then attach Summa</u>
Sample Description	<u>Sub Slab Vapor - slab ~ 16" thick</u>

PID	<u>116 ppm</u>
FID	<u>n/a</u>

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
<u>0.5L Scrub. cell</u>	<u>Radon</u>
TOTAL:	<u>2</u>

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>BAL-SV-010-022806</u>	Project/No.	<u>NP000597.0006</u>
Date	<u>2.28.06</u>	Sampling Personnel	<u>ROM+DBK</u>
Time	<u>1326</u>	Duplicate ID	<u>n/a</u>
Weather	<u>mostly clear, low 30s</u>	Barometric Pressure	<u>29.35" Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Hunsinger Plastics (HPE)</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>9544</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>9544</u>
Cracks?		Pre Sample Vacuum	<u>-30.0" Hg</u>
Room Dimensions		Sample Depth (ft)	<u>Drilled ~8", hanging probe ~8" above bottom</u>
Tie Meas. 1	<u>22' to door wall</u>	Purge Time	<u>1341-1353</u>
Tie Meas. 2	<u>6.5' to I-beam</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>48' to N wall near overhead door</u>	Purge Volume	<u>2.5L</u>
		Begin Sample Time	<u>1355</u>
		End Sample Time	<u>1431</u>
		End Sample Vacuum	<u>-4.5" Hg</u>
Sample Method	<u>6L Summa, sub slab, TO-15 analysis</u>		
Sample Description	<u>Sub Slab Vapor</u>		

FIELD PARAMETERS:

PID 5.2 ppm; background: 0.5 ppm

FID n/a


CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
<u>0.13L scin. cell</u>	<u>Radon</u>

TOTAL:

2

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>BAL-SV-03B-022806</u>	Project/No.	<u>NP000597.0006</u>
Date	<u>2.28.06</u>	Sampling Personnel	<u>ROM + DBK</u>
Time	<u>0929</u>	Duplicate ID	<u>n/a</u>
Weather	<u>mostly clear, mid 20s</u>	Barometric Pressure	<u>29.35" Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Storage Maint. Space</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>403</u>
Floor Type	<u>Concrete w/ areas of hardwood</u>	Flow Regulator No.	<u>403</u>
Cracks?	<u>widely segmented</u>	Pre Sample Vacuum	<u>-29.6" Hg</u>
Room Dimensions	<u>~59' x 79'</u>	Sample Depth (ft)	<u>8" below surface</u>
Tie Meas. 1	<u>29.9"</u>	Purge Time	<u>0917 - 0929</u>
Tie Meas. 2	<u>~74.5'</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>28' 11"</u>	Purge Volume	<u>2.5 L</u>

FIELD PARAMETERS:


Sample Method	<u>Purge 2.5L through scintillation cell, then apply Summa</u>	End Sample Time	<u>1005</u>
Sample Description	<u>Sub Slab Vapor - Slab ~ 11" thick</u>	End Sample Vacuum	<u>-3.0" Hg</u>
	<u>Indoor Air Quality (IAQ-4)</u>		
PID	<u>3.7 ppm</u>		
FID	<u>n/a</u>		

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
<u>.13L cell</u>	<u>Radon</u>

TOTAL: 2

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID BAL-SV-04B-022706 Project/No. NP000597.0006.
 Date 2/27/06 Sampling Personnel DBK, FS.
 Time 1541 Duplicate ID —
 Weather Partly cloudy, 25°F Barometric Pressure 29.56" Hg

DESCRIPTION OF SAMPLE LOCATION:

Location Impress Industries
 Facility Former BES
 Floor Type Concrete
 Cracks? No
 Room Dimensions _____
 Tie Meas. 1 13' 3"
 Tie Meas. 2 19' 10"
 Tie Meas. 3 ~50'

Cannister Type 6L Summa
 Cannister No. 33980
 Flow Regulator No. 33980
 Pre Sample Vacuum -28
 Sample Depth (ft) hole ~14", hanging probe at 6"
 Purge Time 12.5 min
 Purge Rate 200 ml/min
 Purge Volume ~2.5L
 Begin Sample Time 1617
 End Sample Time 1657
 End Sample Vacuum -3

FIELD PARAMETERS:

Sample Method 6 L Summa, TO-15 low level, sub-slab
 Sample Description Sub Slab Vapor


PID 97.1 ppm, 0.8 ppm - ambient
 FID _____

CONTAINER DESCRIPTION:

Container	Analysis
6L Summa	TO-15

TOTAL:

11 by 20 ft
 Location Diagram (Show Tiles)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID BAL-SV-005-1022806
 Date 2.28.06
 Time 1123
 Weather mostly clear, upper 20s

Project/No. NP000597.0006
 Sampling Personnel ROM+DBK
 Duplicate ID 3AL-SV-050-022806
 Barometric Pressure 29.35" Hg

DESCRIPTION OF SAMPLE LOCATION:

Location LEZ Public Storage
 Facility Former BES
 Floor Type Concrete
 Cracks? None from tank feet
 Room Dimensions ~115x
 Tie Meas. 1 20' to S wall
 Tie Meas. 2 30'8" to E wall w/ door
 Tie Meas. 3 18' to stand close room

Cannister Type 6 L Summa
 Cannister No. 94949 (Dup - 94883) 1084
 Flow Regulator No. 94949 (40-100)
 Pre Sample Vacuum -28.4" Hg (Dup - -28.5" Hg)
 Sample Depth (ft) 14"
 Purge Time 1110 - 1122
 Purge Rate 200 mL/min
 Purge Volume 2.5 L
 Begin Sample Time 1123
 End Sample Time 1200
 End Sample Vacuum -3.5" Hg Dp = -9.9" Hg

FIELD PARAMETERS:


Sample Method Purge 2.5L through scintillation cell, attached Summa for sample then attached
 Sample Description Sub Slab Vapor - slab ~17" thick duplicate Summa
Indoor Air Quality (IAQ-4)
 PID 1.6 ppm background: 0.3 ppm
 FID n/a

CONTAINER DESCRIPTION:

Container	Analysis
6L Summa	TO-15
3L scin. cell	Radon

TOTAL: 2 + 20 duplicate

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID BAL-SV-06-022706
 Date 2-27-06
 Time 1220
 Weather Partly cloudy

Project/No. NP000597.0006
 Sampling Personnel DBK, FS
 Duplicate ID —
 Barometric Pressure 29.65" Hg

DESCRIPTION OF SAMPLE LOCATION:

Location S&G
 Facility Former BES
 Floor Type Concrete ~12" thick
 Cracks? None
 Room Dimensions 300' x 500'
 Tie Meas. 1 40'
 Tie Meas. 2 8' 7"
 Tie Meas. 3 11' 4"

Cannister Type Summa
 Cannister No. 937
 Flow Regulator No. 937
 Pre-Sample Vacuum -29
 Sample Depth 8' at ~6" 12" Flashed probe
 Purge Time 12.5 min
 Purge Rate 200ml/min
 Purge Volume ~2.5 L
 Begin Sample Time 1220
 End Sample Time 13:12
 End Sample Vacuum -15

FIELD PARAMETERS:

Sample Method Sub Slab Vapor
 Sample Description Sub Slab Vapor

PID 0.3 PPM
 FID —


CONTAINER DESCRIPTION:

Container
6L Summa

Analysis
TO-15

TOTAL:

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID BAL-SV-07-022706 Project/No. NP000597.0006
 Date 2/27/26 Sampling Personnel DBK
 Time 1400 Duplicate ID —
 Weather Partly cloudy, light snow Barometric Pressure 29.56" Hg
25°F

DESCRIPTION OF SAMPLE LOCATION:

Location S&G Cannister Type SUMMA
 Facility Former BES Cannister No. 421
 Floor Type Asphalt Flow Regulator No. 421
 Cracks? No Pre Sample Vacuum -30
 Room Dimensions 150' x 150' Sample Depth (ft) Flooring 6" below ground surface
 Tie Meas. 1 — Purge Time 30 min Hole in 12"
 Tie Meas. 2 — Purge Rate ~206 mL/min
 Tie Meas. 3 — Purge Volume 2.5 L
 Begin Sample Time 1413
 End Sample Time 1453
 End Sample Vacuum -3.5"

FIELD PARAMETERS:

Sample Method 6L Summa Sub Slab - 30 min. sample
 Sample Description Sub Slab Vapor

PID 44.1 ppm, ambient = 1.7 ppm
 FID —

Mid Sample time 1430
 Mid Sample Vac -14"
 Sample time = 1443
 Sample Vac = -6.0"


CONTAINER DESCRIPTION:

Container
6L Summa

Analysis
TO-15

TOTAL:

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>BAL-SV-008-022806</u>	Project/No.	<u>NP000597.0006</u>
Date	<u>2-28-06</u>	Sampling Personnel	<u>RDM + DBK</u>
Time		Duplicate ID	<u>n/a</u>
Weather	<u>clear, mid-upper 30s</u>	Barometric Pressure	

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Basement below Curves</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>02242</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>02242</u>
Cracks?	<u>no</u>	Pre Sample Vacuum	<u>-30" Hg</u>
Room Dimensions		Sample Depth (ft)	<u>2.0"</u>
Tie Meas. 1	<u>7'9" to doorwall (W)</u>	Purge Time	<u>1456-1508</u>
Tie Meas. 2	<u>14'9" to S wall</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>30'9" to N wall</u>	Purge Volume	<u>2.5 L</u>
		Begin Sample Time	<u>1509</u>
		End Sample Time	<u>1547</u>
		End Sample Vacuum	<u>-4.0" Hg</u>


FIELD PARAMETERS:

Sample Method	<u>Purge 2.5 L through scintillation cell then attach Summa</u>
Sample Description	<u>Sub Slab Vapor</u>
	<u>Indoor Air Quality (IAQ-3A + IAQ-3B) A: upstairs B: basement</u>
PID	<u>0</u>
FID	<u>n/a</u>

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
<u>0.13L Scin. cell</u>	<u>Radon</u>
TOTAL:	<u>2</u>

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID BAL-SV-009-030106
 Date 3.1.06
 Time 0931
 Weather clear, low 30s

Project/No. NP000597.0006.
 Sampling Personnel DOM + DSK
 Duplicate ID n/a
 Barometric Pressure 29.29" Hg

DESCRIPTION OF SAMPLE LOCATION:

Location S+G
 Facility Former BES
 Floor Type Concrete
 Cracks?
 Room Dimensions
 Tie Meas. 1 42' to I-beam w/ off tank
 Tie Meas. 2 115' to E wall
 Tie Meas. 3 252' to N wall

Cannister Type 6L Summa
 Cannister No. 23882
 Flow Regulator No. 23882
 Pre Sample Vacuum -28.6" Hg
 Sample Depth (ft) 7"
 Purge Time 0917-0929
 Purge Rate 200 mL/min
 Purge Volume 2.5 L
 Begin Sample Time 0931
 End Sample Time 1011
 End Sample Vacuum -4.0" Hg

FIELD PARAMETERS:

Sample Method purge 2.5 L through scintillation cell then attach Summa
 Sample Description Sub Slab Vapor - slab ~ 16" thick

PID 116 ppm
 FID n/a

CONTAINER DESCRIPTION:


Container
6L Summa
0.13L Scin. cell

Analysis
TO-15
Radon

TOTAL:

2

Location Diagram (Show Ties)



I-beam supporting
 prior off tank



ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>BAL-SV-010-022806</u>	Project/No.	<u>NP000597.0006</u>
Date	<u>2.28.06</u>	Sampling Personnel	<u>ROM+DBK</u>
Time	<u>1326</u>	Duplicate ID	<u>n/a</u>
Weather	<u>mostly clear, low 30s</u>	Barometric Pressure	<u>29.35" Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Hunsinger Plastics (HPE)</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>9544</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>9544</u>
Cracks?		Pre Sample Vacuum	<u>-30.0" Hg</u>
Room Dimensions		Sample Depth (ft)	<u>Drilled ~8", hanging probe ~8" above bottom</u>
Tie Meas. 1	<u>22' to door wall</u>	Purge Time	<u>1341-1353</u>
Tie Meas. 2	<u>6.5' to I-beam</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>48' to N wall new overhead door</u>	Purge Volume	<u>2.5L</u>
		Begin Sample Time	<u>1355</u>
		End Sample Time	<u>1431</u>
		End Sample Vacuum	<u>-4.5" Hg</u>
Sample Method	<u>6L Summa, sub slab, TO-15 analysis</u>		
Sample Description	<u>Sub Slab Vapor</u>		


FIELD PARAMETERS:

PID 5.2 ppm; background: 0.5 ppm
 FID n/a

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
<u>0.13L scin. cell</u>	<u>Radon</u>
_____	_____
_____	_____
_____	_____
TOTAL: <u>2</u>	

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID Bal-SV-11-030106
 Date 3/1/06
 Time 1107-1150
 Weather Sunny, 75°F

Project/No. NP000597.0006.
 Sampling Personnel DBL, RDM
 Duplicate ID —
 Barometric Pressure 29.36" Hg

DESCRIPTION OF SAMPLE LOCATION:

Location Gregory Woodworking
 Facility Former BES
 Floor Type concrete
 Cracks? unknown
 Room Dimensions 4'6" x 67'
 Tie Meas. 1 19'5" from E wall
 Tie Meas. 2 15' from S wall
 Tie Meas. 3 39" from N wall

Cannister Type 6L Summa
 Cannister No. 23986
 Flow Regulator No. 23986
 Pre Sample Vacuum -33" Hg
 Sample Depth (ft) 3"
 Purge Time 1055-1107
 Purge Rate 200 mL/min
 Purge Volume 2.5 L
 Begin Sample Time 1107
 End Sample Time 1150
 End Sample Vacuum -4.4" Hg

FIELD PARAMETERS:

Sample Method purge 2.5 L through scrubillation cell, then attach Summa
 Sample Description Sub Slab Vapor - slab: 6" thick

PID —
 FID n/a


CONTAINER DESCRIPTION:


Container	Analysis
6L Summa	TO-15
0.13L Schi. cell	Radon

TOTAL:

2

Location Diagram (Show Ties)





Sample ID	AA-West	Project/No.	NP000597.0006.00004
Date	8/28/06	Sampling Personnel	R.Gorrie, A. Faulkner
Time	1110	Duplicate ID	—
Weather	Cloudy, showers	Barometric Pressure	978 mb/hPa
		Corresponding Subslab ID	—

Location	West side of facility	Cannister Type	6 L Summa
Facility	Former BES	Cannister No.	33945
Floor Type	—	Flow Regulator No.	FC00251
Cracks?	—	Pre Sample Vacuum	-30 mm Hg
Room Dimensions		Begin Sample Time	1145
Tie Meas. 1	4.5'	Mid Sample Time	1515
Tie Meas. 2	6.5'	Mid Sample Vacuum	-18 "Hg
Tie Meas. 3	35.0'	End Sample Time	2125
Intake Height	~3 ft.	End Sample Vacuum	-5" Hg


Sample Method	IA SOP.
Sample Description	Ambient air sample on west side of facility.

PID 6.0 ppm.

FID

Container
6L Summa

Analysis
TO-15

Total



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID AA - East
 Date 6/28/06
 Time 1110
 Weather Cloudy, showers

Project/No. NP000597.0006.00004
 Sampling Personnel R. Gorrie, A. Faulkner
 Duplicate ID —
 Barometric Pressure 998 mb/hPa
 Corresponding Subslab ID —

DESCRIPTION OF SAMPLE LOCATION:

Location East side of facility
 Facility Former BES
 Floor Type —
 Cracks? —
 Room Dimensions —
 Tie Meas. 1 24'
 Tie Meas. 2 33'
 Tie Meas. 3 1.3'
 Intake Height ~3'

Cannister Type 6 L Summa
 Cannister No. 22500
 Flow Regulator No. FC00287
 Pre Sample Vacuum 7-30" Hg
 Begin Sample Time 1140
 Mid Sample Time 1526
 Mid Sample Vacuum -19" Hg
 End Sample Time 2010
 End Sample Vacuum -4.5" Hg

FIELD PARAMETERS:

Sample Method IA SOP.
 Sample Description Ambient air on east side of facility.

PID 0.00 ppm
 FID —


Location Diagram (Show Ties)

CONTAINER DESCRIPTION:

Container
6L Summa

Analysis
TO-15

Total





INDOOR AIR QUALITY SAMPLE LOG


Project/No.	NP000597.0006.00004
Sampling Personnel	R.Gorrie, A. Faulkner
Duplicate ID	IA-A-1 (dup)
Barometric Pressure	998 mb/h Pa
Corresponding Subslab ID	SS-A-1

Cannister Type	6 L Summa
Cannister No.	13670 / 95671 (dup)
Flow Regulator No.	FC00615 / FC00831 (dup)
Pre Sample Vacuum	> -30 mmHg / -30 mmHg
Begin Sample Time	1225
Mid Sample Time	-16.5 "Hg / -16 "Hg
Mid Sample Vacuum	1600
End Sample Time	2100
End Sample Vacuum	-5.0" / -5.0"

Sample Method	TA SOP
Sample Description	Outside Inpress building: - Heavy duty engine cleaner/degreaser (Engine Breaker) - Rustoleum (acetone, xylene)
PID	0.0 ppm
FID	

[illegible]

Location Diagram (Show Ties)





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID IA-A-2
 Date 8/28/06
 Time 1120
 Weather Cloudy, showers

Project/No. NP000597.0006.00004
 Sampling Personnel R. Gorrie, A. Faulkner
 Duplicate ID —
 Barometric Pressure 998 mb/hPa
 Corresponding Subslab ID SS-A-2

DESCRIPTION OF SAMPLE LOCATION:

Location Hunsinger Plastics
 Facility Former BES
 Floor Type concrete
 Cracks? —
 Room Dimensions
 Tie Meas. 1 0.5'
 Tie Meas. 2 15'
 Tie Meas. 3 25'
 Intake Height 3'

Cannister Type 6 L Summa
 Cannister No. 35142
 Flow Regulator No. FC00437/10770
 Pre Sample Vacuum -30 mmHg
 Begin Sample Time 1200
 Mid Sample Time 1520
 Mid Sample Vacuum -21 "Hg
 End Sample Time ~~2005~~ 2210
 End Sample Vacuum ~~-21 "Hg~~ -7.5 "Hg

FIELD PARAMETERS:

Sample Method IA-SOP
 Sample Description Hunsinger Plastics indoor air
Plastics materials open - labeled PVC.
 PID 0.0.
 FID —


CONTAINER DESCRIPTION:

Container
6L Summa

 Total _____

Analysis
TO-15

Location Diagram (Show Ties)





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID	<u>IA-A-4</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>8/28/06</u>	Sampling Personnel	<u>R. Gorrie, A. Faulkner</u>
Time	<u>1050</u>	Duplicate ID	<u>—</u>
Weather	<u>Cloudy, Showers</u>	Barometric Pressure	<u>997 mb/hPa</u>
		Corresponding Subslab ID	<u>IA SS-A-4</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Gregory Woodworking</u>	Cannister Type	<u>3387 6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>3387 3387</u>
Floor Type	<u>—</u>	Flow Regulator No.	<u>FC00796</u>
Cracks?	<u>no.</u>	Pre Sample Vacuum	<u>-30" Hg</u>
Room Dimensions	<u>—</u>	Begin Sample Time	<u>1105</u>
Tie Meas. 1	<u>—</u>	Mid Sample Time	<u>1510</u>
Tie Meas. 2	<u>—</u>	Mid Sample Vacuum	<u>-15.5" Hg</u>
Tie Meas. 3	<u>—</u>	End Sample Time	<u>2000</u>
Intake Height	<u>—</u>	End Sample Vacuum	<u>-5.5" Hg</u>


FIELD PARAMETERS:

Sample Method	<u>IA SOP</u>
Sample Description	<u>Greg. Woodworking. Inlet located 3.3 ft. above ground.</u>
	<u>• Stryper: Acetone / toluene / methanol / methylene chloride</u>
PID	<u>0.0 ppm</u>
FID	<u>located in adjacent room.</u>
	<u>Wood stain, spray adhesive, caulk in main room.</u>

Location Diagram (Show Ties)

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
<u>—</u>	<u>—</u>
<u>—</u>	<u>—</u>
<u>—</u>	<u>—</u>
<u>—</u>	<u>—</u>
<u>—</u>	<u>—</u>
<u>—</u>	<u>—</u>
Total	





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID IA-A-5
 Date 8/28/06
 Time _____
 Weather Cloudy, rain showers.

Project/No. NP000597.0006.00004
 Sampling Personnel R. Gorrie, A. Faulkner
 Duplicate ID —
 Barometric Pressure 997 mb/hPa
 Corresponding Subslab ID SS-A-5

DESCRIPTION OF SAMPLE LOCATION:

Location Empty area (former T.G. Packaging)
 Facility Former BES
 Floor Type Concrete
 Cracks? _____
 Room Dimensions _____
 Tie Meas. 1 _____
 Tie Meas. 2 _____
 Tie Meas. 3 _____
 Intake Height _____

Cannister Type 6L Summa
 Cannister No. 83928
 Flow Regulator No. 14117
 Pre Sample Vacuum -30 in Hg
 Begin Sample Time 1030
 Mid Sample Time 1455
 Mid Sample Vacuum -13.5 in Hg
 End Sample Time 1830
 End Sample Vacuum -5 in Hg

FIELD PARAMETERS:

Sample Method IA SOP
 Sample Description IA sample at former TG Packaging. 3' above ground intake.
 PID 0.0 ppm
 FID _____


CONTAINER DESCRIPTION:

Container
6L Summa

Analysis
TO-15

Total

Location Diagram (Show Ties)



32'
 53'



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID	<u>IA-A-6</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>8/28/06</u>	Sampling Personnel	<u>R. Gorrie, A. Faulkner</u>
Time		Duplicate ID	<u>—</u>
Weather	<u>Cloudy, rain showers</u>	Barometric Pressure	<u>997 mb/hPa</u>
		Corresponding Subslab ID	<u>SS-A-6</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>S+W Metals Inc.</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>R-5</u>
Floor Type	<u>concrete slab</u>	Flow Regulator No.	<u>1737</u>
Cracks?		Pre Sample Vacuum	<u>-30 in Hg</u>
Room Dimensions		Begin Sample Time	<u>1040 (-27.5 in Hg)</u>
Tie Meas. 1		Mid Sample Time	<u>1505</u>
Tie Meas. 2		Mid Sample Vacuum	<u>(-15.5 in Hg)</u>
Tie Meas. 3		End Sample Time	<u>2020</u>
Intake Height	<u>3'</u>	End Sample Vacuum	<u>-5 in Hg</u>

FIELD PARAMETERS:


Sample Method	<u>I.A. S.O.P.</u>
Sample Description	<u>Indoor Air Sample @ S+W Metals / 8 hr. Intake at 3'</u>

PID	<u>0.0 ppm</u>
FID	

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
Total	

Location Diagram (Show Ties)





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>SS-A-1</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>8/30/06</u>	Sampling Personnel	<u>R. Gorrie, A. Faulkner</u>
Time		Duplicate ID	<u>SS-A-1 (dup)</u>
Weather	<u>Cloudy</u>	Barometric Pressure	<u>29.53 "Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Impress Industries</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>13671 / 1577</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>FC00890 / FC00785</u>
Cracks?	<u>no.</u>	Pre Sample Vacuum	<u>-30" Hg / -2-30" Hg</u>
Room Dimensions		Sample Depth (ft)	<u>Probe float at 7"</u>
Tie Meas. 1	<u>3'</u>	Purge Time	<u>1115-1125</u>
Tie Meas. 2	<u>17.6'</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>21.2'</u>	Purge Volume	<u>2 L</u>

FIELD PARAMETERS:


Sample Method	<u>SS SOP</u>	Begin Sample Time	<u>1125</u>
Sample Description	<u>Sub Slab Vapor</u>	End Sample Time	<u>1222</u>
PID	<u>0.0 ppm</u>	End Sample Vacuum	<u>-1.5" Hg / -1" Hg</u>
FID			

Total drilled ~ 9". Floated probe at 7"
** S-A-1 (dup) collecting more quickly than other sample and than previous samples. (ie at -7" at 20 min elapsed). No speaker leak or noise noted.*

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-14</u>
TOTAL:	

Location Diagram (Show Ties)



-- = paint line (white)



ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID SS-A-2
 Date 8/30/06
 Time 840
 Weather Cloudy

Project/No. NP000597.0006.00004
 Sampling Personnel R. Gorrie, A. Faulkner
 Duplicate ID —
 Barometric Pressure 29.53 "Hg

DESCRIPTION OF SAMPLE LOCATION:

Location Hunsinger Plastics
 Facility Former BES
 Floor Type Concrete
 Cracks? no.
 Room Dimensions
 Tie Meas. 1 3.9'
 Tie Meas. 2 13.7'
 Tie Meas. 3 21.5'

Cannister Type 6 L Summa
 Cannister No. 31133
 Flow Regulator No. FC00144
 Pre Sample Vacuum 7-30" Hg
 Sample Depth (ft) drilled - 8", floated at 6"
 Purge Time 911-924
 Purge Rate 200 mL/min
 Purge Volume 2 L
 Begin Sample Time 924
 End Sample Time 1028
 End Sample Vacuum -2" Hg


FIELD PARAMETERS:

Sample Method SS SOP
 Sample Description Sub Slab Vapor

PID 18.1 (blgd = 0.4) ppm
 FID —

CONTAINER DESCRIPTION:

Container	Analysis
6L Summa	TO-14
TOTAL:	





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>SS-A-3</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>8/30/06</u>	Sampling Personnel	<u>R. Gorrie, A. Faulkner</u>
Time	<u>1430</u>	Duplicate ID	<u>—</u>
Weather	<u>Cloudy</u>	Barometric Pressure	<u>29.5 "Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Luciano's (former ^{L+Z} Storage)</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>34421</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>FC00185</u>
Cracks?	<u>no</u>	Pre Sample Vacuum	<u>7-30 "Hg</u>
Room Dimensions		Sample Depth (ft)	<u>Drilled 4" through slab. Plect at 4"</u>
Tie Meas. 1	<u>18.5'</u>	Purge Time	<u>1514-1524</u>
Tie Meas. 2	<u>17.8'</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>17.5'</u>	Purge Volume	<u>2 L</u>
		Begin Sample Time	<u>1525</u>
		End Sample Time	<u>1635</u>
		End Sample Vacuum	<u>-2" Hg</u>


FIELD PARAMETERS:

Sample Method SS SOP
 Sample Description Sub Slab Vapor

PID 3kgd: 2.1-4.9, 2.1 at hole.
 FID

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-14</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
TOTAL:	





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>SS-A-4</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>8/29/06</u>	Sampling Personnel	<u>R. Gorrie, A. Faulkner</u>
Time	<u>915</u>	Duplicate ID	<u>—</u>
Weather	<u>Cloudy, showers</u>	Barometric Pressure	<u> </u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Oregon's Woodworking</u>	Cannister Type	<u>6L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>24496</u>
Floor Type	<u>Concrete/linoleum tile</u>	Flow Regulator No.	<u>FC00429</u>
Cracks?	<u>none.</u>	Pre Sample Vacuum	<u>> -30" Hg</u>
Room Dimensions	<u> </u>	Sample Depth (ft)	<u>6"</u>
Tie Meas. 1	<u>1.3</u>	Purge Time	<u>955-1007 (12 min)</u>
Tie Meas. 2	<u>3.75</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>19.4</u>	Purge Volume	<u>2 L</u>
		Begin Sample Time	<u>1008</u>
		End Sample Time	<u>1100</u>
		End Sample Vacuum	<u>-2" Hg</u>


FIELD PARAMETERS:

Sample Method	<u>SS SOP.</u>
Sample Description	<u>Sub Slab Vapor</u>

PID	<u>2.5</u>
FID	<u> </u>

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-14</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
TOTAL:	<u> </u>





ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID	<u>SS-A-5</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>8/29/06</u>	Sampling Personnel	<u>R. Gorrie, A. Faulkner</u>
Time	<u>1135</u>	Duplicate ID	<u>—</u>
Weather	<u>Cloudy, showers</u>	Barometric Pressure	<u>29.32" Hg</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Former STW (empty room)</u>	Cannister Type	<u>6 L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>4064</u>
Floor Type	<u>Concrete Asphalt</u>	Flow Regulator No.	<u>PC00732</u>
Cracks?	<u>—</u>	Pre Sample Vacuum	<u>-30" Hg</u>
Room Dimensions		Sample Depth (ft)	<u>4"</u>
Tie Meas. 1	<u>19'</u>	Purge Time	<u>1218-1228</u>
Tie Meas. 2	<u>21'</u>	Purge Rate	<u>200 mL/min</u>
Tie Meas. 3	<u>30.6'</u>	Purge Volume	<u>~2 L</u>
		Begin Sample Time	<u>1228</u>
		End Sample Time	<u>1326</u>
		End Sample Vacuum	<u>0" Hg</u>


FIELD PARAMETERS:

Sample Method	<u>SS SOP</u>
Sample Description	<u>Sub Slab Vapor - drilled 12", sampled at 11"</u>

PID	<u>50 ppm (max)</u>
FID	<u>—</u>

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-14</u>

TOTAL: 



ARCADIS G&M

SOIL VAPOR SAMPLE LOG

Sample ID SS-A-6
Date 8/29/06
Time 1450
Weather Cloudy showers

Project/No.	NP000597.0006.00004
Sampling Personnel	R. Gorrie, A. Faulkner
Duplicate ID	—
Barometric Pressure	29.32" Hg

DESCRIPTION OF SAMPLE LOCATION:

Location	Cutting Edge
Facility	Former BES
Floor Type	Concrete
Cracks?	none
Room Dimensions	
Tie Meas. 1	8.8
Tie Meas. 2	3.2
Tie Meas. 3	6.3

Cannister Type	6 L Summa
Cannister No.	10781
Flow Regulator No.	FC0046
Pre Sample Vacuum	- 30 "Hg
Sample Depth (ft)	8"
Purge Time	1507-1517
Purge Rate	200 mL/min
Purge Volume	2 Liters
Begin Sample Time	1517
End Sample Time	1620
End Sample Vacuum	- 7.0 "Hg (Zero)

FIELD PARAMETERS:


Sample Method SS SOP End Sample Vacuum 7.0 Hg (atmos)

Sample Description Sub Slab Vapor

Note: Flow controller zeros at -6" Hg. Drilled - 9".

PID 0.00 ppm

FID

CONTAINER DESCRIPTION:[illegible]



ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID	<u>IA-A-1-101206</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>10/12/2006</u>	Sampling Personnel	<u>C. Sharpe</u>
Time	<u>16:30</u>	Duplicate ID	<u>NA</u>
Weather	<u>overcast</u>	Barometric Pressure	
		Corresponding Subslab ID	<u>NA</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Impress Industries</u>	Cannister Type	<u>6 L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>24224</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>24224</u>
Cracks?		Pre Sample Vacuum	<u>28" Hg</u>
Room Dimensions		Begin Sample Time	<u>07:19</u>
Tie Meas. 1	<u>18'</u>	Mid Sample Time	<u>12:03</u>
Tie Meas. 2		Mid Sample Vacuum	<u>16" Hg</u>
Tie Meas. 3		End Sample Time	<u>16:30</u>
Intake Height		End Sample Vacuum	<u>9" Hg</u>


FIELD PARAMETERS:

Sample Method	<u>IA- SOP</u>
Sample Description	<u>Indoor Air Sample Collected to Verify Previous Result at IAQ-1 & IA-1</u>
PID	<u>NA</u>
FID	<u>NA</u>

CONTAINER DESCRIPTION:

Container	Analysis
<u>6L Summa</u>	<u>TO-15</u>
Total	

Location Diagram (Show Ties)





ARCADIS G&M

INDOOR AIR QUALITY SAMPLE LOG

Sample ID	<u>IA-A-3-101206</u>	Project/No.	<u>NP000597.0006.00004</u>
Date	<u>10/12/2006</u>	Sampling Personnel	<u>C. Sharpe</u>
Time	<u>16:21</u>	Duplicate ID	<u>N/A</u>
Weather	<u>P. Sunny</u>	Barometric Pressure	<u></u>
		Corresponding Subslab ID	<u>N/A</u>

DESCRIPTION OF SAMPLE LOCATION:

Location	<u>Impress Industries</u>	Cannister Type	<u>6 L Summa</u>
Facility	<u>Former BES</u>	Cannister No.	<u>14109</u>
Floor Type	<u>Concrete</u>	Flow Regulator No.	<u>14109</u>
Cracks?	<u></u>	Pre Sample Vacuum	<u>28 in Hg</u>
Room Dimensions	<u></u>	Begin Sample Time	<u>0755</u>
Tie Meas. 1	<u>47 ft</u>	Mid Sample Time	<u>12:05</u>
Tie Meas. 2	<u>10 ft</u>	Mid Sample Vacuum	<u>12 in Hg</u>
Tie Meas. 3	<u>30 ft</u>	End Sample Time	<u>1621</u>
Intake Height	<u>6 ft</u>	End Sample Vacuum	<u>7 in Hg</u>


FIELD PARAMETERS:

Sample Method	<u>IA- SOP</u>
Sample Description	<u>Indoor Air Sample Collected in E Corner of Warehouse near several wall penetrations by pipes</u>
PID	<u>NA</u>
FID	<u>NA</u>

CONTAINER DESCRIPTION:


Container	<u>6L Summa</u>	Analysis	<u>TO-15</u>
Total			

Location Diagram (Show Ties)



10/12/06 Sample)

FIRE AND EMERGENCY EVACUATION



ARCADIS

Appendix C

Laboratory Data Packages



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0602635

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally

DATE RECEIVED: 02/27/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 03/09/2006

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT</u> <u>VAC./PRES.</u>
01A	BAL-IAQ-04-022406	Modified TO-15 SIM	5.0 "Hg
02A	BAL-IAQ-05-022406	Modified TO-15 SIM	12.0 "Hg
03A	BAL-IAQ-06-022406	Modified TO-15 SIM	7.5 "Hg
03AA	BAL-IAQ-06-022406 Duplicate	Modified TO-15 SIM	7.5 "Hg
04A	BAL-IAQ-01-022406	Modified TO-15 SIM	5.0 "Hg
05A	BAL-IAQ-02-022406	Modified TO-15 SIM	6.0 "Hg
06A	BAL-IAQ-03B-DUP-022406	Modified TO-15 SIM	6.0 "Hg
07A	BAL-IAQ-03B-022406	Modified TO-15 SIM	6.0 "Hg
08A	BAL-IAQ-03A-022406	Modified TO-15 SIM	4.5 "Hg
09A	BAL-IAQ-07-022406	Modified TO-15 SIM	10.5 "Hg
09AA	BAL-IAQ-07-022406 Duplicate	Modified TO-15 SIM	10.5 "Hg
10A	BAL-IAQ-DW-022406	Modified TO-15 SIM	5.0 "Hg
11A	BAL-IAQ-VW-022406	Modified TO-15 SIM	3.5 "Hg
12A	Lab Blank	Modified TO-15 SIM	NA
13A	CCV	Modified TO-15 SIM	NA
14A	LCS	Modified TO-15 SIM	NA

CERTIFIED BY:

DATE: 03/09/06

Laboratory Director

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,

Accreditation number: E87680, Effective date: 07/01/05, Expiration date: 06/30/06

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630

(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS SIM

Client Sample ID: BAL-IAQ-04-022406

Lab ID#: 0602635-01A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	1.9	0.064	7.4
1,1,1-Trichloroethane	0.032	1.5	0.18	8.4
Trichloroethene	0.032	9.0	0.17	48

Client Sample ID: BAL-IAQ-05-022406

Lab ID#: 0602635-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.022	9.3	0.088	37
1,1,1-Trichloroethane	0.045	2.4	0.24	13
Trichloroethene	0.045	1.4	0.24	7.7

Client Sample ID: BAL-IAQ-06-022406

Lab ID#: 0602635-03A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.018	13	0.071	53
1,1,1-Trichloroethane	0.036	3.6	0.20	19
Trichloroethene	0.036	0.95	0.19	5.1

Client Sample ID: BAL-IAQ-06-022406 Duplicate

Lab ID#: 0602635-03AA

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.018	13	0.071	52
1,1,1-Trichloroethane	0.036	3.6	0.20	20
Trichloroethene	0.036	0.96	0.19	5.2

Client Sample ID: BAL-IAQ-01-022406

Lab ID#: 0602635-04A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.91	0.064	3.6
1,1,1-Trichloroethane	0.032	0.99	0.18	5.4



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS SIM

Client Sample ID: BAL-IAQ-01-022406

Lab ID#: 0602635-04A

Trichloroethene	0.032	7.4	0.17	40
-----------------	-------	-----	------	----

Client Sample ID: BAL-IAQ-02-022406

Lab ID#: 0602635-05A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.017	0.077	0.067	0.30
1,1,1-Trichloroethane	0.034	0.079	0.18	0.43
Trichloroethene	0.034	0.46	0.18	2.5

Client Sample ID: BAL-IAQ-03B-DUP-022406

Lab ID#: 0602635-06A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.017	0.018	0.067	0.070
1,1,1-Trichloroethane	0.034	0.073	0.18	0.40
Trichloroethene	0.034	0.26	0.18	1.4

Client Sample ID: BAL-IAQ-03B-022406

Lab ID#: 0602635-07A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1,1-Trichloroethane	0.034	0.070	0.18	0.38
Trichloroethene	0.034	0.26	0.18	1.4

Client Sample ID: BAL-IAQ-03A-022406

Lab ID#: 0602635-08A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.016	0.063	0.065
1,1,1-Trichloroethane	0.032	0.076	0.17	0.42
Trichloroethene	0.032	0.55	0.17	2.9

Client Sample ID: BAL-IAQ-07-022406

Lab ID#: 0602635-09A



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS SIM

Client Sample ID: BAL-IAQ-07-022406

Lab ID#: 0602635-09A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Trichloroethene	0.041	0.080	0.22	0.43

Client Sample ID: BAL-IAQ-07-022406 Duplicate

Lab ID#: 0602635-09AA

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Trichloroethene	0.041	0.083	0.22	0.45

Client Sample ID: BAL-IAQ-DW-022406

Lab ID#: 0602635-10A

No Detections Were Found.

Client Sample ID: BAL-IAQ-VW-022406

Lab ID#: 0602635-11A

No Detections Were Found.



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-04-022406

Lab ID#: 0602635-01A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030705	Date of Collection: 2/24/06
Dil. Factor:	1.61	Date of Analysis: 3/7/06 03:15 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.041	Not Detected
1,1-Dichloroethene	0.016	1.9	0.064	7.4
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.032	1.5	0.18	8.4
Trichloroethene	0.032	9.0	0.17	48

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	104	70-130
Toluene-d8	115	70-130
4-Bromofluorobenzene	90	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-05-022406

Lab ID#: 0602635-02A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030706	Date of Collection:	2/24/06
Dil. Factor:	2.23	Date of Analysis:	3/7/06 03:53 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.022	Not Detected	0.057	Not Detected
1,1-Dichloroethene	0.022	9.3	0.088	37
1,1-Dichloroethane	0.045	Not Detected	0.18	Not Detected
cis-1,2-Dichloroethene	0.045	Not Detected	0.18	Not Detected
1,1,1-Trichloroethane	0.045	2.4	0.24	13
Trichloroethene	0.045	1.4	0.24	7.7

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	103	70-130
Toluene-d8	101	70-130
4-Bromofluorobenzene	97	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-06-022406

Lab ID#: 0602635-03A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030707	Date of Collection:	2/24/06
Dil: Factor:	1.79	Date of Analysis:	3/7/06 04:33 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.018	Not Detected	0.046	Not Detected
1,1-Dichloroethene	0.018	13	0.071	53
1,1-Dichloroethane	0.036	Not Detected	0.14	Not Detected
cis-1,2-Dichloroethene	0.036	Not Detected	0.14	Not Detected
1,1,1-Trichloroethane	0.036	3.6	0.20	19
Trichloroethene	0.036	0.95	0.19	5.1

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	100	70-130
Toluene-d8	93	70-130
4-Bromofluorobenzene	90	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-06-022406 Duplicate

Lab ID#: 0602635-03AA

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030708	Date of Collection:	2/24/06
Dil. Factor:	1.79	Date of Analysis:	3/7/06 05:11 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.018	Not Detected	0.046	Not Detected
1,1-Dichloroethene	0.018	13	0.071	52
1,1-Dichloroethane	0.036	Not Detected	0.14	Not Detected
cis-1,2-Dichloroethene	0.036	Not Detected	0.14	Not Detected
1,1,1-Trichloroethane	0.036	3.6	0.20	20
Trichloroethene	0.036	0.96	0.19	5.2

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	101	70-130
Toluene-d8	92	70-130
4-Bromofluorobenzene	93	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-01-022406

Lab ID#: 0602635-04A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030709	Date of Collection: 2/24/06
Dil. Factor:	1.61	Date of Analysis: 3/7/06 05:49 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.041	Not Detected
1,1-Dichloroethene	0.016	0.91	0.064	3.6
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.032	0.99	0.18	5.4
Trichloroethene	0.032	7.4	0.17	40

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	102	70-130
Toluene-d8	92	70-130
4-Bromofluorobenzene	94	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-02-022406

Lab ID#: 0602635-05A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030710	Date of Collection:	2/24/06
Dil. Factor:	1.68	Date of Analysis:	3/7/06 06:28 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.017	Not Detected	0.043	Not Detected
1,1-Dichloroethene	0.017	0.077	0.067	0.30
1,1-Dichloroethane	0.034	Not Detected	0.14	Not Detected
cis-1,2-Dichloroethene	0.034	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.034	0.079	0.18	0.43
Trichloroethene	0.034	0.46	0.18	2.5

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	103	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	94	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-03B-DUP-022406

Lab ID#: 0602635-06A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030711	Date of Collection:	2/24/06
Dil. Factor:	1.68	Date of Analysis:	3/7/06 07:11 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.017	Not Detected	0.043	Not Detected
1,1-Dichloroethene	0.017	0.018	0.067	0.070
1,1-Dichloroethane	0.034	Not Detected	0.14	Not Detected
cis-1,2-Dichloroethene	0.034	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.034	0.073	0.18	0.40
Trichloroethene	0.034	0.26	0.18	1.4

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	102	70-130
Toluene-d8	104	70-130
4-Bromofluorobenzene	94	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-03B-022406

Lab ID#: 0602635-07A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030712	Date of Collection:	2/24/06
Dil. Factor:	1.68	Date of Analysis:	3/7/06 07:53 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.017	Not Detected	0.043	Not Detected
1,1-Dichloroethene	0.017	Not Detected	0.067	Not Detected
1,1-Dichloroethane	0.034	Not Detected	0.14	Not Detected
cis-1,2-Dichloroethene	0.034	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.034	0.070	0.18	0.38
Trichloroethene	0.034	0.26	0.18	1.4

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	99	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	92	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-03A-022406

Lab ID#: 0602635-08A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030713	Date of Collection:	2/24/06
Dil. Factor:	1.58	Date of Analysis:	3/7/06 08:39 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.040	Not Detected
1,1-Dichloroethene	0.016	0.016	0.063	0.065
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.12	Not Detected
1,1,1-Trichloroethane	0.032	0.076	0.17	0.42
Trichloroethene	0.032	0.55	0.17	2.9

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	99	70-130
Toluene-d8	105	70-130
4-Bromofluorobenzene	94	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-07-022406

Lab ID#: 0602635-09A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name: 6030714 Date of Collection: 2/24/06
Dil. Factor: 2.06 Date of Analysis: 3/7/06 09:23 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.021	Not Detected	0.053	Not Detected
1,1-Dichloroethene	0.021	Not Detected	0.082	Not Detected
1,1-Dichloroethane	0.041	Not Detected	0.17	Not Detected
cis-1,2-Dichloroethene	0.041	Not Detected	0.16	Not Detected
1,1,1-Trichloroethane	0.041	Not Detected	0.22	Not Detected
Trichloroethene	0.041	0.080	0.22	0.43

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	100	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	92	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-07-022406 Duplicate

Lab ID#: 0602635-09AA

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030718	Date of Collection:	2/24/06
Dil. Factor:	2.06	Date of Analysis:	3/8/06 07:50 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.021	Not Detected	0.053	Not Detected
1,1-Dichloroethene	0.021	Not Detected	0.082	Not Detected
1,1-Dichloroethane	0.041	Not Detected	0.17	Not Detected
cis-1,2-Dichloroethene	0.041	Not Detected	0.16	Not Detected
1,1,1-Trichloroethane	0.041	Not Detected	0.22	Not Detected
Trichloroethene	0.041	0.083	0.22	0.45

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	99	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	88	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-DW-022406

Lab ID#: 0602635-10A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030716	Date of Collection:	2/24/06
Dil. Factor:	1.61	Date of Analysis:	3/7/06 10:42 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.041	Not Detected
1,1-Dichloroethene	0.016	Not Detected	0.064	Not Detected
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.032	Not Detected	0.18	Not Detected
Trichloroethene	0.032	Not Detected	0.17	Not Detected

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	98	70-130
Toluene-d8	93	70-130
4-Bromofluorobenzene	89	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-IAQ-VW-022406

Lab ID#: 0602635-11A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030717	Date of Collection:	2/24/06
Dil. Factor:	1.52	Date of Analysis:	3/7/06 11:30 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.015	Not Detected	0.039	Not Detected
1,1-Dichloroethene	0.015	Not Detected	0.060	Not Detected
1,1-Dichloroethane	0.030	Not Detected	0.12	Not Detected
cis-1,2-Dichloroethene	0.030	Not Detected	0.12	Not Detected
1,1,1-Trichloroethane	0.030	Not Detected	0.16	Not Detected
Trichloroethene	0.030	Not Detected	0.16	Not Detected

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	99	70-130
Toluene-d8	92	70-130
4-Bromofluorobenzene	94	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0602635-12A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030704a	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	3/7/06 01:20 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.010	Not Detected	0.026	Not Detected
1,1-Dichloroethene	0.010	Not Detected	0.040	Not Detected
1,1-Dichloroethane	0.020	Not Detected	0.081	Not Detected
cis-1,2-Dichloroethene	0.020	Not Detected	0.079	Not Detected
1,1,1-Trichloroethane	0.020	Not Detected	0.11	Not Detected
Trichloroethene	0.020	Not Detected	0.11	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	104	70-130
Toluene-d8	104	70-130
4-Bromofluorobenzene	90	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0602635-13A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6030702	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/7/06 11:47 AM

Compound	%Recovery
Vinyl Chloride	110
1,1-Dichloroethene	92
1,1-Dichloroethane	96
cis-1,2-Dichloroethene	88
1,1,1-Trichloroethane	102
Trichloroethene	100

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	100	70-130
Toluene-d8	104	70-130
4-Bromofluorobenzene	94	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0602635-14A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:

6030703

Date of Collection: NA

Dil. Factor:

1.00

Date of Analysis: 3/7/06 12:26 PM

Compound	%Recovery
Vinyl Chloride	92
1,1-Dichloroethene	86
1,1-Dichloroethane	91
cis-1,2-Dichloroethene	89
1,1,1-Trichloroethane	98
Trichloroethene	93

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	103	70-130
Toluene-d8	97	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0602660A

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Bentfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally

DATE RECEIVED: 02/28/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 03/13/2006

FRACTION #

NAME

TEST

RECEIPT
VAC./PRES.

02A

BAL-SV-07-022706

Modified TO-15

3.0 "Hg

03A

BAL-SV-04B-022706

Modified TO-15

3.0 "Hg

04A

Lab Blank

Modified TO-15

NA

05A

CCV

Modified TO-15

NA

06A

LCS

Modified TO-15

NA

CERTIFIED BY:

Laboratory Director

DATE: 03/13/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,
Accreditation number: E87680, Effective date: 07/01/05, Expiration date: 06/30/06

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630

(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE

Modified TO-15

Arcadis Geraghty & Miller

Workorder# 0602660A

Two 6 Liter Summa Canister (100% Certified) samples were received on February 28, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 0.2 liters of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
Daily CCV	+/- 30% Difference.	<= 30% Difference with two allowed out up to <=40%.; flag and narrate outliers
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

b-File was quantified by a second column and detector
r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: BAL-SV-07-022706

Lab ID#: 0602660A-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	74	26000	300	100000
1,1,1-Trichloroethane	74	9300	410	51000
Trichloroethene	74	9000	400	48000

Client Sample ID: BAL-SV-04B-022706

Lab ID#: 0602660A-03A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Trichloroethene	150	39000	800	210000



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-07-022706

Lab ID#: 0602660A-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	i030921	Date of Collection:	2/27/06
Dil. Factor:	149	Date of Analysis:	3/10/06 09:14 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	74	Not Detected	190	Not Detected
1,1-Dichloroethene	74	26000	300	100000
1,1-Dichloroethane	74	Not Detected	300	Not Detected
cis-1,2-Dichloroethene	74	Not Detected	300	Not Detected
1,1,1-Trichloroethane	74	9300	410	51000
Trichloroethene	74	9000	400	48000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	93	70-130
1,2-Dichloroethane-d4	101	70-130
4-Bromofluorobenzene	94	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-04B-022706

Lab ID#: 0602660A-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	i030922	Date of Collection:	2/27/06
Dil. Factor:	298	Date of Analysis:	3/10/06 10:05 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	150	Not Detected	380	Not Detected
1,1-Dichloroethene	150	Not Detected	590	Not Detected
1,1-Dichloroethane	150	Not Detected	600	Not Detected
cis-1,2-Dichloroethene	150	Not Detected	590	Not Detected
1,1,1-Trichloroethane	150	Not Detected	810	Not Detected
Trichloroethene	150	39000	800	210000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	102	70-130
1,2-Dichloroethane-d4	99	70-130
4-Bromofluorobenzene	95	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0602660A-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	i030915	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/9/06.07:27 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.50	Not Detected	1.3	Not Detected
1,1-Dichloroethene	0.50	Not Detected	2.0	Not Detected
1,1-Dichloroethane	0.50	Not Detected	2.0	Not Detected
cis-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
1,1,1-Trichloroethane	0.50	Not Detected	2.7	Not Detected
Trichloroethene	0.50	Not Detected	2.7	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	101	70-130
1,2-Dichloroethane-d4	103	70-130
4-Bromofluorobenzene	103	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0602660A-05A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:

i030909

Date of Collection: NA

Dil. Factor:

1.00

Date of Analysis: 3/9/06 02:04 PM

Compound	%Recovery
Vinyl Chloride	72
1,1-Dichloroethene	87
1,1-Dichloroethane	87
cis-1,2-Dichloroethene	88
1,1,1-Trichloroethane	89
Trichloroethene	83

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	104	70-130
1,2-Dichloroethane-d4	100	70-130
4-Bromofluorobenzene	105	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0602660A-06A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	i030912	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/9/06 04:27 PM

Compound	%Recovery
Vinyl Chloride	74
1,1-Dichloroethene	89
1,1-Dichloroethane	89
cis-1,2-Dichloroethene	91
1,1,1-Trichloroethane	96
Trichloroethene	86

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	105	70-130
1,2-Dichloroethane-d4	103	70-130
4-Bromofluorobenzene	104	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0602660B

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally

DATE RECEIVED: 02/28/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 03/12/2006

FRACTION #

NAME

TEST

RECEIPT
VAC./PRES.

01A BAL-SV-06-022706
02A Lab Blank
03A CCV
04A LCS

Modified TO-15
Modified TO-15
Modified TO-15
Modified TO-15

1.5 "Hg
NA
NA
NA

CERTIFIED BY:

Laboratory Director

DATE: 03/13/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,
Accreditation number: E87680, Effective date: 07/01/05, Expiration date: 06/30/06

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630

(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE
Modified TO-15 Low Level
Arcadis Geraghty & Miller
Workorder# 0602660B

One 6 Liter Summa Canister (100% Certified) sample was received on February 28, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 1.0 liter of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
ICAL %RSD acceptance criteria	+/- 30% RSD with 2 compounds allowed out to < 40% RSD	30% RSD with 4 compounds allowed out to < 40% RSD
Daily Calibration	+/- 30% Difference	<= 30% Difference with four allowed out up to <=40%; flag and narrate outliers
Blank and standards	Zero air	Nitrogen
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds
MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: BAL-SV-06-022706

Lab ID#: 0602660B-01A

No Detections Were Found.



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-06-022706

Lab ID#: 0602660B-01A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7030711	Date of Collection:	2/27/06
Dil. Factor:	1.41	Date of Analysis:	3/7/06 06:27 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.14	Not Detected	0.36	Not Detected
1,1-Dichloroethene	0.14	Not Detected	0.56	Not Detected
1,1-Dichloroethane	0.14	Not Detected	0.57	Not Detected
cis-1,2-Dichloroethene	0.14	Not Detected	0.56	Not Detected
1,1,1-Trichloroethane	0.14	Not Detected	0.77	Not Detected
Trichloroethene	0.14	Not Detected	0.76	Not Detected

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	107	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0602660B-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7030705	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/7/06 01:33 PM

Compound	Rot. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.10	Not Detected	0.26	Not Detected
1,1-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1-Dichloroethane	0.10	Not Detected	0.40	Not Detected
cis-1,2-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1,1-Trichloroethane	0.10	Not Detected	0.54	Not Detected
Trichloroethene	0.10	Not Detected	0.54	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	106	70-130
Toluene-d8	98	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0602660B-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:

7030702

Date of Collection: NA

Dil. Factor:

1.00

Date of Analysis: 3/7/06 10:20 AM

Compound	%Recovery
----------	-----------

Vinyl Chloride	104
1,1-Dichloroethene	100
1,1-Dichloroethane	104
cis-1,2-Dichloroethene	103
1,1,1-Trichloroethane	103
Trichloroethene	104

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
------------	-----------	---------------

1,2-Dichloroethane-d4	104	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	104	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0602660B-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7030703	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/7/06 11:34 AM

Compound	%Recovery
Vinyl Chloride	106
1,1-Dichloroethene	100
1,1-Dichloroethane	105
cis-1,2-Dichloroethene	104
1,1,1-Trichloroethane	107
Trichloroethene	107

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	105	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	103	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0603026

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally

DATE RECEIVED: 03/01/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 03/14/2006

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT VAC./PRES.</u>
01A	BAL-SV-08-022806	Modified TO-15	2.5 "Hg
02A	BAL-SV-05-022806	Modified TO-15	4.5 "Hg
03A	BAL-SV-50-022806	Modified TO-15	3.5 "Hg
04A	BAL-SV-010-022806	Modified TO-15	4.0 "Hg
05A	BAL-SV-03B-022806	Modified TO-15	2.0 "Hg
06A	Lab Blank	Modified TO-15	NA
07A	CCV	Modified TO-15	NA
08A	LCS	Modified TO-15	NA

CERTIFIED BY:

Laboratory Director

DATE: 03/14/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,
Accreditation number: E87680, Effective date: 07/01/05, Expiration date: 06/30/06

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE
Modified TO-15
Arcadis Geraghty & Miller
Workorder# 0603026

Five 6 Liter Summa Canister (100% Certified) samples were received on March 01, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 1.0 liter of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
ICAL %RSD acceptance criteria	+/- 30% RSD with 2 compounds allowed out to < 40% RSD	30% RSD with 4 compounds allowed out to < 40% RSD
Daily Calibration	+/- 30% Difference	<= 30% Difference with four allowed out up to <=40%; flag and narrate outliers
Blank and standards	Zero air	Nitrogen
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: BAL-SV-08-022806

Lab ID#: 0603026-01A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Trichloroethene	0.15	1.7	0.78	9.1

Client Sample ID: BAL-SV-05-022806

Lab ID#: 0603026-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	1.6	140	6.3	580
1,1,1-Trichloroethane	1.6	4.0	8.6	22
Trichloroethene	1.6	490	8.5	2600

Client Sample ID: BAL-SV-50-022806

Lab ID#: 0603026-03A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	1.5	150	6.0	590
1,1,1-Trichloroethane	1.5	4.2	8.3	23
Trichloroethene	1.5	490	8.2	2600

Client Sample ID: BAL-SV-010-022806

Lab ID#: 0603026-04A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethane	1.0	2.2	4.2	9.0
cis-1,2-Dichloroethene	1.0	190	4.1	740
1,1,1-Trichloroethane	1.0	68	5.6	370
Trichloroethene	1.0	92	5.5	490

Client Sample ID: BAL-SV-03B-022806

Lab ID#: 0603026-05A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Trichloroethene	2.4	790	13	4200



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-08-022806

Lab ID#: 0603026-01A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031205	Date of Collection:	2/28/06
Dil. Factor:	1.46	Date of Analysis:	3/13/06 02:05 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.15	Not Detected	0.37	Not Detected
1,1-Dichloroethene	0.15	Not Detected	0.58	Not Detected
1,1-Dichloroethane	0.15	Not Detected	0.59	Not Detected
cis-1,2-Dichloroethene	0.15	Not Detected	0.58	Not Detected
1,1,1-Trichloroethane	0.15	Not Detected	0.80	Not Detected
Trichloroethene	0.15	1.7	0.78	9.1

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	114	70-130
Toluene-d8	98	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-05-022806

Lab ID#: 0603026-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031207	Date of Collection:	2/28/06
Dil. Factor:	15.8	Date of Analysis:	3/13/06 03:43 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	1.6	Not Detected	4.0	Not Detected
1,1-Dichloroethene	1.6	140	6.3	580
1,1-Dichloroethane	1.6	Not Detected	6.4	Not Detected
cis-1,2-Dichloroethene	1.6	Not Detected	6.3	Not Detected
1,1,1-Trichloroethane	1.6	4.0	8.6	22
Trichloroethene	1.6	490	8.5	2600

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	114	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	102	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-50-022806

Lab ID#: 0603026-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031208	Date of Collection:	2/28/06
Dil. Factor:	15.2	Date of Analysis:	3/13/06 04:26 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	1.5	Not Detected	3.9	Not Detected
1,1-Dichloroethene	1.5	150	6.0	590
1,1-Dichloroethane	1.5	Not Detected	6.2	Not Detected
cis-1,2-Dichloroethene	1.5	Not Detected	6.0	Not Detected
1,1,1-Trichloroethane	1.5	4.2	8.3	23
Trichloroethene	1.5	490	8.2	2600

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	117	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	104	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-010-022806

Lab ID#: 0603026-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031209	Date of Collection:	2/28/06
Dil. Factor:	10.3	Date of Analysis:	3/13/06 05:10 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	1.0	Not Detected	2.6	Not Detected
1,1-Dichloroethene	1.0	Not Detected	4.1	Not Detected
1,1-Dichloroethane	1.0	2.2	4.2	9.0
cis-1,2-Dichloroethene	1.0	190	4.1	740
1,1,1-Trichloroethane	1.0	68	5.6	370
Trichloroethene	1.0	92	5.5	490

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	115	70-130
Toluene-d8	98	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-03B-022806

Lab ID#: 0603026-05A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:

7031210

Date of Collection: 2/28/06

Dil. Factor:

24.0

Date of Analysis: 3/13/06 06:04 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	2.4	Not Detected	6.1	Not Detected
1,1-Dichloroethene	2.4	Not Detected	9.5	Not Detected
1,1-Dichloroethane	2.4	Not Detected	9.7	Not Detected
cis-1,2-Dichloroethene	2.4	Not Detected	9.5	Not Detected
1,1,1-Trichloroethane	2.4	Not Detected	13	Not Detected
Trichloroethene	2.4	790	13	4200

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	120	70-130
Toluene-d8	99	70-130
4-Bromofluorobenzene	100	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0603026-06A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031204a	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/13/06 01:10 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.10	Not Detected	0.26	Not Detected
1,1-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1-Dichloroethane	0.10	Not Detected	0.40	Not Detected
cis-1,2-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1,1-Trichloroethane	0.10	Not Detected	0.54	Not Detected
Trichloroethene	0.10	Not Detected	0.54	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	112	70-130
Toluene-d8	97	70-130
4-Bromofluorobenzene	102	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0603026-07A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031202	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/12/06 11:23 PM

Compound	%Recovery
Vinyl Chloride	106
1,1-Dichloroethene	105
1,1-Dichloroethane	108
cis-1,2-Dichloroethene	106
1,1,1-Trichloroethane	118
Trichloroethene	106

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	115	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	103	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0603026-08A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031203	Date of Collection: NA
Dil. Factor:	1:00	Date of Analysis: 3/13/06 12:03 AM

Compound	%Recovery
Vinyl Chloride	104
1,1-Dichloroethene	103
1,1-Dichloroethane	108
cis-1,2-Dichloroethene	104
1,1,1-Trichloroethane	119
Trichloroethene	109

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	113	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0603058A

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally

DATE RECEIVED: 03/02/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 03/15/2006

FRACTION #

NAME

TEST

RECEIPT
VAC./PRES.

02A	BAL-SV-09-030106
03A	Lab Blank
04A	CCV
05A	LCS

Modified TO-15
Modified TO-15
Modified TO-15
Modified TO-15

1.0 "Hg
NA
NA
NA

CERTIFIED BY:

Laboratory Director

DATE: 03/15/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,

Accreditation number: E87680, Effective date: 07/01/05, Expiration date: 06/30/06

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE

Modified TO-15

Arcadis Geraghty & Miller

Workorder# 0603058A

One 6 Liter Summa Canister (100% Certified) sample was received on March 02, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 1.0 liter of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
ICAL %RSD acceptance criteria	+/- 30% RSD with 2 compounds allowed out to < 40% RSD	30% RSD with 4 compounds allowed out to < 40% RSD
Daily Calibration	+/- 30% Difference	<= 30% Difference with four allowed out up to <=40%; flag and narrate outliers
Blank and standards	Zero air	Nitrogen
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: BAL-SV-09-030106

Lab ID#: 0603058A-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1,1-Trichloroethane	0.14	0.14	0.76	0.78
Trichloroethene	0.14	2.1	0.75	11



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-09-030106

Lab ID#: 0603058A-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031211	Date of Collection: 3/1/06
Dil. Factor:	1.39	Date of Analysis: 3/13/06 07:11 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.14	Not Detected	0.36	Not Detected
1,1-Dichloroethene	0.14	Not Detected	0.55	Not Detected
1,1-Dichloroethane	0.14	Not Detected	0.56	Not Detected
cis-1,2-Dichloroethene	0.14	Not Detected	0.55	Not Detected
1,1,1-Trichloroethane	0.14	0.14	0.76	0.78
Trichloroethene	0.14	2.1	0.75	11

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	119	70-130
Toluene-d8	99	70-130
4-Bromofluorobenzene	104	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0603058A-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031204	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/13/06 01:10 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.10	Not Detected	0.26	Not Detected
1,1-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1-Dichloroethane	0.10	Not Detected	0.40	Not Detected
cis-1,2-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1,1-Trichloroethane	0.10	Not Detected	0.54	Not Detected
Trichloroethene	0.10	Not Detected	0.54	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	112	70-130
Toluene-d8	97	70-130
4-Bromofluorobenzene	102	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0603058A-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7031202	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/12/06 11:23 PM

Compound	%Recovery
Vinyl Chloride	106
1,1-Dichloroethene	105
1,1-Dichloroethane	108
cis-1,2-Dichloroethene	106
1,1,1-Trichloroethane	118
Trichloroethene	106

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	115	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	103	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0603058A-05A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name: 7031203
Dil. Factor: 1.00

Date of Collection: NA
Date of Analysis: 3/13/06 12:03 AM

Compound	%Recovery
Vinyl Chloride	104
1,1-Dichloroethene	103
1,1-Dichloroethane	108
cis-1,2-Dichloroethene	104
1,1,1-Trichloroethane	119
Trichloroethene	109

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	113	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0603058B

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally

DATE RECEIVED: 03/02/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 03/15/2006

FRACTION #

NAME

TEST

RECEIPT
VAC./PRES.

01A	BAL-SV-11-030106
02A	Lab Blank
03A	CCV
04A	LCS

Modified TO-15	2.5 "Hg
Modified TO-15	NA
Modified TO-15	NA
Modified TO-15	NA

CERTIFIED BY:

Laboratory Director

DATE: 03/15/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,

Accreditation number: E87680, Effective date: 07/01/05, Expiration date: 06/30/06

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE

Modified TO-15

Arcadis Geraghty & Miller

Workorder# 0603058B

One 6 Liter Summa Canister (100% Certified) sample was received on March 02, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 0.2 liters of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

Requirement	TO-15	ATL Modifications
Daily CCV	+/- 30% Difference	<= 30% Difference with two allowed out up to <=40%; flag and narrate outliers
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: BAL-SV-11-030106

Lab ID#: 0603058B-01A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	73	9500	290	38000
1,1,1-Trichloroethane	73	5000	400	27000
Trichloroethene	73	20000	390	110000



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: BAL-SV-11-030106

Lab ID#: 0603058B-01A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	1031426	Date of Collection:	3/1/06
Dil. Factor:	146	Date of Analysis:	3/15/06 12:07 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	73	Not Detected	190	Not Detected
1,1-Dichloroethene	73	9500	290	38000
1,1-Dichloroethane	73	Not Detected	300	Not Detected
cis-1,2-Dichloroethene	73	Not Detected	290	Not Detected
1,1,1-Trichloroethane	73	5000	400	27000
Trichloroethene	73	20000	390	110000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	98	70-130
1,2-Dichloroethane-d4	110	70-130
4-Bromofluorobenzene	109	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0603058B-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	i031409	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/14/06 05:28 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.50	Not Detected	1.3	Not Detected
1,1-Dichloroethene	0.50	Not Detected	2.0	Not Detected
1,1-Dichloroethane	0.50	Not Detected	2.0	Not Detected
cis-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
1,1,1-Trichloroethane	0.50	Not Detected	2.7	Not Detected
Trichloroethene	0.50	Not Detected	2.7	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	99	70-130
1,2-Dichloroethane-d4	99	70-130
4-Bromofluorobenzene	106	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0603058B-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:

1031406

Date of Collection: NA

Dil. Factor:

1.00

Date of Analysis: 3/14/06 02:58 PM

Compound	%Recovery
----------	-----------

Vinyl Chloride	73
1,1-Dichloroethene	86
1,1-Dichloroethane	86
cis-1,2-Dichloroethene	87
1,1,1-Trichloroethane	88
Trichloroethene	81

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	101	70-130
1,2-Dichloroethane-d4	100	70-130
4-Bromofluorobenzene	107	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0603058B-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	I031407	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 3/14/06 03:44 PM

Compound	%Recovery
Vinyl Chloride	81
1,1-Dichloroethene	101
1,1-Dichloroethane	101
cis-1,2-Dichloroethene	102
1,1,1-Trichloroethane	102
Trichloroethene	99

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	103	70-130
1,2-Dichloroethane-d4	100	70-130
4-Bromofluorobenzene	106	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0610306

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. # NP000597.0006

FAX: 410-987-4392

PROJECT # NP000597.0006.00004 AH Bally

DATE RECEIVED: 10/16/2006

CONTACT: Kelly Buettner

DATE COMPLETED:

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT VAC./PRES.</u>
01A	IA-A-1-101206	Modified TO-15	5.0 "Hg
02A	IA-A-3-101206	Modified TO-15	2.5 "Hg
03A	Lab Blank	Modified TO-15	NA
04A	CCV	Modified TO-15	NA
05A	LCS	Modified TO-15	NA

CERTIFIED BY:

Laboratory Director

DATE: 10/24/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,

Accreditation number: E87680, Effective date: 07/01/06, Expiration date: 06/30/07

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020

LABORATORY NARRATIVE**Modified TO-15****Arcadis Geraghty & Miller****Workorder# 0610306**

Two 6 Liter Summa Canister (100% Certified) samples were received on October 16, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 1.0 liter of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
ICAL %RSD acceptance criteria	+/- 30% RSD with 2 compounds allowed out to < 40% RSD	30% RSD with 4 compounds allowed out to < 40% RSD
Daily Calibration	+/- 30% Difference	<= 30% Difference with four allowed out up to <=40%; flag and narrate outliers
Blank and standards	Zero air	Nitrogen
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request

Receiving Notes

The Chain of Custody (COC) information for sample IA-A-1-101206 and IA-A-3-101206 did not match the information on the canisters with regard to canister identification. The client was notified of the discrepancy and the information on the canisters was used to process and report the samples.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds
MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: IA-A-1-101206

Lab ID#: 0610306-01A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.16	11	0.64	43
1,1,1-Trichloroethane	0.16	8.2	0.88	44
Trichloroethene	0.16	53	0.86	280

Client Sample ID: IA-A-3-101206

Lab ID#: 0610306-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.29	38	1.2	150
1,1,1-Trichloroethane	0.29	31	1.6	170
Trichloroethene	0.29	91	1.6	490



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-1-101206

Lab ID#: 0610306-01A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	a102306	Date of Collection:	10/12/06
Dil. Factor:	1.61	Date of Analysis:	10/23/06 06:35 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.16	Not Detected	0.41	Not Detected
1,1-Dichloroethene	0.16	11	0.64	43
1,1-Dichloroethane	0.16	Not Detected	0.65	Not Detected
cis-1,2-Dichloroethene	0.16	Not Detected	0.64	Not Detected
1,1,1-Trichloroethane	0.16	8.2	0.88	44
Trichloroethene	0.16	53	0.86	280

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	94	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	110	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-3-101206

Lab ID#: 0610306-02A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	a102309	Date of Collection:	10/12/06
Dil. Factor:	2.92	Date of Analysis:	10/23/06 08:34 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.29	Not Detected	0.75	Not Detected
1,1-Dichloroethene	0.29	38	1.2	150
1,1-Dichloroethane	0.29	Not Detected	1.2	Not Detected
cis-1,2-Dichloroethene	0.29	Not Detected	1.2	Not Detected
1,1,1-Trichloroethane	0.29	31	1.6	170
Trichloroethene	0.29	91	1.6	490

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	93	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	110	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0610306-03A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	a102305	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 10/23/06 05:41 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.10	Not Detected	0.26	Not Detected
1,1-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1-Dichloroethane	0.10	Not Detected	0.40	Not Detected
cis-1,2-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1,1-Trichloroethane	0.10	Not Detected	0.54	Not Detected
Trichloroethene	0.10	Not Detected	0.54	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	92	70-130
Toluene-d8	99	70-130
4-Bromofluorobenzene	100	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0610306-04A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	a102302	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 10/23/06 02:55 PM

Compound	%Recovery
Vinyl Chloride	108
1,1-Dichloroethene	105
1,1-Dichloroethane	100
cis-1,2-Dichloroethene	104
1,1,1-Trichloroethane	97
Trichloroethene	108

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	95	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	102	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0610306-05A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	a102304	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 10/23/06 04:49 PM

Compound	%Recovery
Vinyl Chloride	96
1,1-Dichloroethene	91
1,1-Dichloroethane	97
cis-1,2-Dichloroethene	101
1,1,1-Trichloroethane	89
Trichloroethene	104

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	87	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	110	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0609029A

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally Bally

DATE RECEIVED: 09/01/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 08/21/2006

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT VAC./PRES.</u>
01A	AA-West	Modified TO-15 SIM	5.0 "Hg
02A	AA-East	Modified TO-15 SIM	5.5 "Hg
03A	IA-A-1	Modified TO-15 SIM	4.0 "Hg
04A	IA-A-2	Modified TO-15 SIM	4.5 "Hg
05A	IA-A-4	Modified TO-15 SIM	4.5 "Hg
06A	IA-A-6	Modified TO-15 SIM	5.0 "Hg
07A	IA-A-5	Modified TO-15 SIM	3.0 "Hg
07AA	IA-A-5 Duplicate	Modified TO-15 SIM	3.0 "Hg
14A(cancelled)	IA-A-1 (dup)	Modified TO-15 SIM	0.0 "Hg
15A	Lab Blank	Modified TO-15 SIM	NA
16A	CCV	Modified TO-15 SIM	NA
17A	LCS	Modified TO-15 SIM	NA

CERTIFIED BY:

Laboratory Director

DATE: 09/15/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004

NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,

Accreditation number: E87680, Effective date: 07/01/06, Expiration date: 06/30/07

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630

(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE
Modified TO-15 SIM
Arcadis Geraghty & Miller
Workorder# 0609029A

Eight 6 Liter Summa Canister (SIM Certified) samples were received on September 01, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the SIM acquisition mode. The method involves concentrating up to 0.5 liters of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
ICAL %RSD acceptance criteria	$\leq 30\%$ RSD with 2 compounds allowed out to $< 40\%$ RSD	Project specific; default criteria is $\leq 30\%$ RSD with 10% of compounds allowed out to $< 40\%$ RSD
Daily Calibration	$\pm 30\%$ Difference	Project specific; default criteria is $\leq 30\%$ Difference with 10% of compounds allowed out up to $\leq 40\%$; flag and narrate outliers
Blank and standards	Zero air	Nitrogen
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases

Receiving Notes

Sample IA-A-1 (dup) arrived at ambient pressure yet a flow controller was used for sample collection. The client was notified and the analysis was cancelled.

Analytical Notes

There were no analytical discrepancies.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS SIM

Client Sample ID: AA-West

Lab ID#: 0609029A-01A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.019	0.064	0.075
1,1,1-Trichloroethane	0.032	0.050	0.18	0.27
Trichloroethene	0.032	0.036	0.17	0.19

Client Sample ID: AA-East

Lab ID#: 0609029A-02A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.029	0.065	0.12
1,1,1-Trichloroethane	0.033	0.061	0.18	0.33
Trichloroethene	0.033	0.051	0.18	0.27

Client Sample ID: IA-A-1

Lab ID#: 0609029A-03A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.022	16	0.088	62
cis-1,2-Dichloroethene	0.044	0.045	0.18	0.18
1,1,1-Trichloroethane	0.044	19	0.24	100
Trichloroethene	0.044	33	0.24	180

Client Sample ID: IA-A-2

Lab ID#: 0609029A-04A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.32	0.063	1.3
1,1,1-Trichloroethane	0.032	0.28	0.17	1.6
Trichloroethene	0.032	0.71	0.17	3.8

Client Sample ID: IA-A-4

Lab ID#: 0609029A-05A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.018	0.063	0.070



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS SIM

Client Sample ID: IA-A-4

Lab ID#: 0609029A-05A

1,1,1-Trichloroethane	0.032	0.056	0.17	0.30
Trichloroethene	0.032	0.066	0.17	0.35

Client Sample ID: IA-A-6

Lab ID#: 0609029A-06A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.016	0.83	0.064	3.3
1,1,1-Trichloroethane	0.032	0.42	0.18	2.3
Trichloroethene	0.032	0.19	0.17	1.0

Client Sample ID: IA-A-5

Lab ID#: 0609029A-07A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.015	4.9	0.059	19
1,1,1-Trichloroethane	0.030	1.8	0.16	9.6
Trichloroethene	0.030	1.4	0.16	7.4

Client Sample ID: IA-A-5 Duplicate

Lab ID#: 0609029A-07AA

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.015	5.8	0.059	23
1,1,1-Trichloroethane	0.030	1.8	0.16	9.6
Trichloroethene	0.030	1.4	0.16	7.4



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: AA-West

Lab ID#: 0609029A-01A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090714	Date of Collection:	8/28/06
Dil. Factor:	1.61	Date of Analysis:	9/7/06 09:53 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.041	Not Detected
1,1-Dichloroethene	0.016	0.019	0.064	0.075
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.032	0.050	0.18	0.27
Trichloroethene	0.032	0.036	0.17	0.19

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	128	70-130
Toluene-d8	105	70-130
4-Bromofluorobenzene	114	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: AA-East

Lab ID#: 0609029A-02A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090715	Date of Collection:	8/28/06
Dil. Factor:	1.64	Date of Analysis:	9/7/06 10:43 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.042	Not Detected
1,1-Dichloroethene	0.016	0.029	0.065	0.12
1,1-Dichloroethane	0.033	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.033	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.033	0.061	0.18	0.33
Trichloroethene	0.033	0.051	0.18	0.27

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	126	70-130
Toluene-d8	104	70-130
4-Bromofluorobenzene	115	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-1

Lab ID#: 0609029A-03A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090718	Date of Collection:	8/28/06
Dil. Factor:	2.21	Date of Analysis:	9/8/06 01:51 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.022	Not Detected	0.056	Not Detected
1,1-Dichloroethene	0.022	16	0.088	62
1,1-Dichloroethane	0.044	Not Detected	0.18	Not Detected
cis-1,2-Dichloroethene	0.044	0.045	0.18	0.18
1,1,1-Trichloroethane	0.044	19	0.24	100
Trichloroethene	0.044	33	0.24	180

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	119	70-130
Toluene-d8	104	70-130
4-Bromofluorobenzene	113	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-2

Lab ID#: 0609029A-04A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090719	Date of Collection:	8/28/06
Dil. Factor:	1.58	Date of Analysis:	9/8/06 02:39 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.040	Not Detected
1,1-Dichloroethene	0.016	0.32	0.063	1.3
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.12	Not Detected
1,1,1-Trichloroethane	0.032	0.28	0.17	1.6
Trichloroethene	0.032	0.71	0.17	3.8

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	122	70-130
Toluene-d8	99	70-130
4-Bromofluorobenzene	108	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-4

Lab ID#: 0609029A-05A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090720	Date of Collection:	8/28/06
Dil. Factor:	1.58	Date of Analysis:	9/8/06 03:32 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.040	Not Detected
1,1-Dichloroethene	0.016	0.018	0.063	0.070
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.12	Not Detected
1,1,1-Trichloroethane	0.032	0.056	0.17	0.30
Trichloroethene	0.032	0.066	0.17	0.35

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	124	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	108	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: 1A-A-6

Lab ID#: 0609029A-06A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090721	Date of Collection:	8/28/06
Dil. Factor:	1.61	Date of Analysis:	9/8/06 04:15 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.016	Not Detected	0.041	Not Detected
1,1-Dichloroethene	0.016	0.83	0.064	3.3
1,1-Dichloroethane	0.032	Not Detected	0.13	Not Detected
cis-1,2-Dichloroethene	0.032	Not Detected	0.13	Not Detected
1,1,1-Trichloroethane	0.032	0.42	0.18	2.3
Trichloroethene	0.032	0.19	0.17	1.0

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	119	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	104	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-5

Lab ID#: 0609029A-07A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090722	Date of Collection:	8/28/06
Dil. Factor:	1.49	Date of Analysis:	9/8/06 05:10 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.015	Not Detected	0.038	Not Detected
1,1-Dichloroethene	0.015	4.9	0.059	19
1,1-Dichloroethane	0.030	Not Detected	0.12	Not Detected
cis-1,2-Dichloroethene	0.030	Not Detected	0.12	Not Detected
1,1,1-Trichloroethane	0.030	1.8	0.16	9.6
Trichloroethene	0.030	1.4	0.16	7.4

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	122	70-130
Toluene-d8	99	70-130
4-Bromofluorobenzene	106	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: IA-A-5 Duplicate

Lab ID#: 0609029A-07AA

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090723	Date of Collection:	8/28/06
Dil. Factor:	1.49	Date of Analysis:	9/8/06 05:55 AM

Compound	Rot. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.015	Not Detected	0.038	Not Detected
1,1-Dichloroethene	0.015	5.8	0.059	23
1,1-Dichloroethane	0.030	Not Detected	0.12	Not Detected
cis-1,2-Dichloroethene	0.030	Not Detected	0.12	Not Detected
1,1,1-Trichloroethane	0.030	1.8	0.16	9.6
Trichloroethene	0.030	1.4	0.16	7.4

Container Type: 6 Liter Summa Canister (SIM Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	126	70-130
Toluene-d8	98	70-130
4-Bromofluorobenzene	112	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0609029A-15A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090704	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/7/06 11:25 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.010	Not Detected	0.026	Not Detected
1,1-Dichloroethene	0.010	Not Detected	0.040	Not Detected
1,1-Dichloroethane	0.020	Not Detected	0.081	Not Detected
cis-1,2-Dichloroethene	0.020	Not Detected	0.079	Not Detected
1,1,1-Trichloroethane	0.020	Not Detected	0.11	Not Detected
Trichloroethene	0.020	Not Detected	0.11	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	121	70-130
Toluene-d8	101	70-130
4-Bromofluorobenzene	105	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0609029A-16A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090702	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/7/06 09:34 AM

Compound	%Recovery
Vinyl Chloride	85
1,1-Dichloroethene	91
1,1-Dichloroethane	96
cis-1,2-Dichloroethene	90
1,1,1-Trichloroethane	105
Trichloroethene	84

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	115	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	101	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0609029A-17A

MODIFIED EPA METHOD TO-15 GC/MS SIM

File Name:	6090703	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/7/06 10:12 AM

Compound	%Recovery
Vinyl Chloride	78
1,1-Dichloroethene	89
1,1-Dichloroethane	101
cis-1,2-Dichloroethene	88
1,1,1-Trichloroethane	109
Trichloroethene	86

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	117	70-130
Toluene-d8	104	70-130
4-Bromofluorobenzene	98	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

CHAIN-OF-CUSTODY RECORD

Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, state, federal, national, laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. P.O. Box 1800, 487-4922.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

Page 1 of 2

Contact Person Christopher Sharpe

Company ARCADIS

Email csharpe@arcadis-us.com

Address 10 Terry D. Sullivan Dr. Suite 300 City Newton State PA Zip 15745
Phone 807-685-1800 Fax 807-685-1801

Collected by: (signature) Michael Houlihan

Project Info:

P.O. # _____

Project # NP597.6 At Bally

Project Name Bally

Turn Around Time:

☐ Normal

☐ Rush

Pressurized by: LB

Date: 9/21/06

Pressurization Gas: _____

specify _____

He: _____

Lab ID	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum
01A	AA - West	33945	8/28/06	2125	Modified TD-15	Initial Final Receipt Final
02A	AA - East	22500	8/28/06	2010	Modified TD-15	Initial Final Receipt Final
03A	IA-A-1	13500	8/28/06	2100		Initial Final Receipt Final
04A	IA-A-2	30493	8/28/06	2210		Initial Final Receipt Final
05A	IA-A-4	33987	8/28/06	2000		Initial Final Receipt Final
06A	IA-A-6	15	8/28/06	2000		Initial Final Receipt Final
07A	IA-A-5	33938	8/28/06	1830		Initial Final Receipt Final
08A	SS-A-1	13671	8/30/06	1222		Initial Final Receipt Final
09A	SS-A-2	31133	8/30/06	1028		Initial Final Receipt Final
10A	SS-A-3	3421	8/30/06	1635		Initial Final Receipt Final
Relinquished by: (signature) <u>Michael Houlihan</u> Date/Time <u>9/30/06 1030</u>		Received by: (signature) _____ Date/Time _____		Notes: <u>✓</u>		
Relinquished by: (signature) _____ Date/Time _____		Received by: (signature) _____ Date/Time _____				
Relinquished by: (signature) _____ Date/Time _____		Received by: (signature) _____ Date/Time _____				
Lab	Shipper Name	Air Bill #	Temp (°C)	Condition	Customer Seals Intact?	Work Order #
Use Only	<u>TD-15</u>	<u>792196158133</u>	<u>11A</u>	<u>Good</u>	<u>Yes</u> <input checked="" type="checkbox"/> <u>No</u> <input type="checkbox"/> <u>None</u> <input type="checkbox"/>	<u>0609029A</u>



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0609029B

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally Bally

DATE RECEIVED: 09/01/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 09/15/2006

FRACTION

NAME

TEST

RECEIPT VAC./PRES.

09A

SS-A-2

Modified TO-15

0.5 "Hg

10A

SS-A-3

Modified TO-15

0.5 "Hg

10AA

SS-A-3 Duplicate

Modified TO-15

0.5 "Hg

11A

SS-A-4

Modified TO-15

1.5 "Hg

13A

SS-A-6

Modified TO-15

1.0 "Hg

14A

Lab Blank

Modified TO-15

NA

15A

CCV

Modified TO-15

NA

16A

LCS

Modified TO-15

NA

CERTIFIED BY:

DATE: 09/15/06

Laboratory Director

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,
Accreditation number: E87680, Effective date: 07/01/06, Expiration date: 06/30/07

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630

(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020

**LABORATORY NARRATIVE****Modified TO-15****Arcadis Geraghty & Miller****Workorder# 0609029B**

Four 6 Liter Summa Canister (100% Certified) samples were received on September 01, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 1.0 liter of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

Requirement	TO-15	ATL Modifications
ICAL %RSD acceptance criteria	+/- 30% RSD with 2 compounds allowed out to < 40% RSD	30% RSD with 4 compounds allowed out to < 40% RSD
Daily Calibration	+/- 30% Difference	<= 30% Difference with four allowed out up to <=40%; flag and narrate outliers
Blank and standards	Zero air	Nitrogen
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

The recovery of surrogate 1,2-Dichloroethane-d4 in samples SS-A-2 and SS-A-6 was outside control limits due to high level hydrocarbon matrix interference. Data is reported as qualified.

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: SS-A-2

Lab ID#: 0609029B-09A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.27	1.5	1.1	6.0
1,1-Dichloroethane	0.27	0.62	1.1	2.5
cis-1,2-Dichloroethene	0.27	51	1.1	200
1,1,1-Trichloroethane	0.27	19	1.5	100
Trichloroethene	0.27	66	1.5	350

Client Sample ID: SS-A-3

Lab ID#: 0609029B-10A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	2.7	61	11	240
1,1,1-Trichloroethane	2.7	3.9	15	21
Trichloroethene	2.7	560	15	3000

Client Sample ID: SS-A-3 Duplicate

Lab ID#: 0609029B-10AA

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	2.7	60	11	240
1,1,1-Trichloroethane	2.7	3.8	15	21
Trichloroethene	2.7	570	15	3100

Client Sample ID: SS-A-4

Lab ID#: 0609029B-11A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Trichloroethene	0.14	0.85	0.76	4.6

Client Sample ID: SS-A-6

Lab ID#: 0609029B-13A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	0.14	0.21	0.55	0.84
1,1,1-Trichloroethane	0.14	0.94	0.76	5.1



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds
MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: SS-A-6

Lab ID#: 0609029B-13A

Trichloroethene	0.14	0.70	0.75	3.8
-----------------	------	------	------	-----



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-2

Lab ID#: 0609029B-09A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090518	Date of Collection:	8/30/06
Dil. Factor:	2.72	Date of Analysis:	9/6/06 12:51 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.27	Not Detected	0.70	Not Detected
1,1-Dichloroethene	0.27	1.5	1.1	6.0
1,1-Dichloroethane	0.27	0.62	1.1	2.5
cis-1,2-Dichloroethene	0.27	51	1.1	200
1,1,1-Trichloroethane	0.27	19	1.5	100
Trichloroethene	0.27	66	1.5	350

Q = Exceeds Quality Control limits of 70% to 130%, due to matrix effects.

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	154 Q	70-130
Toluene-d8	103	70-130
4-Bromofluorobenzene	108	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-3

Lab ID#: 0609029B-10A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090519	Date of Collection:	8/30/06
Dil. Factor:	27.2	Date of Analysis:	9/6/06 01:40 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	2.7	Not Detected	7.0	Not Detected
1,1-Dichloroethene	2.7	61	11	240
1,1-Dichloroethane	2.7	Not Detected	11	Not Detected
cis-1,2-Dichloroethene	2.7	Not Detected	11	Not Detected
1,1,1-Trichloroethane	2.7	3.9	15	21
Trichloroethene	2.7	560	15	3000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	112	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	100	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-3 Duplicate

Lab ID#: 0609029B-10AA

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090520	Date of Collection:	8/30/06
Dil. Factor:	27.2	Date of Analysis:	9/6/06 02:24 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	2.7	Not Detected	7.0	Not Detected
1,1-Dichloroethene	2.7	60	11	240
1,1-Dichloroethane	2.7	Not Detected	11	Not Detected
cis-1,2-Dichloroethene	2.7	Not Detected	11	Not Detected
1,1,1-Trichloroethane	2.7	3.8	15	21
Trichloroethene	2.7	570	15	3100

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	110	70-130
Toluene-d8	99	70-130
4-Bromofluorobenzene	102	70-130

AR100949



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-4

Lab ID#: 0609029B-11A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090521	Date of Collection:	8/29/06
Dil. Factor:	1.41	Date of Analysis:	9/6/06 03:08 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.14	Not Detected	0.36	Not Detected
1,1-Dichloroethene	0.14	Not Detected	0.56	Not Detected
1,1-Dichloroethane	0.14	Not Detected	0.57	Not Detected
cis-1,2-Dichloroethene	0.14	Not Detected	0.56	Not Detected
1,1,1-Trichloroethane	0.14	Not Detected	0.77	Not Detected
Trichloroethene	0.14	0.85	0.76	4.6

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	125	70-130
Toluene-d8	100	70-130
4-Bromofluorobenzene	103	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-6

Lab ID#: 0609029B-13A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090522	Date of Collection:	8/29/06
Dil. Factor:	1.39	Date of Analysis:	9/6/06 03:47 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.14	Not Detected	0.36	Not Detected
1,1-Dichloroethene	0.14	0.21	0.55	0.84
1,1-Dichloroethane	0.14	Not Detected	0.56	Not Detected
cis-1,2-Dichloroethene	0.14	Not Detected	0.55	Not Detected
1,1,1-Trichloroethane	0.14	0.94	0.76	5.1
Trichloroethene	0.14	0.70	0.75	3.8

Q = Exceeds Quality Control limits of 70% to 130%, due to matrix effects.

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	171 Q	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	94	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0609029B-14A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090510	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/5/06 05:26 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.10	Not Detected	0.26	Not Detected
1,1-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1-Dichloroethane	0.10	Not Detected	0.40	Not Detected
cis-1,2-Dichloroethene	0.10	Not Detected	0.40	Not Detected
1,1,1-Trichloroethane	0.10	Not Detected	0.54	Not Detected
Trichloroethene	0.10	Not Detected	0.54	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	107	70-130
Toluene-d8	95	70-130
4-Bromofluorobenzene	105	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: CCV

Lab ID#: 0609029B-15A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090504	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/5/06 10:20 AM

Compound	%Recovery
Vinyl Chloride	112
1,1-Dichloroethene	109
1,1-Dichloroethane	111
cis-1,2-Dichloroethene	113
1,1,1-Trichloroethane	116
Trichloroethene	104

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	106	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	93	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0609029B-16A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	7090503	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/5/06 09:40 AM

Compound	%Recovery
Vinyl Chloride	111
1,1-Dichloroethene	107
1,1-Dichloroethane	110
cis-1,2-Dichloroethene	104
1,1,1-Trichloroethane	110
Trichloroethene	110

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
1,2-Dichloroethane-d4	102	70-130
Toluene-d8	102	70-130
4-Bromofluorobenzene	97	70-130



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and International laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.O.T. Hotline (800) 467-4022.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

CHAIN-OF-CUSTODY RECORD

Page 1 of 2

Contact Person Christopher Sharpe
Company ARCADIS Email csharpe@arcadis-us
Address 6 Terry Dr. Suite 300 City Newton State PA Zip 18940
Phone 267-685-1800 Fax 267-685-1801
Collected by: (Signature) Aligail Faulkner

Project Info:
P.O. #
Project # NP597.6 AHBally
Project Name Bally

Turn Around Time:

☐ Normal
☐ Rush

Can Use Date
Pressurized by
Date 9/2/06
Pressurization Gas
No. 1

Lab ID	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Receipt	Final
01A	AA - West	33745	8/28/06	2125	modified TO-15				
01B	AA - East	22500	8/28/06	2010	modified TO-15	-30"	-4.5"		
02A	IA-A-1	13830	8/28/06	2100		-30"	-5.0"		
02B	IA-A-2	3542	8/28/06	2210		-30"	-6.5"		
03A	IA-A-4	33987	8/28/06	2000		-30"	-5.5"		
03B	IA-A-6	R5	8/28/06	1830		-30"	-5.0"		
04A	IA-A-5	33938	8/28/06	1830		-30"	-5.0"		
05A	SS-A-1	13671	8/30/06	1222		-30"	-1.5"		
05B	SS-A-2	31133	8/30/06	1028		-30"	-2"		
06A	SS-A-3	31121	8/30/06	1635					

Relinquished by: (signature) Date/Time
Aligail Faulkner 8/31/06 1030

Received by: (signature) Date/Time

Notes:

Relinquished by: (signature) Date/Time

Received by: (signature) Date/Time

Relinquished by: (signature) Date/Time

Received by: (signature) Date/Time

Shipper Name	Shipper ID	Temp (C)	Condition	Customer Seals Intact	Work Order #
FedEx	7921 96158133	NA	Good	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> None	06090296



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and international laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.O.T. Hotline (800) 467-4822.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

CHAIN-OF-CUSTODY RECORD

Page 2 of 2

Contact Person Christopher Sharpe
Company ARCADIS Email CSHARPE@arcadis-us.com
Address 6 Terry Dr. Suite 300 City Newtown State PA Zip 18940
Phone 267-685-1800 Fax 267-685-1801
Collected by: (Signature) Alison S. Kullner

Project Info:	Turn Around Time:	Canister Gas Pressurized by <u>B</u> Date <u>9/2/06</u> Pressurization Gas <u>N₂</u> He
P.O. #	<input type="checkbox"/> Normal <input type="checkbox"/> Rush specify	
Project # <u>NP597.6 AH Bally</u>		
Project Name <u>Bally</u>		

Lab I.D.	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Receipt	Final
<u>11</u>	<u>SS-A-4</u>	<u>24446</u>	<u>8/29/06</u>	<u>1100</u>	<u>Modified TO-15</u> ↓	<u>-30"</u>	<u>-2"</u>	<u>15.14</u>	<u>5.46</u>
<u>12</u>	<u>SS-A-5</u>	<u>4064</u>	<u>8/29/06</u>	<u>1326</u>		<u>-30"</u>	<u>-1"</u>	<u>15.14</u>	<u>1.0</u>
<u>13</u>	<u>SS-A-6</u>	<u>10381</u>	<u>8/29/06</u>	<u>1620</u>		<u>-30"</u>	<u>-7"</u>	<u>1.0</u>	<u>1.0</u>
<u>14</u>	<u>IA-A-1 (dup)</u>	<u>95671</u>	<u>8/28/06</u>	<u>2100</u>		<u>-30"</u>	<u>-5.0"</u>	<u>1.0</u>	<u>1.0</u>
<u>15</u>	<u>SS-A-1 (dup)</u>	<u>1577</u>	<u>8/30/06</u>	<u>1222</u>		<u>-30"</u>	<u>-1.0"</u>	<u>0.0</u>	<u>1.0</u>

Relinquished by: (signature) <u>Alison S. Kullner</u> Date/Time <u>8/3/06 1030</u>	Received by: (signature) _____ Date/Time _____	Notes: <u>Tommy Zadal ATC 9/1/06 855</u>
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	

Shipper Name <u>FedEx</u>	Air Bill # <u>LNA</u>	Temp (C) <u>Good</u>	Condition <u>Good</u>	Customer Seals Intact <u>Yes</u> No None	Work Order # <u>06080298</u>
---------------------------	-----------------------	----------------------	-----------------------	--	------------------------------



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and international laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.O.T. Hotline (800) 467-4822.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

CHAIN-OF-CUSTODY RECORD

Page 1 of 2

Contact Person Christopher Sharpe
Company ARCADIS Email csharpe@arcadis-us.com
Address 6 Terry Dr. Suite 300 City Newton State PA Zip 15740
Phone 267-685-1800 Fax 267-685-1801
Collected by: (signature) Aligail Faulstich

Project Info:		Turn Around Time: <input type="checkbox"/> Normal <input type="checkbox"/> Rush specify _____
P.O. # _____		
Project # <u>NP597.6 At/Bally</u>		
Project Name <u>Bally</u>		

Lab ID	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Drop	Rate
AA-1	AA- West West	33745	8/28/06	2125	Modified TO-15				
AA-2	AA- East East	22500	8/28/06	2010	Modified TO-15	-30"	-4.5"		
IA-A-1	IA-A-1	13670	8/28/06	2100		-30"	-5.0"		
IA-A-2	IA-A-2	33812	8/28/06	2210		-30"	-6.5"		
IA-A-4	IA-A-4	33817	8/28/06	2000		-30"	-5.5"		
IA-A-6	IA-A-6	15	8/28/06	1830 2030		-30"	-5.0"		
IA-A-5	IA-A-5	33938	8/28/06	1830		-30"	-5.0"		
SS-A-1	SS-A-1	13671	8/30/06	1222		-30"	-1.5"		
SS-A-2	SS-A-2	31133	8/30/06	1028		-30"	-2"		
SS-A-3	SS-A-3	33821	8/30/06	1135	✓				

Relinquished by: (signature) <u>Aligail Faulstich</u> Date/Time <u>8/31/06 1030</u>	Received by: (signature) _____ Date/Time _____	Notes:
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) <u>Tony B...</u> Date/Time <u>9/1/06 855</u>	

Ship Via <u>FedEx</u>	Tracking # <u>7921 96158133</u>	Temp <u>NA</u>	Condition <u>Good</u>	Customer Seal/Label <u>Yes</u>	Work Order # <u>06090298</u>
-----------------------	---------------------------------	----------------	-----------------------	--------------------------------	------------------------------



Sample Transportation Notice

Relinquishing signature on this document indicates that sample is being shipped in compliance with all applicable local, State, Federal, national, and international laws, regulations and ordinances of any kind. Air Toxics Limited assumes no liability with respect to the collection, handling or shipping of these samples. Relinquishing signature also indicates agreement to hold harmless, defend, and indemnify Air Toxics Limited against any claim, demand, or action, of any kind, related to the collection, handling, or shipping of samples. D.O.T. Hotline (800) 467-4922.

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630-4719
(916) 985-1000 FAX (916) 985-1020

CHAIN-OF-CUSTODY RECORD

Page 2 of 2

Contact Person Christopher Sharpe
Company ARCADIS Email CSharpe@arcadis-us.com
Address 6 Terry Dr. Suite 300 City Newtown State PA Zip 18740
Phone 267-685-1800 Fax 267-685-1801
Collected by: (Signature) Miguel Sanchez

Project Info:		Turn Around Time:
P.O. #	<input type="checkbox"/> Normal	Date: _____ Pressure/Vacuum: _____ Initials: _____
Project # <u>NP597.6 AH/Bally</u>	<input type="checkbox"/> Rush	
Project Name <u>Bally</u>		specify: _____

Date/ID	Field Sample I.D. (Location)	Can#	Date	Time	Analyses Requested	Canister Pressure/Vacuum			
						Initial	Final	Pressure	Vacuum
8/29/06	SS-A-4	24486	8/29/06	1100	Modified TO-15 ↓ ↓ ↓ ↓	-30"	-2"		
8/29/06	SS-A-5	4069	8/29/06	1326		-30"	-1"	15.1"	5.1"
8/29/06	SS-A-6	10381	8/29/06	1620		-30"	-7"		
8/29/06	IA-A-1 (dup)	9567	8/29/06	2100		-30"	-5.0"		
8/30/06	SS-A-1 (dup)	1577	8/30/06	1222		-30"	-1.0"	10.0"	0.0"

Relinquished by: (signature) <u>Miguel Sanchez</u> Date/Time <u>8/31/06 1030</u>	Received by: (signature) _____ Date/Time _____	Notes:
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) _____ Date/Time _____	
Relinquished by: (signature) _____ Date/Time _____	Received by: (signature) <u>Tony Zadal</u> Date/Time <u>ATL 9/1/06 855</u>	

Shipper Name: <u>FedEx</u>	Service: <u>NA</u>	Condition: <u>Good</u>	Container: <u>06090296</u>
----------------------------	--------------------	------------------------	----------------------------



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

WORK ORDER #: 0609029C

Work Order Summary

CLIENT: Ms. Diane Wisbeck
Arcadis G&M, Inc.
1114 Benfield Blvd., Suite A
Millersville, MD 21108

BILL TO: Mr. Christopher Sharpe
Arcadis G&M, Inc.
6 Terry Dr., Suite 300
Newtown, PA 18940

PHONE: 410-987-0032

P.O. #

FAX: 410-987-4392

PROJECT # NP597.6 AH Bally Bally

DATE RECEIVED: 09/01/2006

CONTACT: Kelly Buettner

DATE COMPLETED: 08/21/2006

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT VAC./PRES.</u>
08A	SS-A-1	Modified TO-15	1.0 "Hg
12A	SS-A-5	Modified TO-15	1.5 "Hg
12AA	SS-A-5 Duplicate	Modified TO-15	1.5 "Hg
15A	SS-A-1 (dup)	Modified TO-15	0.0 "Hg
16A	Lab Blank	Modified TO-15	NA
17A	CCV	Modified TO-15	NA
18A	LCS	Modified TO-15	NA

CERTIFIED BY:

Sandra D. Fumara

Laboratory Director

DATE: 09/15/06

Certification numbers: CA NELAP - 02110CA, LA NELAP/LELAP- AI 30763, NJ NELAP - CA004
NY NELAP - 11291, UT NELAP - 9166389892

Name of Accrediting Agency: NELAP/Florida Department of Health, Scope of Application: Clean Air Act,

Accreditation number: E87680, Effective date: 07/01/06, Expiration date: 06/30/07

Air Toxics Ltd. certifies that the test results contained in this report meet all requirements of the NELAC standards

This report shall not be reproduced, except in full, without the written approval of Air Toxics Ltd.

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA - 95630
(916) 985-1000 . (800) 985-5955 . FAX (916) 985-1020



LABORATORY NARRATIVE
Modified TO-15
Arcadis Geraghty & Miller
Workorder# 0609029C

Three 6 Liter Summa Canister (100% Certified) samples were received on September 01, 2006. The laboratory performed analysis via modified EPA Method TO-15 using GC/MS in the full scan mode. The method involves concentrating up to 0.2 liters of air. The concentrated aliquot is then flash vaporized and swept through a water management system to remove water vapor. Following dehumidification, the sample passes directly into the GC/MS for analysis.

Method modifications taken to run these samples are summarized in the below table. Specific project requirements may over-ride the ATL modifications.

<i>Requirement</i>	<i>TO-15</i>	<i>ATL Modifications</i>
Daily CCV	+/- 30% Difference	<= 30% Difference with two allowed out up to <=40%; flag and narrate outliers
Sample collection media	Summa canister	ATL recommends use of summa canisters to insure data defensibility, but will report results from Tedlar bags at client request
Method Detection Limit	Follow 40CFR Pt.136 App. B	The MDL met all relevant requirements in Method TO-15 (statistical MDL less than the LOQ). The concentration of the spiked replicate may have exceeded 10X the calculated MDL in some cases

Receiving Notes

There were no receiving discrepancies.

Analytical Notes

Definition of Data Qualifying Flags

Eight qualifiers may have been used on the data analysis sheets and indicates as follows:

B - Compound present in laboratory blank greater than reporting limit (background subtraction not performed).

J - Estimated value.

E - Exceeds instrument calibration range.

S - Saturated peak.

Q - Exceeds quality control limits.

U - Compound analyzed for but not detected above the reporting limit.

UJ- Non-detected compound associated with low bias in the CCV

N - The identification is based on presumptive evidence.

File extensions may have been used on the data analysis sheets and indicates as follows:

a-File was requantified



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

b-File was quantified by a second column and detector

r1-File was requantified for the purpose of reissue



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Summary of Detected Compounds MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

Client Sample ID: SS-A-1

Lab ID#: 0609029C-08A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
cis-1,2-Dichloroethene	8.7	12	34	49
1,1,1-Trichloroethane	8.7	13	47	69
Trichloroethene	8.7	2700	47	14000

Client Sample ID: SS-A-5

Lab ID#: 0609029C-12A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	56	20000	220	79000
1,1,1-Trichloroethane	56	9500	310	52000
Trichloroethene	56	8800	300	47000

Client Sample ID: SS-A-5 Duplicate

Lab ID#: 0609029C-12AA

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
1,1-Dichloroethene	140	18000	560	72000
1,1,1-Trichloroethane	140	8500	770	46000
Trichloroethene	140	7900	760	42000

Client Sample ID: SS-A-1 (dup)

Lab ID#: 0609029C-15A

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
cis-1,2-Dichloroethene	6.7	7.3	26	29
1,1,1-Trichloroethane	6.7	10	36	54
Trichloroethene	6.7	1700	36	9300



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-1

Lab ID#: 0609029C-08A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	f091118	Date of Collection:	8/30/06
Dil. Factor:	17.4	Date of Analysis:	9/11/06 11:51 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	8.7	Not Detected	22	Not Detected
1,1-Dichloroethene	8.7	Not Detected	34	Not Detected
1,1-Dichloroethane	8.7	Not Detected	35	Not Detected
cis-1,2-Dichloroethene	8.7	12	34	49
1,1,1-Trichloroethane	8.7	13	47	69
Trichloroethene	8.7	2700	47	14000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	91	70-130
1,2-Dichloroethane-d4	114	70-130
4-Bromofluorobenzene	97	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-5

Lab ID#: 0609029C-12A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name: f091120 Date of Collection: 8/29/06
Dil. Factor: 113 Date of Analysis: 9/12/06 01:42 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	56	Not Detected	140	Not Detected
1,1-Dichloroethene	56	20000	220	79000
1,1-Dichloroethane	56	Not Detected	230	Not Detected
cis-1,2-Dichloroethene	56	Not Detected	220	Not Detected
1,1,1-Trichloroethane	56	9500	310	52000
Trichloroethene	56	8800	300	47000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	90	70-130
1,2-Dichloroethane-d4	116	70-130
4-Bromofluorobenzene	99	70-130



AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-5 Duplicate

Lab ID#: 0609029C-12AA

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name: f091119 Date of Collection: 8/29/06
Dil. Factor: 282 Date of Analysis: 9/12/06 12:39 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	140	Not Detected	360	Not Detected
1,1-Dichloroethene	140	18000	560	72000
1,1-Dichloroethane	140	Not Detected	570	Not Detected
cis-1,2-Dichloroethene	140	Not Detected	560	Not Detected
1,1,1-Trichloroethane	140	8500	770	46000
Trichloroethene	140	7900	760	42000

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	96	70-130
1,2-Dichloroethane-d4	111	70-130
4-Bromofluorobenzene	95	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: SS-A-1 (dup)

Lab ID#: 0609029C-15A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	f091121	Date of Collection:	8/30/06
Dil. Factor:	13.4	Date of Analysis:	9/12/06 02:29 AM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	6.7	Not Detected	17	Not Detected
1,1-Dichloroethene	6.7	Not Detected	26	Not Detected
1,1-Dichloroethane	6.7	Not Detected	27	Not Detected
cis-1,2-Dichloroethene	6.7	7.3	26	29
1,1,1-Trichloroethane	6.7	10	36	54
Trichloroethene	6.7	1700	36	9300

Container Type: 6 Liter Summa Canister (100% Certified)

Surrogates	%Recovery	Method Limits
Toluene-d8	92	70-130
1,2-Dichloroethane-d4	118	70-130
4-Bromofluorobenzene	98	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: Lab Blank

Lab ID#: 0609029C-16A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	f091108	Date of Collection:	NA
Dil. Factor:	1.00	Date of Analysis:	9/11/06 02:36 PM

Compound	Rpt. Limit (ppbv)	Amount (ppbv)	Rpt. Limit (uG/m3)	Amount (uG/m3)
Vinyl Chloride	0.50	Not Detected	1.3	Not Detected
1,1-Dichloroethene	0.50	Not Detected	2.0	Not Detected
1,1-Dichloroethane	0.50	Not Detected	2.0	Not Detected
cis-1,2-Dichloroethene	0.50	Not Detected	2.0	Not Detected
1,1,1-Trichloroethane	0.50	Not Detected	2.7	Not Detected
Trichloroethene	0.50	Not Detected	2.7	Not Detected

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	91	70-130
1,2-Dichloroethane-d4	110	70-130
4-Bromofluorobenzene	100	70-130



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

Client Sample ID: LCS

Lab ID#: 0609029C-18A

MODIFIED EPA METHOD TO-15 GC/MS FULL SCAN

File Name:	f091103	Date of Collection: NA
Dil. Factor:	1.00	Date of Analysis: 9/11/06 11:04 AM

Compound	%Recovery
Vinyl Chloride	76
1,1-Dichloroethene	84
1,1-Dichloroethane	85
cis-1,2-Dichloroethene	90
1,1,1-Trichloroethane	97
Trichloroethene	97

Container Type: NA - Not Applicable

Surrogates	%Recovery	Method Limits
Toluene-d8	97	70-130
1,2-Dichloroethane-d4	105	70-130
4-Bromofluorobenzene	97	70-130

ARCADIS

Appendix D

Data Validation Reports

Data Validation Checklist for 0602635

Project Name: Bally, PA
 Project Number: NP000597.00006.0006
 Sample Date(s): 2/28/06
 Sample Team: Philadelphia Field Team
 Matrix/Number of: Air / 10
 Samples: Air/ 11 Duplicates/ 1
 samples Trip Blanks / 0
 Field Blanks/ 0
 Analyzing: Air Toxics
 Laboratory: 180 Blue Ravine Road Suite B
 Folsom, CA 95630
 Phone: (916) 985-1000
 Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15

ARCADIS, Inc.
 6 Terry Drive, Suite 300
 Newton, PA
 18940
 Tel: 267-685-1800
 Fax: 267-685-1801

Laboratory Report Job Number: 0602635 Dated: 3/9/06

1. ANALYTICAL DATA PACKAGE DOCUMENTATION

1.1 GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		X		X	
2. Parameters analyzed		X		X	
3. Method of analysis		X		X	
4. Sample collection date		X		X	
5. Laboratory sample received date		X		X	
6. Sample preparation/extraction date					X
7. Sample analysis date		X		X	
8. Copy of chain-of-custody form signed by lab sample custodian		X		X	
9. Narrative summary of QA or sample problems provided		X		X	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

1.2 ORGANIC ANALYSES (VOCs)

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison		x		x	
VOCs - volatile organic compounds					
%R - percent recovery					
%D - percent difference					
%RSD - percent relative standard deviation					
RRF - relative response factor					
RPD - relative percent difference					

Comments:

14. Sample BAL-IAQ-03B-022406 was replicated in the field and labeled BAL-IAQ-3B-DUP-022406. The replicated data was acceptable.

2. SUMMARY AND DATA QUALIFIER CODES

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



VALIDATION REVIEWED BY
SIGNATURE:



Data Validation Checklist for 0602660A

Project Name: Bally, PA
 Project Number: NP000597.00006.0006
 Sample Date(s): 2/28/06
 Sample Team: Philadelphia Field Team
 Matrix/Number of Samples: Air / 2
 Duplicates / 0
 Trip Blanks / 0
 Field Blanks/0
 Analyzing Laboratory: Air Toxics
 180 Blue Ravine Road Suite B
 Folsom, CA 95630
 Phone: (916) 985-1000
 Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15

Laboratory Report Job Number: 0602660A Dated: 3/17/06

1. ANALYTICAL DATA PACKAGE DOCUMENTATION

1.1 GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		x		x	
2. Parameters analyzed		x		x	
3. Method of analysis		x		x	
4. Sample collection date		x		x	
5. Laboratory sample received date		x		x	
6. Sample preparation/extraction date					x
7. Sample analysis date		x		x	
8. Copy of chain-of-custody form signed by lab sample custodian		x		x	
9. Narrative summary of QA or sample problems provided		x		x	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

1.2 ORGANIC ANALYSES (VOCs)

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison					x
VOCs - volatile organic compounds	%D - percent difference		RRF - relative response factor		
%R - percent recovery	%RSD - percent relative standard deviation		RPD - relative percent difference		

Comments:


Performance was acceptable without exception.

2. SUMMARY AND DATA QUALIFIER CODES

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



VALIDATION REVIEWED BY
SIGNATURE:



Data Validation Checklist for 0602660B

Project Name: Bally, PA
 Project Number: NP000597.00006.0006
 Sample Date(s): 2/28/06
 Sample Team: Philadelphia Field Team
 Matrix/Number of: Air / 1
 Samples: Air/ 1 Duplicates/ 0
 samples Trip Blanks / 0
 Field Blanks/0
 Air Toxics
 Analyzing 180 Blue Ravine Road Suite B
 Laboratory: Folsom, CA 95630
 Phone: (916) 985-1000
 Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15

Laboratory Report Job Number: 0602660B Dated: 3/13/06

1. ANALYTICAL DATA PACKAGE DOCUMENTATION

1.1 GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		x		x	
2. Parameters analyzed		x		x	
3. Method of analysis		x		x	
4. Sample collection date		x		x	
5. Laboratory sample received date		x		x	
6. Sample preparation/extraction date					x
7. Sample analysis date		x		x	
8. Copy of chain-of-custody form signed by lab sample custodian		x		x	
9. Narrative summary of QA or sample problems provided		x		x	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

1.2 ORGANIC ANALYSES (VOCs)

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison					x
VOCs - volatile organic compounds		%D - percent difference		RRF - relative response factor	
%R - percent recovery		%RSD - percent relative standard deviation		RPD - relative percent difference	

Comments:


Performance was acceptable without exception.

2. SUMMARY AND DATA QUALIFIER CODES

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



VALIDATION REVIEWED BY
SIGNATURE:



Data Validation Checklist for 0603026

Project Name: Bally, PA
Project Number: NP000597.00006.0006
Sample Date(s): 2/28/06
Sample Team: Philadelphia Field Team
Matrix/Number of Samples: Air / 3
Duplicates/ 1
Trip Blanks / 0
Field Blanks/ 0
Analyzing Laboratory: Air Toxics
180 Blue Ravine Road Suite B
Folsom, CA 95630
Phone: (916) 985-1000
Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15

ARCADIS, Inc.
6 Terry Drive, Suite 300
Newton, PA
18940
Tel: 267-685-1800
Fax: 267-685-1801

Laboratory Report Job Number: 0603026 Dated: 3/14/06

1. ANALYTICAL DATA PACKAGE DOCUMENTATION

1.1 GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		x		x	
2. Parameters analyzed		x		x	
3. Method of analysis		x		x	
4. Sample collection date		x		x	
5. Laboratory sample received date		x		x	
6. Sample preparation/extraction date					x
7. Sample analysis date		x		x	
8. Copy of chain-of-custody form signed by lab sample custodian		x		x	
9. Narrative summary of QA or sample problems provided		x		x	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

1.2 ORGANIC ANALYSES (VOCs)

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison		x		x	
VOCs - volatile organic compounds		%D - percent difference		RRF - relative response factor	
%R - percent recovery		%RSD - percent relative standard deviation		RPD - relative percent difference	

Comments:


14. Sample BAL-SV-05-022806 was replicated in the field and labeled BAL-SV-50-022806. The replicated data was acceptable.

2. SUMMARY AND DATA QUALIFIER CODES

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



VALIDATION REVIEWED BY
SIGNATURE:



Data Validation Checklist for 0603058A

Project Name: Bally, PA
Project Number: NP000597.00006.0006
Sample Date(s): 3/1/06
Sample Team: Philadelphia Field Team
Matrix/Number of: Air / 1
Samples: Air/ 1 Duplicates/ 0
samples Trip Blanks / 0
Field Blanks/0
Air Toxics
Analyzing 180 Blue Ravine Road Suite B
Laboratory: Folsom, CA 95630
Phone: (916) 985-1000
Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15

ARCADIS, Inc.
6 Terry Drive, Suite 300
Newton, PA
18940
Tel: 267-685-1800
Fax: 267-685-1801

Laboratory Report Job Number: 0603058A Dated: 3/15/06

1. ANALYTICAL DATA PACKAGE DOCUMENTATION

1.1 GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		x		x	
2. Parameters analyzed		x		x	
3. Method of analysis		x		x	
4. Sample collection date		x		x	
5. Laboratory sample received date		x		x	
6. Sample preparation/extraction date					x
7. Sample analysis date		x		x	
8. Copy of chain-of-custody form signed by lab sample custodian		x		x	
9. Narrative summary of QA or sample problems provided		x		x	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

1.2 ORGANIC ANALYSES (VOCs)

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison					x
VOCs - volatile organic compounds					
%R - percent recovery					
%D - percent difference					
%RSD - percent relative standard deviation					
RRF - relative response factor					
RPD - relative percent difference					

Comments:


Performance was acceptable without exception.

2. SUMMARY AND DATA QUALIFIER CODES

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



VALIDATION REVIEWED BY
SIGNATURE:



Data Validation Checklist for 0603058B

Project Name: Bally, PA
 Project Number: NP000597.00006.0006
 Sample Date(s): 3/1/06
 Sample Team: Philadelphia Field Team
 Matrix/Number of: Air / 1
 Samples: Air/ 1 Duplicates/ 0
 samples Trip Blanks / 0
 Field Blanks/0
 Analyzing: Air Toxics
 Laboratory: 180 Blue Ravine Road Suite B
 Folsom, CA 95630
 Phone: (916) 985-1000
 Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15

ARCADIS, Inc.
 6 Terry Drive, Suite 300
 Newton, PA
 18940
 Tel: 267-685-1800
 Fax: 267-685-1801

Laboratory Report Job Number: 0603058B Dated: 3/15/06

1. ANALYTICAL DATA PACKAGE DOCUMENTATION

1.1 GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		x		x	
2. Parameters analyzed		x		x	
3. Method of analysis		x		x	
4. Sample collection date		x		x	
5. Laboratory sample received date		x		x	
6. Sample preparation/extraction date					x
7. Sample analysis date		x		x	
8. Copy of chain-of-custody form signed by lab sample custodian		x		x	
9. Narrative summary of QA or sample problems provided		x		x	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

1.2 ORGANIC ANALYSES (VOCs)

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison					x
VOCs - volatile organic compounds	%D - percent difference		RRF - relative response factor		
%R - percent recovery	%RSD - percent relative standard deviation		RPD - relative percent difference		

Comments:


Performance was acceptable without exception.

2. SUMMARY AND DATA QUALIFIER CODES

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



VALIDATION REVIEWED BY
SIGNATURE:



DATA VALIDATION CHECKLIST

Project Name: Bally, PA
Project Number: NP000597.00006.0006
Sample Date(s): 8/28/06 through 8/30/06
Sample Team: Abigail Faulkner
Matrix/Number of: Air / 4
Samples: Air/ 4 Duplicates/ 0
samples Trip Blanks / 0
Field Blanks/ 0
Air Toxics
Analyzing 180 Blue Ravine Road Suite B
Laboratory: Folsom, CA 95630
Phone: (916) 985-1000
Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15 SIM

ARCADIS, Inc.
6 Terry Drive, Suite 300
Newton, PA
18940
Tel: 267-685-1800
Fax: 267-685-1801

Laboratory Report Job Number: 0609029B Dated: 9/15/06

ANALYTICAL DATA PACKAGE DOCUMENTATION GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		X		X	
2. Parameters analyzed		X		X	
3. Method of analysis		X		X	
4. Sample collection date		X		X	
5. Laboratory sample received date		X		X	
6. Sample preparation/extraction date					X
7. Sample analysis date		X		X	
8. Copy of chain-of-custody form signed by lab sample custodian		X		X	
9. Narrative summary of QA or sample problems provided		X		X	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

9. Sample IA-A-1 (dup) was cancelled due to sample arrival at lab at ambient pressure.

Pages

1/3

AR100989

ORGANIC ANALYSES

VOCs

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x	x		
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison					x
<hr/>					
VOCs - volatile organic compounds	%D - percent difference		RRF - relative response factor		
%R - percent recovery	%RSD - percent relative standard deviation		RPD - relative percent difference		

Comments:


11. The surrogate recoveries for 1,2-dichloroethane-d4 was outside of control limits in samples SS-A-2 and SS-A-6. However, all other blanks and spike recovery were within control limits. Therefore no qualification is required.

**DATA VALIDATION CHECKLIST
SUMMARY AND DATA QUALIFIER CODES**

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:

A handwritten signature in black ink, appearing to read "J. M. Ford", is written over a horizontal line.

DATA VALIDATION CHECKLIST

Project Name: Bally, PA
Project Number: NP000597.00006.0006
Sample Date(s): 8/28/06 through 8/30/06
Sample Team: Abigail Faulkner
Matrix/Number of: Air / 3
Samples: Air/3 Duplicates/ 1
samples Trip Blanks / 0
Field Blanks/ 0
Air Toxics
Analyzing 180 Blue Ravine Road Suite B
Laboratory: Folsom, CA 95630
Phone: (916) 985-1000
Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15 SIM

ARCADIS, Inc.
6 Terry Drive, Suite 300
Newton, PA
18940
Tel: 267-685-1800
Fax: 267-685-1801

Laboratory Report Job Number: 0609029C Dated: 9/15/06

ANALYTICAL DATA PACKAGE DOCUMENTATION GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		X		X	
2. Parameters analyzed		X		X	
3. Method of analysis		X		X	
4. Sample collection date		X		X	
5. Laboratory sample received date		X		X	
6. Sample preparation/extraction date					X
7. Sample analysis date		X		X	
8. Copy of chain-of-custody form signed by lab sample custodian		X		X	
9. Narrative summary of QA or sample problems provided		X		X	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

9. Sample IA-A-1 (dup) was cancelled due to sample arrival at lab at ambient pressure.

ORGANIC ANALYSES

VOCs

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		X		X	
2. Blanks					
A. Method blank		X		X	
B. Field blanks					X
C. Trip blanks					X
3. GC/MS Instrument performance check		X		X	
4. Initial calibration RRF's and %RSD's		X		X	
5. Continuing calibration RRF's and %D's		X		X	
6. Matrix spike (MS) %R					X
7. Matrix spike duplicate (MSD) %R					X
8. MS/MSD precision (RPD)					X
9. Laboratory control sample (LCS) %R & RPD		X		X	
10. Laboratory duplicate precision					X
11. Surrogate spike recoveries		X		X	
12. Internal standard retention times and areas		X		X	
13. Compound identification and quantitation		X		X	
14. Field duplicate comparison		X		X	
VOCs - volatile organic compounds %D - percent difference RRF - relative response factor %R - percent recovery %RSD - percent relative standard deviation RPD - relative percent difference					

Comments:


14. Sample SS-A-1 was replicated in the field and labeled SS-A-1 (dup). The replicated data was acceptable.

**DATA VALIDATION CHECKLIST
SUMMARY AND DATA QUALIFIER CODES**

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:

A handwritten signature in dark ink, appearing to read "D. J. [unclear]", is written over a horizontal line.

DATA VALIDATION CHECKLIST

Project Name: Bally, PA
Project Number: NP000597.00006.0006
Sample Date(s): 10/12/06
Sample Team: Chris Sharpe
Matrix/Number of Samples: Air / 2

ARCADIS, Inc.
6 Terry Drive, Suite 300
Newton, PA
18940
Tel: 267-685-1800
Fax: 267-685-1801

Analyzing: Air Toxics
Laboratory: 180 Blue Ravine Road Suite B
Folsom, CA 95630
Phone: (916) 985-1000
Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15 SIM

Laboratory Report Job Number: 0610306

Dated: 10/24/06

ANALYTICAL DATA PACKAGE DOCUMENTATION GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		X		X	
2. Parameters analyzed		X		X	
3. Method of analysis		X		X	
4. Sample collection date		X		X	
5. Laboratory sample received date		X		X	
6. Sample preparation/extraction date					X
7. Sample analysis date		X		X	
8. Copy of chain-of-custody form signed by lab sample custodian		X		X	
9. Narrative summary of QA or sample problems provided		X		X	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

ORGANIC ANALYSES

VOCs

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		x		x	
2. Blanks					
A. Method blank		x		x	
B. Field blanks					x
C. Trip blanks					x
3. GC/MS Instrument performance check		x		x	
4. Initial calibration RRF's and %RSD's		x		x	
5. Continuing calibration RRF's and %D's		x		x	
6. Matrix spike (MS) %R					x
7. Matrix spike duplicate (MSD) %R					x
8. MS/MSD precision (RPD)					x
9. Laboratory control sample (LCS) %R & RPD		x		x	
10. Laboratory duplicate precision					x
11. Surrogate spike recoveries		x		x	
12. Internal standard retention times and areas		x		x	
13. Compound identification and quantitation		x		x	
14. Field duplicate comparison					x

VOCs - volatile organic compounds %D - percent difference RRF - relative response factor
 %R - percent recovery %RSD - percent relative standard deviation RPD - relative percent difference

Comments:

Performance was acceptable without exception.

1) Information on Canister did not match sample information on COC. Information on canister was identified by ARCADIS as the correct data.

**DATA VALIDATION CHECKLIST
SUMMARY AND DATA QUALIFIER CODES**

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:



DATA VALIDATION CHECKLIST

Project Name: Bally, PA
Project Number: NP000597.00006.0006
Sample Date(s): 8/28/06 through 8/30/06
Sample Team: Abigail Faulkner
Matrix/Number of: Air / 8
Samples: Air/ 8 Duplicates/ 1
samples Trip Blanks / 0
Field Blanks/ 0
Air Toxics
Analyzing 180 Blue Ravine Road Suite B
Laboratory: Folsom, CA 95630
Phone: (916) 985-1000
Analyses: Volatile organic compounds (VOCs) by USEPA method TO-15 SIM

ARCADIS, Inc.
6 Terry Drive, Suite 300
Newton, PA
18940
Tel: 267-685-1800
Fax: 267-685-1801

Laboratory Report Job Number: 0609029A Dated: 9/21/06

ANALYTICAL DATA PACKAGE DOCUMENTATION GENERAL INFORMATION

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Sample results		X		X	
2. Parameters analyzed		X		X	
3. Method of analysis		X		X	
4. Sample collection date		X		X	
5. Laboratory sample received date		X		X	
6. Sample preparation/extraction date					X
7. Sample analysis date		X		X	
8. Copy of chain-of-custody form signed by lab sample custodian		X		X	
9. Narrative summary of QA or sample problems provided		X		X	

QA - quality assurance

Comments:

Field data, field notes, and sampling logs were not reviewed. An Arcadis Level IV validation was conducted on the data. Analytical data were validated in accordance with "USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review" (October 1999), the "USEPA CLP National Functional Guidelines for Inorganic Data Review", July 2002, and ARCADIS professional judgment.

9. Sample IA-A-1 (dup) was cancelled due to sample arrival at lab at ambient pressure.

ORGANIC ANALYSES

VOCs

	Reported		Performance Acceptable		Not Required
	No	Yes	No	Yes	
1. Holding times		X		X	
2. Blanks					
A. Method blank		X		X	
B. Field blanks					X
C. Trip blanks					X
3. GC/MS Instrument performance check		X		X	
4. Initial calibration RRF's and %RSD's		X		X	
5. Continuing calibration RRF's and %D's		X		X	
6. Matrix spike (MS) %R					X
7. Matrix spike duplicate (MSD) %R					X
8. MS/MSD precision (RPD)					X
9. Laboratory control sample (LCS) %R & RPD		X		X	
10. Laboratory duplicate precision					X
11. Surrogate spike recoveries		X		X	
12. Internal standard retention times and areas		X		X	
13. Compound identification and quantitation		X		X	
14. Field duplicate comparison					X
VOCs - volatile organic compounds	%D - percent difference		RRF - relative response factor		
%R - percent recovery	%RSD - percent relative standard deviation		RPD - relative percent difference		

Comments:


Performance was acceptable without exception.

**DATA VALIDATION CHECKLIST
SUMMARY AND DATA QUALIFIER CODES**

Job Number:

Sample ID	Analyte(s)	Qualifier	Reason(s)
VOC			
None			

VALIDATION PERFORMED BY:

A handwritten signature in black ink, written over a horizontal line. The signature is cursive and appears to read "J. J. [unclear]".

SDMS US EPA Region III
Imagery Insert Form

Site Name: Bally Groundwater

Document ID: 2095155

Some images in this document may be illegible or unavailable in SDMS. Please see reason(s) indicated below:



ILLEGIBLE due to bad source documents. Images(s) in SDMS equivalent to hard copy.

Specify Type of Document(s) / Comments:



Includes ____ COLOR or ____ RESOLUTION variations. Unless otherwise noted, these pages are available in monochrome. The source document page(s) is more legible than the images. The original document is available for viewing at the Superfund Records Center.

Specify Type of Document(s) / Comments:



RESTRICTED CONFIDENTIAL BUSINESS INFORMATION (CBI-R):
Restricted or copyrighted documents that cannot be imaged.

Specify Type of Document(s) / Comments:



UNSCANNABLE MATERIAL:

____ Oversized or ____ Format. Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS. The original document is available for viewing at the EPA Region 3 Superfund Records Center.

Specify Type of Document(s) / Comments:

CD: Facility Vapor Intrusion Eval. Summary
Appendix C



Document is available at the EPA Region 3 Superfund Records Center.

Specify Type of Document(s) / Comments:

